FINAL SUBDIVISION & LAND DEVELOPMENT PLAN
FOR
AUTUMN CHASE PRD PHASE II
LOCATED IN
UPPER ALLEN TOWNSHIP, CUMBERLAND COUNTY, PA.

Tax Parcels associated with this plan

Tax Parcel No. 42-11-0272-001
Tax Parcel No. 42-11-0274-028

INTENT OF PLAN

The intent of this plan is to obtain Final Subdivision Plat approval for "AUTUMN CHASE PHASE II". AUTUMN CHASE is a Planned Residential Development (PRD). The Tentative Planned Residential Development Plan for Autumn Chase was approved by the Upper Allen Township Board of Commissioners as per a written decision dated –May 8, 2012. The Master Plan on plan sheet 2 provides a reference to the overall community. Autumn Chase Phase II consists of 56 residential dwelling units (34 townhouses & 24 duplexes) and 1 open space lot. The project shall be implemented in accordance with the Decision Approving Application of Hertzler Road Associates, L.P. for Tentative Approval of Autumn Chase Planned Residential Development dated May 8, 2012. Certain waivers and modifications were granted as part of the Tentative Plan approval. A Developer Agreement, between Hertzler Road Associates, L.P. and Upper Allen Township, dated April 26, 2012, provides for certain Hertzler Road improvements and recreation improvements to satisfy the recreation requirements for Autumn Chase. Hertzler Road shall be improved with the project in accordance with the approved Developers Agreement. See additional note below and on the Master Development Plan, sheet 2.

SITE DATA

1. Applicant and Equitable Owner:
   Hertzler Road Associates, L.P.
   4400 Deer Path Road, Suite 201
   Harrisburg, PA 17110
   717–234–4000
2. The subject tract consists of two (2) parcels of Land; both tracts are owned by: Hertzler Road Associates, LP (including Phases I&3)
   Total Gross Area of both Parcels: 6,209,731 sf or 142.55 ac
   Total Net Area of both Parcels: 6,134,676 sf or 140.83 ac
   Tax Parcel No. 42–11–0272–001
   Instrument #201124513
   Total Gross Area: 5,378,304.8 Sq Ft = 123.47 Ac.
   Total Net Area: 5,303,249.9 Sq Ft = 121.75 Ac.
   Hertzler Road Legal R/W: 75,054.8 Sq Ft = 1.72 Ac.
   Tax Parcel No. 42–11–0274–028
   Instrument #201124513
   Total Gross/Net Area 831,426 sf or 19.087 acres
3. Subject Tract is located in the R–1 (Low Density Residential District) and RL (Rural Living)
   R–1 (Low Density Residential): 5,565,535 sf or 127.77 ac
   RL (Rural Living): 644,196 sf or 14.79 ac
4. Total number of existing dwellings: 78 lots previous Phases I & 3
5. Total number of proposed dwellings: 295 Total all Phases
   Phase II: 56 dwelling units (32 townhouses & 24 duplexes)
   Entire Project including Phase III: 295 units with the following uses (See Master Plan sheet for Phasing Plan);
   - 161 Single–family dwelling lots (78 North and 83 south of Hertzler Road);
   - 60 Duplex Units;
   - 74 Townhouse Units (7–6plexes and 8–4plexes);
6. Existing Land Use: Agriculture use
7. Proposed Use: Residential "Planned Residential Development"
8. Proposed Density: 1.2 units per acre
9. Proposed Length of New Streets:
   Phase II: 2,456' or 0.4650 miles
10. Proposed Length of Hertzler Road Widening: 3,493' total including off site (There are no Hertzler Road improvements associated with this Phase II Plan)
11. Minimum Lot Size Proposed in Phase II: 156,489 sf or 3.59 ac
12. Total Area of Open Space Lots 1 through 9 (see sheet 2):
    Existing Phases I & 3: 800,593 sf or 0.808 acres
    Phase II: 156,489 sf or 3.59 acres (OS–4)
    Entire Project: 2,851,323 sf or 65.457 ac
13. –

ZONING REQUIREMENTS

Below zoning criteria as approved with the Autumn Chase PRD

Building Setbacks
50' setback from tract perimeter apply's to all of the residential uses

Single Family Detached Lots: (none in Phase II)
Front = 25'
Side = 5'
Rear = 15'

Townhouse & Duplex Units (setback from parent tract)
Front = 25'
Side = 10'
Rear = 15'
*see below for interior yards

*Interior Yard Separations (Rear to rear, side to rear, etc. – Sec. 245–155)
Rear to rear = 40'
Side to rear = 35'
Side to side = 25'

Townhouse & Duplex
Minimum Building setback from sidewalks = 20'
Minimum Front setback from internal street R/W = 20'

Townhouse & Duplex
Minimum Building setback from off street parking = 20'

Maximum Building Height = 35'

Maximum Building Coverage = 35%

Maximum Impervious Coverage = 55%

The below waivers and deferrals as listed were granted with the February 15, 2012 tentative approval of the Autumn Chase PRD.

Section	Waiver Requirement	Date of Waiver Approval
225-15.B(5)	Cul-de-sacs to not exceed 800 feet and not serve more than 20 dwelling units.	February 15, 2012

Section	Modification Requirement	Date of Modification Approval
220-18.B	Allowed the residential block to have a length of 1,652 feet instead of the required maximum length of 1,500 feet.	February 15, 2012
220-15.B(11)(a) & 220-15.F.(2)	To and the requirements of Section 220-15 F.(2) and allow the applicant to provide widening along Hertzler Road to 24 feet with a full width 1 ½ inch depth overlay pavement along the property frontage with the condition that the applicant also widen to 24 feet and provide full width 1 ½ inch depth overlay pavement Hertzler Road from the development west to the property line of the Winding Hill PRD. A note shall be added on the plan stating that in the opinion of the Township Engineer, should field conditions indicate insufficient structural integrity in areas of existing pavement to receive overlay, those areas shall receive full depth reconstruction (Section 220-15.G(1)).	February 15, 2012
220-16.A(3)	Permit slant curbing within development instead of vertical curbing.	February 15, 2012
220-16.B.(4)	Sidewalks to be installed along one side of proposed streets (Road J'/ Brittany Circle and Lot OS-7 only) instead of both sides of the street.	February 15, 2012
220-16.B(3)	Provide a six foot wide walking trail on the south side of Hertzler Road in lieu of sidewalks. The trail shall be shown on the final plan extending from the western property boundary line with the existing Allendale PRD to the Township Greenway property to the east.	February 15, 2012
220-16.A.(2)	To permit Hertzler Road improvements in lieu of curbs, to include widening and overlay of off-ske portions of the road west approximately 650 feet toward the improvements completed by the Winding Hills PRD and east approximately 400 feet toward the intersection of Hertzler Road/ and Kinedinst Road. Improvements along the property frontage shall consist of widening of the cartway to twenty-four (24) feet and installing a 1 ½ inch wearing course overlay. A note shall be added on the plan stating that in the opinion of the Township Engineer, should field conditions indicate insufficient structural integrity in areas of existing pavement to receive overlay, those areas shall receive full depth reconstruction (Section 220-15.G(1)).	February 15, 2012

See below additional waivers requested with this Phase II Final Plan.

WAIVER SECTION	WAIVER REQUIREMENT	DATE OF WAIVER REQUEST	DATE OF WAIVER APPROVAL
220–9.C(2)(e)	Provide one foot contour interval	July 1, 2022	September 7, 2022
220–10.B(2)(b)	Provide street cross sections at 50' intervals	July 1, 2022	September 7, 2022

DRAWING INDEX

SHEET NO.	TITLE
1 of 21	COVER SHEET
2 of 21	MASTER DEVELOPMENT PLAN
3 of 21	EXISTING FEATURES PLAN
4–5 of 21	FINAL SUBDIVISION PLAN
6–7 of 21	GRADING AND UTILITY PLAN
8–9 of 21	STREET AND UTILITY PROFILES
10–12 of 21	POST CONSTRUCTION STORMWATER MANAGEMENT PLANS
13 of 21	LANDSCAPE PLAN
14 of 21	LIGHTING PLAN
15–17 of 21	CONSTRUCTION DETAILS
18–21 of 21	EROSION CONTROL PLANS

GENERAL NOTES

1. The applicant shall comply with all Township regulations in effect at the time of the filing of this plan. All proposed improvements shall conform to Upper Allen Township construction standards. All work shall be in accordance with PennDOT Publication 408, Specifications and Publication 72, Roadway Construction Standards, unless otherwise noted. Work zone traffic control shall be in accordance with PennDOT Publication 213.
2. Autumn Chase Phase II consists of 56 Single–family residential dwelling units (32 townhouses and 24 duplexes) and 1 Open Space lot.
3. The recreation requirements for Autumn Chase are being satisfied in accordance with the Developer Agreement, dated April 26, 2012, between Hertzler Road Associates, L.P. and Upper Allen Township.
4. A Homeowners Association is proposed with the development. The Home Owners Association Documents shall be reviewed by the Township in conjunction with this plan. The association shall be responsible for maintenance and upkeep of the following:
   a. All Open Space Areas except for open space areas accepted by the township for recreation land dedication (See notes on Open Space below);
   b. All on–site stormwater management facilities located outside of a public right–of–way;
   c. All sidewalk located within Open Space areas and sidewalk within the public right–of–way that abuts open space areas. Individual property owners of single family detached dwelling lots are responsible for sidewalk maintenance and snow removal of the sidewalk abutting their respective lot (there are no single–family detached dwelling lots proposed in Phase II although note provided for consistency);
   d. Boulevard Landscape islands;
   a. The landscape and boulevard islands shall be maintained by the developer until such responsibility is transferred to the homeowners association established with the development. Upper Allen Township shall not be held responsible for damage to plantings within the islands for any reason, and the municipality may remove or trim the vegetation if necessary for public safety.
5. The boundary information is based on a field survey performed by CEDG, Inc. in April 2005 & August 2008 and verified by A to Z Land Consulting Services, LLC. In May & June 2022. The horizontal datum is NAD 83. The bearing is based on state plane coordinates, Pennsylvania south zone. Site benchmark: Northeasterly corner of concrete headwall on the southerly side of Hertzler Road, approximately 300' east of railroad crossing. Elev.=445.75 (NAVD 88) Topographic information shown is based on photogrammetry mapping performed by air survey, flown April 6, 2005. The vertical datum is NAVD 1988.
6. All streets proposed with this project shall be constructed to township standards and shall be offered for dedication to the township upon completion of improvements. All proposed streets are classified as minor streets and shall be 34' wide curbed cartways (slant curb) with an associated 50' right–of–way except for the boulevard entrances which will be 20' cartways with a 10' landscaped boulevard island with an associated 66' right–of–way. Hertzler Road shall be improved along the subject tract's entire length of road frontage and certain off site areas as detailed in the Developer Agreement. The portions of Hertzler Road outside of the approximately 1,125 linear feet associated with Phase 1 (east to Kinedinst Road and west approximately 650' to the western property line of 521 Hertzler Road) will be widened to approximately 24 feet (see Hertzler Road Design Plan) and improved via a cement based full depth reclamation to include 12" of cement treated base at 5% cement, 2.5" base paving course and 1.5" wearing course as outlined in the Kleinfelder Geotechnical Engineering Report dated May 27, 2021. There are no Hertzler Road improvements nor any boulevards associated with this Phase II Plan.
7. There is an unnamed stream tributary to the Yellow Breeches Creek (CWF) that parallels Hertzler Road through the site. There is a 0.25 acre wetland pocket located along the south side of Hertzler Road towards the eastern side of the site (no wetland impacts proposed). There are no significant rock outcrops or contaminated soils known to exist on the site. There are two (2) sink holes–depressions located along the southern property line on the south side of Hertzler Road; the sinkholes are proposed to be repaired with the applicable future phase. A Water Obstruction and Encroachment Permit was obtained for the stream impacts associated with Hertzler Road improvements (Permit No. E21–468, issued on April 28, 2020.)
8. Within clear sight triangles as shown on this plan, no structure or growing material shall exceed a height of 3' above the grade of the street, and no branch of a tree, or obstruction, shall be lower than 9' feet above the grade of the street, with the exception of traffic signs, public utility poles, and similar–type structures.
9. Nothing shall be planted, placed, or set within any easement that would affect the function of the easement or conflict with the easement agreement.
10. The applicant is responsible for paying for the installation of all street and traffic control signs required for this project as deemed necessary by Upper Allen Township. All traffic control signs and devices are to be installed prior to any certificate of occupancy being issued. Street signs shall conform to PennDOT Publication 236M, dated April 1997, as amended. In addition, a separate permit is required for development signs, and all signs shall conform to all applicable requirements within Chapter 245, Article XXIII of the Codified Ordinances of Upper Allen Township or such applicable ordinances that are in effect at the time of the application for the sign.
11. The proposed water lines shown on this plan are per approved design prepared Veolia Water (public supplier).
12. A Geologic Evaluation and Infiltration Testing Report was prepared for the project by CMX, 910 Century Drive, Mechanicsburg, PA 17055; 717–458–0800. The site is partially underlain by limestone geology. Due to the geology, the site has an increased potential for sinkhole development. Because all sinkhole are unique and repair methods for each type may require a specific method for repair, it is recommended that the site contractor consult with a Geo–Technical Engineer prior to start of construction of each phase. The Geo–Technical Engineer should evaluate the site's features for vertical and horizontal extents and relation of features to the proposed improvements and then provide repair measures to the contractor for repair of each sinkhole. In addition, builders are recommended to consult with a Geo–Technical engineer for guidance pertaining to building construction in sinkhole prone areas.
13. All new utilities shall be placed under ground.
14. There is a FEMA delineated floodplain located on the property. The floodplain is located along the eastern property line where Hertzler Road and the existing unnamed stream pass under the railroad bridge. The floodplain is depicted per scan overlay of Flood Insurance Rate Map (Community–Panel Number 42041C0287E, Zone A, dated March 16, 2009). The current study is a Zone A non–detailed study area with no base flood elevation information.
15. Street lighting is proposed throughout the development as shown on this plan. Street lights are proposed at all street intersections and at other locations indicated on the plan.
16. All proposed property corners and existing unmarked property corners shall be marked with iron pins or concrete monuments prior to dedication of the streets. Concrete monuments will be set as shown, all other property corners to be marked with iron pins. All proposed marker materials and installation methods shall be in accordance with Township standards.
17. An NPDES Permit was obtained from the Cumberland County Soil Conservation District authorizing earth disturbance activities associated with the project (Permit No. PAC210094, expiration date 11–13–2023). The contractor shall implement erosion and sedimentation pollution control measures in accordance with PA State Code Chapter 102 requirements and associated NPDES Permit Conditions. Contractor must obtain a copy of the approved Erosion Control Plan and be a co–permittee on the NPDES Permit prior to start of construction. The NPDES permittee and all co–permittee shall be responsible for implementation and maintenance of erosion control measures in accordance with the approved Erosion Control Plan.
18. All lot grading shall maintain positive drainage away from the dwelling. Lot owners are required to maintain lot grading and surface drainage patterns and characteristics consistent with the approved grading plan.
19. Manhole covers for stormwater manholes shall be cast with the word "Storm" for identification purposes.
20. Any construction or work within the public street right–of–way related to storm drainage facilities requires inspection by Upper Allen Township. Provide a minimum of 48 hours notice to the Township before starting work.
21. Contractor shall schedule a pre–construction meeting with the Township Engineer at least 48 hours prior to starting site construction activities.
22. In compliance with Act 287 of 1974 as amended by Act 199 of 2004, all underground utilities shown on this plan are a compilation of actual field locations and data furnished from information supplied by others. The developer, surveyor and engineer assume no responsibility for the location of any underground utilities as depicted on this drawing. Any request for additional underground utility information should be directed to that respective utility company. See One Call table for Serial Numbers.
23. All known existing easements and rights–of–ways have been shown on the plan and all utilities have been notified per PA One Call requirements.
24. All lots shall be subject to restrictions and covenants as defined in the "Protective Covenants, Reservations and Easements". All property owners shall be provided with a copy of the covenants documents.
25. All single– family detached dwellings will have a two–vehicle garage and a driveway with additional space to equal at least three off–street parking spaces. Maximum driveway width at the street right–of–way line is 10' for a single car garage and 24' width for a 2 car garage. All driveways shall not connect with a public street within 50 feet of the right–of–way lines of any intersecting streets nor within five feet of a fire hydrant, in accordance with Section 220–17.A(3) of the Codified Ordinances of Upper Allen Township; (there are no single–family detached dwelling lots proposed in Phase II although note provided for consistency with previous plan approvals).
26. As–built Mylar plans and electronic data files shall be provided to the Township. All drawings must be signed and sealed by a professional engineer or land surveyor attesting to the correctness of the facility information shown, in accordance with Section 220–13.C(2) of the Codified Ordinances of Upper Allen Township.
27. The Home Owners Association shall maintain the grass area around the Greenway Trail and associated easement areas.
28. Should a phased final plan propose fewer trees and/or shrubs than Ordinance requirements, the additional trees required to meet Ordinance requirements should be planted in the open space areas and/or adjacent to or along the Greenway Trail as directed by the Township.

PHASE I RECORDING INFORMAITON

The Final Plat for Autumn Chase PRD Phase I was recorded on October 21, 2021 in Instrument #202135830.

PHASE III RECORDING INFORMAITON

The Final Plat for Autumn Chase PRD Phase III was recorded on September 22, 2022 in Instrument #202226446.

APPLICANT & OWNER

HERTZLER ROAD ASSOCIATES, L.P.
4400 DEER PATH ROAD, SUITE 201
HARRISBURG, PA 17110
(717) 234-4000

MELLOTT ENGINEERING, INC.
CIVIL ENGINEERING • LAND PLANNING & DESIGN • WATER RESOURCES
7500 DEVONSHIRE HEIGHTS ROAD • HUMMELSTOWN, PA 17036
mellotteng@comcast.net
(717)–566–6533

SANITARY SEWER CONSTRUCTION NOTES

1. All sanitary sewer construction materials and methods shall conform to the latest standards of Upper Allen Township, Cumberland County, Pennsylvania and shall be subject to the approval by the township's engineer. See Standard construction and material specifications for sanitary sewer system extensions, latest edition. Construction of all sanitary sewers shall conform to standards adopted by Upper Allen Township. Contractor shall obtain specifications and construction details directly from the Authority.
2. All sanitary sewers constructed in public streets shall be subject to backfill compaction testing at the discretion of the township representative and at the expense of the developer.
3. All proposed sanitary sewer mains shall be offered for dedication to Upper Allen Township. Upon completion of the sanitary sewer extension and before release of installation financial security and before acceptance of maintenance financial security, developer must prepare a separate sanitary sewer deed of dedication and easement agreement for the sanitary sewer extension for Township review, followed by recording of same by the developer.
4. Upon acceptance of any sanitary sewer mains, laterals, manholes and other appurtenances by the Township located in public streets not yet dedicated to the Township, developer grants to Township a temporary sanitary sewer easement thirty (30) feet in width measured from the centerline of the sanitary sewer main for the purpose of emergency or other repairs to the sanitary sewer system, until such time that the street and all utilities included therein are dedicated to the Township.
5. On streets having grades 2% or greater, sanitary sewer manhole frames and covers shall be adjusted using tapered rubber riser rings per standard details.
6. A 30' wide right–of–way shall be provided around all proposed sewers that are not located within a public right–of–way.
7. Contractor shall test pit all existing utility crossings prior to installing any sanitary sewer pipe to verify existing horizontal and vertical elevations to assure no conflict with new sewer.
8. When sewers are installed through Township's right–of–way, including planter islands, no house, structure, trees, shrubs, gardens, or obstruction on or over, or that will interfere with vehicular access for the construction, maintenance or operation of any sewer, shall be installed within limits of the easement, and no changes in the grade or contour over the sewer shall be permitted in accordance with the Township's standard deed of dedication.
9. Contractor shall field verify existing manhole elevations prior to construction.
10. All sanitary sewer pipe installed shall be inspected by a Upper Allen Township representative prior to backfilling.
11. A ten (10') foot minimum horizontal separation or an 18"vertical separation must be maintained wherever possible between water lines and sewer lines.

GENERAL CONSTRUCTION NOTES

1. The intent of this plan is to obtain subdivision / land development approval for the planned site development. Construction procedures have not been specified by Mellott Engineering, Inc. beyond what is required by the township and the standard methods as outlined in Pennsylvania Department of Transportation (PennDOT) Publication 408 for earth moving and installation of PennDOT structures.
2. No environmental studies, subsurface investigations or testing of soils were performed in the preparation of these plans beyond the Geologic Evaluation and Infiltration Testing Report prepared for the project by CMX. Mellott Engineering, Inc. recommends the owner and contractor consult a geotechnical engineer prior to construction to determine appropriate soil bearing capacity, fill placement procedures, compaction and building foundation requirements.
3. The project drawings are generally diagrammatic in indicating the presence of existing underground utilities. Information on existing utilities has been compiled from available information including utility company and municipal record maps and field survey and is not guaranteed correct or complete. Utilities are shown to alert the contractor to their presence and the contractor is solely responsible for determining actual locations and elevations of all utilities, including services. When the utilities are to be left in place, the contractor shall provide adequate means of support and protection during the excavation and backfilling operations.
4. Should any uncharted or incorrectly charted, existing piping or other utility be uncovered during excavation, consult the engineer immediately for directions before proceeding further with the work in this area.
5. Do not interrupt existing utilities servicing facilities occupied and used by the owner or others during occupied hours except when such interruptions have been authorized in writing by the owner, Township and applicable utility company. Interruptions shall only occur after acceptable temporary service has been provided.
6. The contractor shall restore any structure or areas disturbed during construction to their original condition or better if they are not indicated to be altered on the plans.
7. The contractor shall verify all site conditions in the field and contact the site engineer if there are any questions or conflicts regarding the construction documents and/or field conditions.
8. The contractor is responsible for ensuring all construction methods and procedures meet all regulatory requirements and developer requirements. The contractor is responsible for obtaining all necessary permits required by governmental agencies prior to construction. The contractor shall obtain all necessary permits from the municipality required to perform the work.
9. The fire hydrants shown on this plan must be reviewed by the township Fire Marshall. Fire Marshall will make the final determination of hydrant locations. Veolia Water will provide a water main design after the plan is approved by the township.

PENNSYLVANIA ONE CALL SYSTEM, INC. 1-800-242-1776 STOP–CALL BEFORE YOU DIG!

Before You Dig Anywhere

In . . . . PENNSYLVANIA

STOP! Call 1–800–242–1776 Toll Free

PA Law requires 3 working days before you excavate

PA One Call System, Inc.

One Call Serial # –

PENNSYLVANIA ACT 199 (2004) AS AMENDED REQUIRES NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN THE COMMONWEALTH.

COMPANY: PENNSYLVANIA AMERICAN WATER ADDRESS: 852 WESLEY DRIVE, MECHANICSBURG, PA. 17055 CONTACT: JERRY BONANNO

COMPANY: FRONTIER COMMUNICATIONS CTSI LLC ADDRESS: 100 CTE DR DALLAS, PA. 18612 CONTACT: DAVID MORRIS

COMPANY: ELANTIC NETWORKS INC ADDRESS: 1450 E PARHAM RD RICHMOND, VA. 23228 CONTACT: CONI DUFF EMAIL: cduff@covtel.com

COMPANY: VERIZON PENNSYLVANIA INC ADDRESS: 201 STANWIX ST 4TH FLOOR PITTSBURGH, PA. 15222 CONTACT: OFFICE PERSONNEL

COMPANY: BUCKEYE PARTNERS ADDRESS: PO BOX 368 EMMAUS, PA. 180490368 CONTACT: DONALD SAMALA

COMPANY: Veolia WATER ADDRESS: 317 NORTH MARKET STREET MECHANICSBURG, PA. 17055 CONTACT: KIM GENETTI EMAIL: Kim.Genetti@veolia-na.com

COMPANY: FIRSTENERGY CORP ADDRESS: 76 S MAIN ST AKRON, OH. 443081893 CONTACT: OFFICE PERSONNEL

COMPANY: XO COMMUNICATIONS INC ADDRESS: C/O DE–TECH INC 120 N PEARL ST CRESTLINE, OH. 44827 CONTACT: ROBERT FREED E MAIL: jessica.m.revelle@sprint.com


COMPANY: PPL ELECTRIC UTILITIES CORPORATION ADDRESS: 1801 BROOKWOOD ST HARRISBURG, PA. 171042222 CONTACT: JEANETTE ANDERSON EMAIL: janderson@pplweb.com

COMPANY: COMCAST CABLE COMMUNICATIONS INC ADDRESS: 4601 SMITH ST HARRISBURG, PA. 17109 CONTACT: CONSTRUCTION COORDINATOR

COMPANY: UPPER ALLEN TOWNSHIP OF ADDRESS: 100 GETTYSBURG PIKE MECHANICSBURG, PA. 17055 CONTACT: KODI B. HOCKENBERRY EMAIL: khockenberry@uatwp.org

COMPANY: UGI UTILITIES INC ADDRESS: 1500 PAXTON ST HARRISBURG, PA. 17104 CONTACT: TOM WITT EMAIL: twitt@ugi.com

COMPANY: SPRINT COMMUNICATIONS CO LP ADDRESS: 6500 SPRINT PARKWAY MS: KSOPHR0312 OVERLAND PARK, KS. 662156100 CONTACT: JESSICA REVELLE EMAIL: jessica.m.revelle@sprint.com



SITE LOCATION MAP

SCALE : 1" = 2,000'

APPROVED BY THE BOARD OF COMMISSIONERS OF UPPER ALLEN TOWNSHIP, THIS _____ DAY OF _____, 20____.

ATTEST: _____ _____
SECRETARY CHAIRMAN

APPROVED BY THE PLANNING COMMISSION OF UPPER ALLEN TOWNSHIP, THIS 28th DAY OF August, 2022.

ATTEST: _____ _____
SECRETARY CHAIRMAN

REVIEWED THIS 16th DAY OF August 16, 2022, BY CUMBERLAND COUNTY PLANNING DEPARTMENT.

ATTEST: _____
DIRECTOR OF PLANNING

REVIEWED BY THE UPPER ALLEN TOWNSHIP ENGINEER

REVIEWED THIS _____ DAY OF _____, 20____

_____
ENGINEER

I, Timothy L. Mellott, P.E., hereby certify that I am a Pennsylvania registered professional engineer and that all elements of the plan are inconformity with the Township Code and applicable state regulations, as required by Section 220–15.N(3) of the Codified Ordinances of Upper Allen Township.

I, Timothy L. Mellott, P.E., hereby certify the portions of this site are underlain by limestone bedrock based on geological maps, and upon a carbonate assesment report prepared by Pierre O. MaCoy, Geologist with CMX.

"I, Timothy L. Mellott, P.E., on this date _____, have reviewed and hereby certify that the SWM site plan meets all design standards and criteria of the Upper Allen Township Stormwater Management Ordinance."

COMMONWEALTH OF PENNSYLVANIA REGISTERED PROFESSIONAL TIMOTHY L. MELLOTT ENGINEER No. 056207–E

Timothy L. Mellott, P.E.
Mellott Engineering, Inc.
7500 Devonshire Heights Road
Hummelstown, PA 17036
PH: 717–566–6533
FAX: 717–427–2700

COMMONWEALTH OF PENNSYLVANIA
COUNTY OF
ON THIS THE _____ DAY OF _____, 20____

BEFORE ME, _____, THE UNDERSIGNED OFFICER, PERSONALLY APPEARED
WHO ACKNOWLEDGED HIMSELF TO BE THE PRESIDENT OR VICE PRESIDENT OF HERTZLER ROAD ASSOCIATED, L.P. A CORPORATION, AND THAT HE AS SUCH PRESIDENT OR VICE PRESIDENT, BEING AUTHORIZED TO DO SO, EXECUTED THE FOREGOING INSTRUMENT FOR THE PURPOSE THEREIN CONTAINED BY SIGNING THE NAME OF THE CORPORATION BY HIMSELF AS PRESIDENT OR VICE PRESIDENT.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL.

MY COMMISSION EXPIRES _____

_____ _____
NOTARY PUBLIC DATE

IT IS HEREBY CERTIFIED THAT THE UNDERSIGNED HAS LEGAL OR EQUITABLE TITLE TO THE LAND SHOWN AND THAT ALL ROADS, STREETS OR RIGHT–OF–WAY (OR EASEMENTS) SHOWN HEREON, IF NOT PREVIOUSLY DEDICATED, ARE HEREBY OFFERED FOR PUBLIC USE.

_____
OWNER

OWNER STORMWATER MANAGEMENT FACILITIES ACKOWLEDGEMENT

I Francis McNaughton, hereby acknowledge that the Stormwater Management Facilities and BMP's are to be permanent fixtures that can be altered or removed only after approval of a revised plan by the applicable municipality.

_____
OWNER

I, Rory Chapman, hereby certify that I am a registered Land Surveyor in compliance with the laws of the Commonwealth of Pennsylvania; that this plan correctly represents a survey originally completed by CDEG on April 2005 and reconfirmed by A to Z Land Surveyors in May 2022; that all monuments shown thereon actually exist and that their location, size, type and material are accurately shown.

_____
SURVEYOR
Rory Chapman, P.L.S.

COMMONWEALTH OF PENNSYLVANIA REGISTERED PROFESSIONAL RORY L. CHAPMAN LAND SURVEYOR SU061142

No.	REVISION	DATE
3	Addressing Review Comments	August 3, 2022
4	Addressing Review Comments	September 5, 2022
5	Adding Veolia Water System Design	May 1, 2023
6	Added signature block approval dates	May 18, 2023

MELLOTT ENGINEERING, INC.
Copyright © 2022

DRAWING ID 202202cov
DATE: July 1, 2022
SHEET 1 of 21

All Drawings, Specifications & Ideas Design Prepared, Presented, Developed, Submitted, Signed & Sealed Are, And Shall Remain The Property Of Mellott Engineering, Inc. And Are Not To Be Used In Any Way Without The Written Permission Of Mellott Engineering, Inc.


INTENT OF PLAN

The intent of this plan sheet is to provide a Master Development Plan for the overall Autumn Chase PRD. The Autumn Chase PRD was approved by the Upper Allen Township Board of Commissioners as per Written decision dated – May 8, 2012. The project shall be implemented in accordance with the Developer Agreement, dated April 26, 2012, between Hertzler Road Associates, L.P. and Upper Allen Township. See the below notes and plan references for general project information; see other plan sheets for detailed information pertaining to Phase II.

PLAN NOTES

(See circled # on plan for note association)

1. Autumn Chase is an approved Planned Residential Development consisting of a total of 295 residential units with the following uses (See Phasing Plan):
   - 161 Single–family dwelling lots (78 North and 83 south of Hertzler Road);
   - 60 Duplex Units;
   - 74 Townhouse Units;
   - Open Space Lots (>30% of gross tract)
2. A Homeowners Association is proposed with the development. The Home Owners Association Documents shall be reviewed by the Township in conjunction with this plan. The association shall be responsible for maintenance and upkeep of the following:
   a. All Open Space Areas;
   b. All on–site stormwater management facilities located outside of a public right–of–way including but not limited to: stormwater detention basins, water quality basins, infiltration facilities, piping, riprap aprons, swales, etc.;
   c. All sidewalk located within Open Space areas and sidewalk within the public right–of–way that abuts open space areas;
   d. Boulevard Landscape islands (landscape and boulevard islands shall be maintained by the developer until such responsibility is transferred to the homeowners association established with the development. Upper Allen Township shall not be held responsible for damage to plantings within the islands for any reason, and the municipality may remove or trim the vegetation if necessary for public safety);
3. Hertzler Road shall be improved along the subject tract's entire length of road frontage and off site in accordance with the Developers Agreement.
4. DEP Permitting has been obtained for the stream impacts associated with the proposed Hertzler Road improvements. All work to be in accordance with the permit conditions.
5. All streets proposed with this project shall be constructed to township standards and shall be offered for dedication to the township upon completion of improvements. All proposed streets are classified as minor streets and shall be 34' wide curbed cartways (slant curb) with an associated 50' right–of–way except for the boulevard entrances which will be 20' cartways with a 10' landscaped boulevard island with an associated 66' right–of–way. All Landscape Boulevard Islands shall be maintained by the homeowners association.
6. Stormwater Best Management Practices were incorporated into the site design to manage stormwater runoff discharge rates, enhance water quality and promote groundwater recharge to the extent practical; see Post Construction Stormwater Management Plan.
7. There is a FEMA delineated floodplain located on the property. The floodplain is located along the eastern property line where Hertzler Road and the existing unnamed stream pass under the railroad bridge. The floodplain is depicted per scan overlay of Flood Insurance Rate Map (Community–Panel Number 42041C0287E, Zone A, dated March 16, 2009). The current study is a Zone A non–detailed study area with no base flood elevation information
8. Landscaping is proposed throughout the development to enhance the community and to provide other desired functions, such as:
   a. Tree buffer proposed along Hertzler Road frontage to provide for a visual vegetative buffer between Hertzler Road and units proposed in the development;
   b. Tree plantings proposed along the existing stream (parallels Hertzler Road) to provide a vegetated riparian buffer along the stream;
   c. Tree plantings and landscaping proposed around some of the water quality facilities (plantings provide shade to cool runoff)
   d. Tree plantings and landscaping other than street trees shall be selected in accordance with Upper Allen Township Subdivision and Land Development Ordinance Section 220–26.B(2).
   e. Boulevard islands shall be landscaped to provide for shading and overall aesthetic enhancement to the community;
   f. Street trees shall be planted along both sides of all proposed streets at a rate of two (2) trees per every 100'; all proposed street trees shall be selected and installed in accordance with Upper Allen Township Subdivision and Land Development Ordinance Section 220–26.D(7)
   g. Should a phased final plan propose fewer trees and/or shrubs than Ordinance requirements, the additional trees required to meet Ordinance requirements should be planted in the open space areas and/or adjacent to or along the Greenway Trail as directed by the Township.
9. Street lighting is proposed throughout the development as shown on this plan. Street lights are proposed at all street intersections and at other locations depicted on the plan. In addition to the street lights, each single family detached dwelling lot shall install an outside electric dusk til dawn yard light. Each individual home owner shall be responsible for maintenance of their own yard light although the Home Owners Association shall be responsible for maintenance of the street lights; developer is responsible for street light maintenance until the HOA is formed.
10. A six foot wide off–street trail shall be constructed along the frontage of Hertzler Road as shown on this plan. Timing of the trail installation shall be installed in accordance the Developer Agreement, dated April 26, 2012, between Hertzler Road Associates, L.P. and Upper Allen Township.
11. Open Space is provided throughout the development (>30% of gross tract area). Total area of Open Space Lots 1–9 is 65.457 acres.
12. In accordance with the Developer Agreement, the Residual Area is not a part of and shall not be subject to the terms of the Autumn Chase PRD. A stormwater easement is hereby established over the residual area, in a location, size and designation to be later established, for the purposes of conveying and managing stormwater flows from the Autumn Chase PRD to the Southern Basin. This easement shall in no way restrict future use of the Residual Area."



Phasing Schedule: In accordance with Section 709(c) of the MPC, 53 P.S. § 10709(c), Developer's intended schedule for the phases of the Autumn Chase PRD (each a "Phase" and collectively the "Phases") is as follows (the "Phasing Schedule"):

Existing Phase 1 - 39 Units (Plan filing date 2015)
Phase 2 - 56 Units (Plan filing date 2022)
Existing Phase 3 - 39 Units (Plan filing date 2021)
Phase 4 - 28 Units (Plan filing date 2023)
Phase 5 - 35 Units (Plan filing date 2023)
Phase 6 - 36 Units (Plan filing date 2025)
Phase 7 - 20 Units (Plan filing date 2026)
Phase 8 - 42 Units (Plan filing date 2028)

PHASING PLAN
Scale: 1" = 1,000'

LANDSCAPE LEGNED
- Proposed Shade Tree
- Proposed Evergreen Tree
- Proposed shrub
- Conceptual Cluster of Ornamental Plantings
- Proposed Private Open Space
- Proposed Residual Area

Scale: 1" = 120'

Original Tract
Below Areas Include Phases I & III
Total Gross Area of both Parcels: 6,209,731 sf or 142.55 ac
Total Net Area of both Parcels: 6,134,676 sf or 140.83 ac
Tax Parcel No. 42–11–0272–001
Total Gross Area: 5,378,304.8 Sq Ft = 123.47 Ac.
Total Net Area: 5,303,249.9 Sq Ft = 121.75 Ac.
Hertzler Road Legal R/W: 75,054.8 Sq Ft = 1.72 Ac.
Tax Parcel No. 42–11–0274–028
Total Gross/Net Area 831,426 sf or 19.087 acres

78 Single–Family Dwelling Lots (North of Hertzler Road) (161 total)

74 Townhouse Units

24 Duplex Units (60 Total)

36 Duplex Units (60 Total)

83 Single–Family Dwellings (South of Hertzler Road) (153 total)

Residual Area

OS–1 through OS–9 (Open Space)

Stormwater Basin 4A, 4B, #5

Hertzler Road Improvements

Hertzler Road Off–Street Trail

Stream Culvert Improvements

Proposed Streets

Landscaping

Street Lights

Stormwater Management

Homeowners Association Proposed

Drainage Easements

Gazebo

FEMA Floodplain (Zone A)

Nature Trail

Pennigton Farm Development

Winding Hills (PRD)

Hertzler Road

S. Autumn Chase Drive

N. Autumn Chase Drive

Sycamore Drive

Cedar Lake Drive

Allen View

Autumn Ridge Drive

N. Pal Harvest Drive

S. Pal Harvest Drive

Autumn Lane

Autumn Chase Court


MASTER DEVELOPMENT PLAN
FOR
AUTUMN CHASE PRD – PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road • Hummelstown, PA 17036
mellotteng@comcast.net
717–566–6533

REVISIONS	DATE
1. Addressing Review Comments	8–3–2022
2. Addressing Review Comments	9–5–2022
3. Adding Veolia Water System Design to the plans	5–1–2023
4. –	–
5. –	–
6. –	–
7. –	–
8. –	–
9. –	–

Sheet No. 2 of 21
Project No. 202202
Date July 1, 2022

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 MP.dwg, 4/28/2023 2:53:59 PM, EDT



PASADA Map 2018

AERIAL LOCATION MAP
Scale: 1" = 1,000'

EXISTING FEATURES PLAN NOTES

1. Overal original subject tract consisted of two (2) parcels of Land; both tracts are owned by:
   Hertzler Road Associates, LP (areas include Phases I & III)
   Total Gross Area of both Parcels: 6,209,731 sf or 142.55 ac
   Total Net Area of both Parcels: 6,134,676 sf or 140.83 ac
   Phase I & III Residual Tract Area: 4,010,285 Sq Ft or 92.063 Ac (south side of Hertzler Road)
   Tax Parcel No. 42-11-0272-001
2. Subject Tract is located in the R-1 (Low Density Residential District) and RL (Rural Living)
   R-1 (Low Density Residential): 5,565,535 sf or 127.77 ac
   RL (Rural Living): 644,196 sf or 14.79 ac
3. There is an unnamed stream tributary to the Yellow Breeches Creek (CWF) that parallels Hertzler Road through the site. There is a 0.25 acre wetland pocket located along the south side of Hertzler Road towards the eastern side of the site (no wetland impacts proposed). There are no significant rock outcrops or contaminated soils known to exist on the site. There are two (2) sink holes located along the southern property line on the south side of Hertzler Road; the sinkholes are proposed to be repaired with the applicable future phase of construction.
4. There is a FEMA delineated floodplain located on the property. The floodplain is located along the eastern property line where Hertzler Road and the existing unnamed stream pass under the railroad bridge. The floodplain is depicted per scan overlay of Flood Insurance Rate Map (Community–Panel Number 42041C0287E, Zone A, dated March 16, 2009). The current study is a Zone A non–detailed study area with no base flood elevation information.

Phase III Existing Property Line Table

Line	Length	Bearing
EL1	103.76	N 86°39'48" E
EL2	128.06	S 70°34'15" E
EL3	47.82	S 58°33'5" E
EL4	107.99	S 46°44'0" E
EL5	105.35	S 89°58'9" E
EL6	106.94	S 85°33'17" E
EL7	310.90	S 87°59'5" E
EL8	228.00	S 88°33'12" E
EL9	101.72	N 83°3'45" E
EL10	42.63	N 85°40'41" E
EL11	364.69	S 29°46'11" W
EL12	1498.97	S 41°59'18" W
EL13	868.85	N 65°9'27" W
EL14	173.79	N 27°0'30" W
EL15	642.50	N 25°22'37" W
EL16	1566.92	N 26°19'7" E
EL17	54.39	N 89°5'10" E

Phase III Existing Property Curve Table

Curve	Length	Radius	Chord Dir	Chord Len
EC1	156.95	395.00	N 81°57'13" W	155.92
EC2	203.49	970.00	N 64°33'40" W	203.11
EC3	55.69	270.00	N 52°38'32" W	55.59
EC4	249.02	330.00	S 68°21'5" E	243.15
EC5	20.80	270.00	N 87°45'43" W	20.80
EC6	14.00	330.00	S 86°46'11" E	14.00
EC7	179.99	1230.00	N 87°15'17" E	179.83
EC8	21.46	470.00	S 84°22'13" W	21.45
EC9	878.28	3927.57	N 36°13'4" E	876.45
EC10	13.76	330.00	N 87°51'29" E	13.76

SOILS TABLE

SOIL SYMBOL	SOIL DESCRIPTION	SLOPE (%)	HYDROLOGIC GROUP
BdB	Bedington Shaly Silt Loam	3 to 8%	B
BdC	Bedington Shaly Silt Loam	8 to 15%	B
BdD	Bedington Shaly Silt Loam	15 to 25%	B
BpB	Blairton silt loam	3 to 8%	C
BrB	Brinkerton silt loam	3 to 8%	D
DuB	Duffield silt loam	3 to 8%	B
EdB	Edom silt loam	3 to 8%	B
EdC	Edom silt loam	8 to 15%	B
HaA	Hagerstown shaly silt loam	0 to 3%	B
HaB	Hagerstown shaly silt loam	3 to 8%	B
Me	Melvin silt loam	0 to 2%	B/D
Pe	Penlaw silt loam	0 to 3%	C/D

In general, the soils present should not pose any significant limitation to the type of development proposed. Reference the following recommendations pertaining to possible issues that may be encountered during construction.

- If unrippable rock is encountered during proposed grading, blasting or drilling may be required. Removed rock can be crushed if necessary and used for fill.
- If water table is encountered during excavation, dirty water shall be pumped out into a filter bag or sediment removal pond.
- The SCS Dauphin County Soil Survey indicates some of the soils have a poor rating for use as road fill. The contractor should use only what soils are suitable for road fill and shall place and compact fill in accordance with standard practice. All road fill must meet Penn DOT Pub. 408 standards.
- Trap/Basin Core material shall be unified class CH or CL soil compacted to 98% of max dry density. Homogeneous embankment material to be compacted in 8" layers to a minimum final density of not less than 98% of max. Dry density within 2% of optimum moisture content. (ASTM Method D1557).

Scale: 1"=100'

DATE
REVISIONS
1. 2. 3. 4. 5. 6. 7. 8. 9.

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

EXISTING RESOURCES AND SITE ANALYSIS PLAN

FOR

AUTUMN CHASE PRD – PHASE II

Land Developer: Hertzler Road Associates, L.P.

UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
3 of 21

M:\Drawings\2022\202202 Autumn Chase Phase II\202202 EX.dwg, 6/29/2022 3:46:04 PM, EDT

SUBDIVISION PLAN GENERAL NOTES

The subdivision associated with the Autumn Chase Phase II Final Subdivision Plan consists of the creation of Open Space Lot OS–4, public street right of way and temporary right of way associated with the temporary cul–de–sacs. In addition, stormwater and sanitary sewer easements are proposed for all storm and sanitary sewer improvements located outside of a public street right of way. See other plan sheets for proposed improvements. Concrete monuments shall be set as shown and iron pins shall be set at all other unmarked property and right of way corners. See other plan sheets for design information.

0 40 80

1 inch = 80 ft.

LEGEND

- PROPOSED BUILDING SETBACK LINE
- PROPOSED RIGHT–OF–WAY LINE
- PROPOSED PROPERTY LINE
- PROPOSED PUBLIC RIGHT–OF–WAY
- PROPOSED CONCRETE MONUMENT
- PROPOSED DRAINAGE/STREAM EASEMENT
- PROPOSED SANITARY EASEMENT
- PROPOSED CLEAR SIGHT TRIANGLE
- PROPOSED ACCESS EASEMENT
- N48°54'34"W 120.55' PROPOSED PROPERTY LINE DESCRIPTION
- *N66°34'22"E 88.91'* *Existing Property Line Descriptions*
- *Existing Property Line*
- *Existing Adjoining Property*
- *Existing Right–of–way*
- *Existing PPL Right of Way*
- *Existing Zoning District Boundary Line*
- *Existing 100 Year Floodplain*

Phase II Residual Land

Gross: 3,722,762 Sq Ft or 85.46 Ac.
Net: 3,697,072 Sq Ft or 84.87 Ac.
(Net Area excludes temp cul–de–sac R/W)

Match Line

PHASE II DRAINAGE EASEMENT LINE TABLE		
Line	Length	Bearing
D1	281.64	S 76°16'50" W
D2	39.18	N 26°19'7" E
D3	256.43	N 76°16'50" E
D4	234.72	S 75°28'4" E
D5	141.56	S 68°25'8" E
D6	22.78	S 41°16'43" E
D7	70.89	S 65°41'3" E
D8	10.77	N 51°7'20" E
D9	11.96	S 18°35'51" W
D10	24.75	N 71°24'10" W
D11	93.76	N 65°41'3" W
D12	22.78	N 41°16'43" W
D13	141.56	N 68°25'8" W
D14	234.72	N 75°28'4" W
D15	17.00	S 18°35'51" W
D16	21.26	N 71°24'9" W
D17	106.08	N 77°1'46" W
D18	100.02	N 41°16'43" W
D19	30.00	N 21°5'29" E
D20	100.02	S 41°16'43" E
D21	107.55	S 77°1'46" E
D22	19.40	S 71°24'9" E
D23	159.83	S 87°59'6" E
D24	88.67	S 2°37'39" W
D25	184.76	N 87°50'21" W
D26	228.63	S 84°1'11" W
D27	85.90	N 5°8'23" W
D28	87.13	N 66°2'51" W
D29	12.70	N 18°35'51" E
D30	105.35	S 89°58'9" E
D31	106.94	S 85°33'17" E

PHASE II DRAINAGE EASEMENT LINE TABLE		
Line	Length	Bearing
D32	31.07	S 87°59'6" E
D33	228.00	S 88°33'12" E
D34	338.99	S 30°32'46" E
D35	108.44	S 77°19'57" W
D36	68.83	S 46°46'5" W
D37	50.00	S 77°19'57" W
D38	50.08	S 88°50'59" W
D39	618.05	S 77°19'57" W
D40	43.24	S 85°29'11" W
D41	51.59	S 86°48'42" W
D42	55.77	S 79°27'2" W
D43	56.51	N 29°56'37" E
D44	64.52	N 7°49'12" W
D45	21.63	N 69°35'40" W
D46	311.06	S 70°14'50" W
D47	201.08	N 4°20'51" W
D49	30.00	N 85°39'9" E
D50	201.08	S 4°20'51" E
D51	311.06	N 70°14'50" E
D52	39.57	S 69°35'40" E
D53	92.73	S 7°49'12" E
D54	66.77	S 29°56'37" W
D55	57.70	N 79°27'2" E
D56	5.33	N 86°48'42" E
D57	82.93	N 86°48'42" E
D58	629.59	N 77°19'57" E
D59	16.21	S 2°9'39" W
D60	50.00	S 87°50'21" E
D61	46.80	N 2°9'39" E
D62	118.86	N 5°49'22" E
D63	164.96	N 2°9'39" E

PHASE II DRAINAGE EASEMENT CURVE TABLE				
Curve	Length	Radius	Chord Dir	Chord Len
DC1	41.91	85.00	N 89°35'37" W	41.49
DC2	56.70	115.00	N 89°35'37" W	56.13
DC3	27.07	220.00	N 71°56'36" W	27.05
DC4	101.84	215.00	N 54°50'56" W	100.89
DC5	78.80	185.00	S 53°28'53" E	78.21
DC6	23.77	330.00	S 62°1'6" E	23.76
DC7	38.96	27.00	N 22°44'31" W	35.67
DC8	91.58	215.00	S 53°28'53" E	90.89
DC9	87.63	185.00	N 54°50'56" W	86.82
DC10	23.37	190.00	N 71°56'36" W	23.36
DC11	13.56	27.00	N 4°12'23" E	13.42
DC12	71.76	115.00	S 59°9'16" E	70.60
DC13	122.97	255.00	N 55°5'37" W	121.78
DC14	137.44	285.00	N 55°5'37" W	136.11
DC15	53.04	85.00	S 59°9'16" E	52.18
DC16	14.00	330.00	S 86°46'11" E	14.00
DC17	42.48	27.00	N 42°54'43" W	38.23
DC18	36.73	27.00	S 57°34'27" W	33.97
DC19	37.55	330.00	S 86°42'33" E	37.53
DC20	20.80	270.00	N 87°45'43" W	20.80
DC21	68.74	1230.00	N 89°50'46" E	68.73
DC22	148.04	65.00	S 35°18'11" E	118.06
DC23	255.83	365.00	N 89°40'26" W	250.62
DC24	91.98	50.00	S 57°3'1" E	79.55
DC25	36.79	20.00	S 57°3'1" E	31.82
DC26	276.85	395.00	N 89°40'26" W	271.22
DC27	79.71	35.00	S 35°18'11" E	63.57
DC28	5.88	92.00	S 3°59'31" W	5.88
DC29	6.90	108.00	N 3°59'31" E	6.90
DC30	42.34	27.00	S 47°5'17" W	38.14

PHASE II access easements are defined for sidewalk located outside of the public street right of way (easement extends 5' past edge of sidewalk)

PHASE II SANITARY SEWER EASEMENT LINE TABLE		
Line	Length	Bearing
S1	282.85	N 89°49'30" W
S2	30.02	N 2°9'39" E
S3	251.81	S 89°49'30" E
S4	32.78	N 0°10'30" E
S5	30.01	S 88°33'12" E
S6	62.11	S 0°10'30" W
S7	287.68	S 26°21'38" W
S8	30.00	N 63°38'22" W
S9	293.52	N 26°21'38" E
S10	30.56	S 52°37'3" E

Phase II Residual Land

Gross: 3,722,762 Sq Ft or 85.46 Ac.
Net: 3,697,072 Sq Ft or 84.87 Ac.
(Net Area excludes temp cul–de–sac R/W)

STREET RIGHT OF WAY LINE TABLE		
Line	Length	Bearing
R1	164.96	S 2°9'39" W
R2	118.86	S 5°49'22" W
R3	46.80	S 2°9'39" W
R4	50.00	N 87°50'21" W
R5	73.00	N 2°9'39" E
R6	21.07	N 87°50'21" W
R7	395.51	S 74°13'43" W
R8	13.27	N 67°58'31" W
R9	35.92	S 35°7'20" W
R10	50.00	N 54°52'40" W
R11	35.92	N 35°7'20" E
R12	127.08	N 18°35'51" E
R13	50.19	N 71°24'9" W
R14	95.01	N 41°16'43" W
R15	195.12	N 75°28'4" W
R16	50.00	N 52°37'3" W
R17	195.12	S 75°28'4" E
R18	95.01	S 41°16'43" E
R19	42.19	S 71°24'9" E
R20	102.62	N 18°35'51" E
R21	122.85	S 18°35'51" W
R22	144.69	S 21°39'1" W
R23	32.68	S 18°36'57" W
R24	12.28	S 67°58'31" E
R25	395.51	N 74°13'43" E
R26	13.07	S 87°50'21" E
R27	165.85	N 2°9'39" E
R28	120.00	S 87°59'6" E
R29	44.34	N 2°9'39" E
R30	50.00	S 87°50'21" E
R31	2.06	S 2°9'39" W
R32	2.06	N 35°7'20" E
R33	50.00	S 54°52'40" E
R34	44.34	S 35°7'20" W
R35	50.00	S 52°37'3" E

STREET RIGHT OF WAY CURVE TABLE				
Curve	Length	Radius	Chord Dir	Chord Len
RC1	42.34	27.00	S 47°5'17" W	38.14
RC2	6.90	108.00	N 3°59'31" E	6.90
RC3	6.88	92.00	S 3°59'31" W	6.88
RC4	42.41	27.00	N 42°50'21" W	38.18
RC5	54.77	175.00	S 83°11'41" W	54.55
RC6	115.44	175.00	S 86°52'24" E	113.36
RC7	38.91	27.00	S 70°44'27" W	35.63
RC8	37.08	375.00	N 32°17'22" E	37.06
RC9	93.73	325.00	N 26°51'35" E	93.41
RC10	42.41	27.00	N 26°24'9" W	38.18
RC11	92.01	175.00	S 56°20'26" E	90.95
RC12	193.93	325.00	N 58°22'24" W	191.07
RC13	263.70	225.00	S 70°57'26" W	248.86
RC14	322.30	275.00	N 70°57'26" W	304.16
RC15	223.77	375.00	N 58°22'24" W	220.46
RC16	65.72	125.00	S 56°20'26" E	64.97
RC17	42.41	27.00	N 63°35'51" E	38.18
RC18	38.96	27.00	N 22°44'31" W	35.67
RC19	111.55	330.00	S 73°45'55" E	111.02
RC20	36.73	27.00	S 57°34'27" W	33.97
RC21	5.75	108.00	N 20°7'26" E	5.75
RC22	4.87	92.00	S 20°7'59" W	4.87
RC23	40.80	27.00	S 24°41'20" E	37.02
RC24	82.46	125.00	S 86°52'24" E	80.97
RC25	70.42	225.00	S 83°11'41" W	70.13
RC26	42.41	27.00	N 47°9'39" E	38.18
RC27	42.48	27.00	N 42°54'43" W	38.23
RC28	9.89	7.00	S 38°17'48" E	9.08
RC29	241.88	50.00	N 59°50'0" E	66.15
RC30	241.88	50.00	S 22°33'1" E	66.15
RC31	9.89	7.00	N 75°34'47" E	9.08
RC32	10.20	275.00	S 36°19'11" W	10.20
RC33	2.23	225.00	S 37°5'56" W	2.23
RC34	10.55	10.00	S 6°35'21" W	10.07
RC35	251.54	50.00	S 59°30'44" E	58.60
RC36	8.61	10.00	N 59°56'5" E	8.35

Phase III Existing Property Line Table		
Line	*Length*	*Bearing*
EL1	*103.76*	*N 86°39'48" E*
EL2	*128.06*	*S 70°34'16" E*
EL3	*47.82*	*S 58°13'5" E*
EL4	*107.99*	*S 46°44'0" E*
EL5	*105.35*	*S 89°58'9" E*
EL6	*106.94*	*S 85°33'17" E*
EL7	*310.90*	*S 87°59'6" E*
EL8	*228.00*	*S 88°33'12" E*
EL9	*101.72*	*N 83°1'45" E*
EL10	*42.63*	*N 85°40'41" E*
EL11	*364.69*	*S 29°46'11" W*
EL12	*1498.97*	*S 41°59'18" W*
EL13	*868.85*	*N 65°9'27" W*
EL14	*173.79*	*N 27°0'30" W*
EL15	*642.50*	*N 25°22'37" W*
EL16	*1566.92*	*N 26°19'7" E*
EL17	*54.39*	*N 89°31'0" E*

Phase II Existing Property Curve Table				
Curve	*Length*	*Radius*	*Chord Dir*	*Chord Len*
EC1	*156.95*	*395.00*	*N 81°57'13" W*	*155.92*
EC2	*203.49*	*970.00*	*N 64°33'40" E*	*203.11*
EC3	*55.69*	*270.00*	*N 52°36'32" W*	*55.59*
EC4	*249.02*	*330.00*	*S 68°21'5" E*	*243.15*
EC5	*20.80*	*270.00*	*N 87°45'43" W*	*20.80*
EC6	*14.00*	*330.00*	*S 86°46'11" E*	*14.00*
EC7	*179.99*	*1230.00*	*N 87°15'7" E*	*179.83*
EC8	*21.46*	*470.00*	*S 84°22'13" W*	*21.46*
EC9	*878.28*	*3927.57*	*N 36°13'4" E*	*876.45*
EC10	*13.76*	*330.00*	*N 87°51'29" E*	*13.76*

Hertzler Road
Allen View
Ashwood Lane
Brittany Drive
S. Autumn Chase Drive
S. Fall Harvest Drive
N. Fall Harvest Drive
N. Autumn Chase Drive
Hertzler Road rightofway dedication (Phase I)
Hertzler Road rightofway dedication (Phase II)
OS–1 35,184 Sq Ft 0.808 Ac.
OS–2 690,287 Sq Ft 15.847 Ac.
OS–4 156,489 Sq Ft 3.59 Ac.
Temporary Cul–de–sac (40' dia. pave, 50' R/W)
Temporary Sanitary Sewer Easement until future public road right way extension
Proposed Concrete Monument
Drainage Easement
Sanitary Sewer Easement
Existing Nature Trail Easement
Ex. 50' PA POWER & LIGHT CO RIGHT OF WAY (DB 282–PG 620)
Ex. 100' PA POWER & LIGHT CO RIGHT OF WAY (DB 149–PG 575)
Ex. 200' PA POWER & LIGHT CO RIGHT OF WAY (DB 149–PG 569)
FEMA 100 Year Floodplain
PRD PLANNED RESIDENTIAL DEVELOPMENT
R LOW DENSITY RESIDENTIAL
RL RURAL LIVING
N/F Allenview Home Owners Association Deed Book 35, Volume X, Page 952 Plan Book 42, Page 69 Tax Parcel 42–28–2423–268
N/F Hollinger Development II, LLC Instr # 201107738 Tax Parcel 42–11–0272–140

DATE
8–3–2022

REVISIONS
1. Addressing Review Comments
2.
3.
4.
5.
6.
7.
8.
9.

M:\Drawings\2022\202202 Autumn Chase Phase II\202202 SUB.dwg 8/2/2022 10:37:50 AM EDT

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road • Hummelstown, PA 17036
mellotteng@comcast.net
717–566–6533

FINAL SUBDIVISION PLAN

FOR

AUTUMN CHASE PRD – PHASE II

Land Developer: Hertzler Road Associates, L.P.

UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.

4 of 21

Match Line

Phase II Residual Land

Gross: 3,722,762 Sq Ft or 85.46 Ac.
Net: 3,697,072 Sq Ft or 84.87 Ac.
(Net Area excludes temp cul-de-sac R/W)

Temporary Cul-de-sac (40' dia. pave, 50' R/W)

Proposed Concrete Monument

Drainage Easement

EX 50' PA POWER & LIGHT CO RIGHT OF WAY (DB 282-PG 620)

EX 100' PA POWER & LIGHT CO RIGHT OF WAY (DB 149-PG 575)

EX 85' PA POWER & LIGHT CO RIGHT OF WAY (DB 282-PG 620)

EX 200' PA POWER & LIGHT CO RIGHT OF WAY (DB 149-PG 569)

EX 35' PA POWER & LIGHT CO RIGHT OF WAY (DB 282-PG 620)

Existing Nature Trail Easement

50' Setback from site boundary

N/F
Allenview Home Owners Association
Deed Book 35, Volume X, Page 953
Plan Book 47, Page 43
Tax Parcel 42-28-2423-268

N/F
Allenview Home Owners Association
Deed Book 35, Volume X, Page 953
Plan Book 29, Page 77
Tax Parcel 42-29-2452-014

N/F
Hollinger Development II, LLC
Instr # 201107738
Tax Parcel 42-11-0272-140

N/F
Township of Upper Allen
Deed Book 20124512
Plan# 2010-26589
Tax Parcel 42-11-0272-145EX

N/F
Pennington Community Association, Inc.
Instr # 201023922, Tract No. 1
Plan Instr. # 200828172, Lot OS41
Tax Parcel 42-11-0274-008

Pennington Farm Development

R-1 LOW DENSITY RESIDENTIAL
RL RURAL LIVING

EL15 EL14 EL13 EL12

DRAINAGE EASEMENT

IP (typ)

STREET RIGHT OF WAY LINE TABLE		
Line	Length	Bearing
R1	164.96	S 2°9'39" W
R2	118.86	S 5°49'22" W
R3	46.80	S 2°9'39" W
R4	50.00	N 87°50'21" W
R5	73.00	N 2°9'39" E
R6	21.07	N 87°50'21" W
R7	395.51	S 74°13'43" W
R8	13.27	N 67°58'31" W
R9	35.92	S 35°7'20" W
R10	50.00	N 54°52'40" W
R11	35.92	N 35°7'20" E
R12	127.08	N 18°35'51" E
R13	50.19	N 71°24'9" W
R14	95.01	N 41°16'43" W
R15	195.12	N 75°28'4" W
R16	50.00	N 52°37'3" W
R17	195.12	S 75°28'4" E
R18	95.01	S 41°16'43" E
R19	42.19	S 71°24'9" E
R20	102.62	N 18°35'51" E
R21	122.85	S 18°35'51" W
R22	144.69	S 21°39'1" W
R23	32.68	S 18°36'57" W
R24	12.28	S 67°58'31" E
R25	395.51	N 74°13'43" E
R26	13.07	S 87°50'21" E
R27	165.85	N 2°9'39" E
R28	120.00	S 87°59'6" E
R29	44.34	N 2°9'39" E
R30	50.00	S 87°50'21" E
R31	2.06	S 2°9'39" W
R32	2.06	N 35°7'20" E
R33	50.00	S 54°52'40" E
R34	44.34	S 35°7'20" W
R35	50.00	S 52°37'3" E

Phase III Existing Property Line Table		
Line	Length	Bearing
EL1	103.76	N 86°39'48" E
EL2	128.06	S 70°34'15" E
EL3	47.82	S 58°33'5" E
EL4	107.99	S 46°44'0" E
EL5	105.35	S 89°58'9" E
EL6	106.94	S 85°37'17" E
EL7	310.90	S 87°59'6" E
EL8	228.00	S 88°33'12" E
EL9	101.72	N 83°13'45" E
EL10	42.63	N 85°40'41" E
EL11	364.69	S 29°46'11" W
EL12	1498.97	S 41°59'18" W
EL13	868.85	N 65°9'22" W
EL14	173.79	N 27°0'30" W
EL15	642.50	N 25°22'37" W
EL16	1566.82	N 26°19'27" E
EL17	54.39	N 89°3'10" E

Phase II Existing Property Curve Table				
Curve	Length	Radius	Chord Dir	Chord Len
EC1	156.95	395.00	N 81°57'13" W	155.92
EC2	203.49	970.00	N 64°13'40" W	203.11
EC3	55.69	270.00	N 52°38'32" W	55.59
EC4	249.02	330.00	S 68°21'5" E	243.15
EC5	20.80	270.00	N 87°45'43" W	20.80
EC6	14.00	330.00	S 86°46'11" E	14.00
EC7	179.99	1230.00	N 87°15'17" E	179.83
EC8	21.46	470.00	S 84°22'13" W	21.46
EC9	878.28	3927.57	N 36°13'4" E	876.45
EC10	13.76	330.00	N 87°51'29" E	13.76

STREET RIGHT OF WAY CURVE TABLE				
Curve	Length	Radius	Chord Dir	Chord Len
RC1	42.34	27.00	S 47°5'17" W	38.14
RC2	6.90	108.00	N 3°59'31" E	6.90
RC3	5.88	92.00	S 3°59'31" W	5.88
RC4	42.41	27.00	N 42°50'21" W	38.18
RC5	54.77	175.00	S 83°11'41" W	54.55
RC6	115.44	175.00	S 86°52'24" E	113.36
RC7	38.91	27.00	S 70°44'27" W	35.63
RC8	37.08	375.00	N 32°17'22" E	37.06
RC9	93.73	325.00	N 26°51'35" E	93.41
RC10	42.41	27.00	N 26°24'9" W	38.18
RC11	92.01	175.00	S 56°20'26" E	90.95
RC12	193.93	325.00	N 58°22'24" W	191.07
RC13	263.70	225.00	S 70°57'26" W	248.86
RC14	322.30	275.00	S 70°57'26" W	304.16
RC15	223.77	375.00	N 58°22'24" W	220.46
RC16	65.72	125.00	S 56°20'26" E	64.97
RC17	42.41	27.00	N 63°35'51" E	38.18
RC18	38.96	27.00	N 22°44'31" W	35.67
RC19	111.55	330.00	S 73°45'55" E	111.02
RC20	36.73	27.00	S 57°34'27" W	33.97
RC21	5.75	108.00	N 20°7'26" E	5.75
RC22	4.87	92.00	S 20°7'59" W	4.87
RC23	40.80	27.00	S 24°41'20" E	37.02
RC24	82.46	125.00	S 86°52'24" E	80.97
RC25	70.42	225.00	S 83°11'41" W	70.13
RC26	42.41	27.00	N 47°9'39" E	38.18
RC27	42.48	27.00	N 42°54'43" W	38.23
RC28	9.80	7.00	S 38°17'48" E	9.08
RC29	241.88	50.00	N 59°50'0" E	66.15
RC30	241.88	50.00	S 22°33'1" E	66.15
RC31	9.89	7.00	N 75°34'47" E	9.08
RC32	10.20	275.00	S 36°19'11" W	10.20
RC33	2.23	225.00	S 37°5'56" W	2.23
RC34	10.55	10.00	S 6°35'21" W	10.07
RC35	251.54	50.00	S 59°30'44" E	58.60
RC36	8.61	10.00	N 59°56'5" E	8.35

0 40 80
1 inch = 80 ft.

DATE
8-3-2022

REVISIONS
Addressing Review Comments

1. 2. 3. 4. 5. 6. 7. 8. 9.

M:\Drawings\2022\202202 Autumn Chase Phase II\202202 SUB.dwg 8/2/2022 11:37:50 AM EDT

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

FINAL SUBDIVISION PLAN
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
5 of 21

SIGN LEGEND

NO.	DOT NO.	LEGEND	QTY.
A	R1-2	YIELD	3
B	R2-1	SPEED LIMIT 25	5
C	No Ref.	STREET NAME	8 4 Post
D	R1-1	STOP 30"	2

Note:
1. Signs shall be installed at locations shown on the plan unless alternative locations are approved by the township.

0 25 50

1 inch = 50 ft.

LEGEND

- PROPOSED STORM SEWER, INLET
- PROPOSED END SECTION W/ RIPRAP
- PROPOSED SANITARY SEWER MAIN, MANHOLE
- PROPOSED SANITARY SEWER LATERAL & CLEANOUT
- PROPOSED 8" DIP WATER MAIN
- PROPOSED 6" DIP HYDRANT WATER LINE
- PROPOSED WATER SERVICE, CURB STOP, METER (1" Type "K" service, 1" curb stop, 3/4" metter pit)
- PROPOSED STREET LIGHT
- PROPOSED CURB/EDGE OF PAVE
- PROPOSED PERMANENT CONTOUR (2')
- PROPOSED TEMPORARY CONTOUR (2')
- PROPOSED PHASE II PAVEMENT
- Original Existing 2' Contour
- Existing Property Line
- Existing Adjoining Property
- Existing Right-of-way
- Existing Edge of Pave
- Existing Storm Sewer, Inlet, ID#
- Existing Water Main, Hydrant, Valve
- Existing Sanitary Sewer, MH, ID#
- Existing Stream

GENERAL NOTES

1. Gravity public sanitary sewer service shall be provided to all proposed units. Sanitary Sewer Main installation associated with Phase II construction consists of a sewer extension out of existing manhole LS11-31 (LS11-31 was installed with Phase I construction). All sewer construction to be in accordance with Township standards. See Cover sheet and Construction Detail sheets for additional Sanitary Sewer Notes and details.
2. Public water service shall be provided to the project via water main extensions from the existing water main stubs installed with Phase I construction. The water system shown on this plan is per approved Veolia design. All Phase II water mains shall be 8" DIP CL 52 and all water services shall be 1" Type "K" copper. All water system improvements shall be installed in accordance with Veolia requirements.
3. Electric and telecommunication utilities shall be provided and installed as per applicable local utility provider.
4. See Post Construction Stormwater Management Plans for stormwater management BMP detailing.
5. See Erosion Control Plans for temporary BMPs to be implemented during construction.
6. Community cluster mailboxes are proposed as shown.
7. All streets proposed with this project shall be constructed to township standards and shall be offered for dedication to the township upon completion of improvements. All proposed streets are classified as minor streets and shall be 34' wide curbed cartways (slant curb) with an associated 50' right-of-way except for the boulevard entrances which will be 20' cartways with a 10' landscaped boulevard island with an associated 66' right-of-way. Stormwater inlets in streets shall be Type C inlets (8"); see curb to inlet transition detail. Four foot wide concrete sidewalk shall be installed as shown; 5'x5' passing spaces shall be installed where shown.
8. All inlets located in the street shall be PennDOT Type "C" inlets with 8" hoods and all inlets in grass areas shall be Type "M" inlets.
9. Curb ramps shall be installed where sidewalk meets with a street/curbline. Curb Ramps shall be installed in accordance with current Commonwealth of Pennsylvania Department of Transportation Standards for Roadway Construction Publication 72M requirements. The curb ramps shall be installed in accordance with RC-67M Alternative Type 4A Curb Ramp (Perpendicular) dated February 19, 2021. Painted Crosswalks shall be installed at each ramp/road crossing in accordance with Publication 111 TC-8600 requirements (6' crosswalk width centered on crossing, 6" white lines). Stop sign and stop bar shall be installed 4' away from the crosswalks where applicable.

DATE
8-5-2022
9-5-2022
5-1-2023

REVISIONS
1. Addressing Review Comments
2. Addressing Review Comments
3. Adding Veolia Water System Design to the plans
4.
5.
6.
7.
8.
9.

M:\Drawings\2021\202202 Autumn Chase Phase 2\202202 GRD.dwg 5/18/2023 6:43:17 PM EDT

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road • Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

GRADING AND UTILITY PLAN
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
6 of 21

Hertzler Road

Allen View

N/F
Allenview Home Owners Association
Deed Book 35, Volume X, Page 953
Plan Book 42, Page 69
Tax Parcel 42-26-2423-268

Building Setback from site boundary

Temporary Cul-de-sac (40' dia. pave, 50' R/W)

Painted Crosswalk (6' width)

Proposed Hydrant

Phase 2 sewer installation to extend to LS11-44 including laterals as shown

Future phase infrastructure not proposed with this Phase 2 Plan; shown for reference

Future phase infrastructure not proposed with this Phase 4 Plan; shown for reference

Sweet Honey Lane

Temporary Phase 2 Grading contours

Swale P1

Swale P2

Swale P3

Swale P4

Proposed path

Existing Swale

Stream Easement

Ex. Drainage Easement

Existing Culvert "1" 15" HDPE Inv in 494.59 Inv out 492.23

Unnamed Stream (UNT)

25 mph speed limit sign

Inlet Grate=516.61 Inv=514.51

Building P
Building C
Building B
Building N
Building O
Building A

S. Autumn Chase Drive

4' Sidewalk

Proposed Community Mailbox Pavilion (14'x14')

Sidewalk Passing Space (5'x5')

Proposed Hydrant

Extend R-4 riprap apron as shown

N. Fall Harvest Drive

S. Fall Harvest Drive

Existing Sewer Laterals installed with Phase I

Existing Phase I Road Taper

Stormwater Basin #1C

Outlet C2

Lot 36

Painted Crosswalk (6' width)

Existing Concrete Box Culvert "H" (Phase I)

Top of Berm 474.0

4' Sidewalk (typ)

Start taper

Pedestrian Access Easement (typ)

Stormwater Basin #4B

Proposed Gazebo

Proposed Temporary Swale T1

Future phase storm sewer shown for reference

Brittany Drive

Proposed Hydrant

Temporary Cul-de-sac (40' dia. pave, 50' R/W)

EX 50' PA POWER & LIGHT CO RIGHT OF WAY

EX 100' PA POWER & LIGHT CO RIGHT OF

EX 85' PA POWER & LIGHT CO RIGHT OF WAY (DB 282-PG 620)

1 inch = 50 ft.

REVISIONS	DATE
1. Addressing Review Comments	8-5-2022
2. Addressing Review Comments	9-5-2022
3. Adding Veolia Water System Design to the plans	5-1-2023
4.	-
5.	-
6.	-
7.	-
8.	-
9.	-

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 GRD.dwg 5/18/2023 6:43:17 PM EDT

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road • Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

GRADING AND UTILITY PLAN

FOR

AUTUMN CHASE PRD - PHASE II

Land Developer: Hertzler Road Associates, L.P.

UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA


Project No. 202202
Date July 1, 2022

Sheet No.
7 of 21


SANITARY SEWER PIPE LENGTHS SHOWN ON PROFILE REPRESENTS DISTANCE FROM CENTER OF MANHOLE TO CENTER OF MANHOLE; PIPE SLOPE SHOWN ON PROFILE IS CALCULATED BASED ON DISTANCE FROM INSIDE FACE OF MANHOLE TO INSIDE FACE OF MANHOLE

See Construction Detail sheet for Sanitary Sewer Index Map and Manhole location coordinates

STORMWATER INLETS
All inlets located in the street shall be PennDOT Type "C" inlets with 8" hoods and all inlets in grass areas shall be Type "M" inlets.



SANITARY SEWER PROFILE
(LS11-32 TO EXISTING LS11-31)
SCALE: HORZ. 1" = 50'
VERT. 1" = 5'




S. Autumn Chase Drive Profile
SCALE: HORZ. 1" = 50'
VERT. 1" = 5'

S. Autumn Chase Drive Profile
SCALE: HORZ. 1" = 50'
VERT. 1" = 5'

STORM SEWER PROFILE
(ENDWALL A28 TO ENDWALL A27)
SCALE: HORZ. 1" = 50'
VERT. 1" = 5'

STORM SEWER PROFILE
(INLET A31 TO ENDWALL A29)
SCALE: HORZ. 1" = 50'
VERT. 1" = 5'



STORM SEWER PROFILE
(OS-4B TO ENDWALL A1)
SCALE: HORZ. 1" = 50'
VERT. 1" = 5'

S. Autumn Chase Drive Profile
SCALE: HORZ. 1" = 50'
VERT. 1" = 5'

	DATE
1.	8-5-2022
2.	9-5-2022
3.	5-1-2023
4.	-
5.	-
6.	-
7.	-
8.	-
9.	-

REVISIONS
Addressing Review Comments
Addressing Review Comments
Adding Veolia Water System Design to the plans


M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 PR.dwg, 4/28/2023 6:48:15 PM, EST

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road • Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

STREET AND UTILITY PROFLES
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA


Project No. 202202
Date July 1, 2022

Sheet No.
8 of 21




S. Fall Harvest Drive Profile

SCALE: HORZ. 1" = 50'
VERT. 1" = 5'



STORM SEWER PROFILE (ENDWALL A16 TO INLET A14)

SCALE: HORZ. 1" = 50'
VERT. 1" = 5'



STORM SEWER PROFILE (EW-A25A TO EW-A25)

SCALE: HORZ. 1" = 50'
VERT. 1" = 5'


STORM SEWER PROFILE (INLET A25 TO ENDWALL A10)

SCALE: HORZ. 1" = 50'
VERT. 1" = 5'

SANITARY PIPE LENGTHS SHOWN ON PROFILE REPRESENTS DISTANCE FROM CENTER OF MANHOLE TO CENTER OF MANHOLE. PIPE SLOPE SHOWN ON PROFILE IS CALCULATED BASED ON DISTANCE FROM INSIDE FACE OF MANHOLE TO INSIDE FACE OF MANHOLE

See Construction Detail sheet for Sanitary Sewer Index Map and Manhole location coordinates

STORMWATER INLETS
All inlets located in the street shall be PennDOT Type "C" inlets with 8" hoods and all inlets in grass areas shall be Type "M" inlets.



Brittany Drive Profile

SCALE: HORZ. 1" = 50'
VERT. 1" = 5'

DATE	
8-5-2022	
9-5-2022	
5-1-2023	

REVISIONS
1. –
2. Addressing Review Comments
3. Addressing Review Comments
4. Adding Veolia Water System Design to the plans
5. –
6. –
7. –
8. –
9. –

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 PR.dwg, 5/8/2023 12:45:15 PM, EST

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road • Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

STREET AND UTILITY PROFILES
FOR
AUTUMN CHASE PRD – PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
9 of 21

PCSM PLAN INTENT NOTE

The intent of the PCSM Plan sheets are to detail the Post Construction Stormwater Management facilities and Ownership and Maintenance Requirements.

STORMWATER BEST MANAGEMENT PRACTICES SUMMARY

The Post Construction Stormwater Management Plan provides for collection and treatment of project runoff. The main structural stormwater BMPs associated with the project consist of Bioretention–Detention Basins, vegetated swales and storm sewers. See below list of proposed Stormwater BMPs along with general descriptions.

1. Bioretention–Detention Basins – The Basins shall provide several key functions including but not limited to the following:
   a. Stormwater Runoff Rate control shall be provided by using Basin storage and associated outlet structures to attenuate the post development stormwater discharge rates to below pre–development rates for the 2–100 year storm events, including required rate reduction for southern watersheds.
   b. Stormwater Runoff volume control shall be provided through infiltration in Basins. All basins shall be constructed with flat bottoms with shallow sump and planted with retentive basin seed mixture which shall improve water quality, increase infiltration volume and promote evapotranspiration. Soil amendments shall also be used in the basin bottom preparation to enhance vegetation and associated root structure.
   c. The basin design provides for extended detention via use of small low flow orifices. The extended attenuation of the basin discharge provides for stream bank protection, promotes infiltration and provides for longer periods of filtering and plant uptake within the basins.
2. Vegetated Swales and sheet flow are proposed for collection and conveyance to the extent practical. Storm sewer system collection and conveyance is proposed where needed; riprap apron protection shall be provided at all pipe discharges.
3. Soil restoration & amendments: Soil restoration and amendments of the Stormwater Basin bottoms shall be provided. The basin bottom preparation consists of over excavating the basin bottom to 12″ below finished grade, scarification/till the subgrade bottom (minimum 10″ depth desired). Place 12″ of the amended soils mixture over the prepared (tilled) basin bottom followed by stabilization with intended basin seed mixture and mulch. The scarification/tiling of the subsoils shall enhance permeability of the subsoils and to provide increased interface between the subsoils and the amended soils mixture and the amended soils mixture shall promote infiltration through enhance vegetation growth.
4. Street trees and landscaping are proposed with the project. The landscaping/trees shall provide the following benefits: nutrient uptake, evapotranspiration and thermal protection by shading of street pavement/sidewalk areas. Trees are also proposed around the stormwater basins. In addition, the retentive basin seeding shall also provide thermal protection of the basin runoff discharge through shading and additional uptake.
5. Rooftop Disconnect: All roof runoff shall be discharged overland prior to being conveyed to the basins; some roof area shall sheet flow directly to a basin although the majority of the runoff will be collected and conveyed to a respective basin via pipe and/or swale flow.
6. Drainage way(s) and natural features preservation. The stream paralleling Hertzler Road shall be preserved in a drainage easement. The existing wetland pocket on the south side of Hertzler Road shall also be preserved in an easement; no wetland impacts proposed.

GENERAL PCSM NOTES

1. An NPDES Permit related to construction activities is associated with this project (existing NPDES Permit No. PAC210094, expires November 13, 2023. All work to be performed in accordance with permit conditions.
2. The entire project site is located within the Yellow Breeches Creek watershed (CWF).
3. Wetlands shown on this plan are per field delineation performed by Vortex Environmental, Inc.. No wetland impacts are proposed with this project and the wetlands shall be perserved in an easement.
4. BMPs, trees, debris and any other materials not proposed to permanently remain on–site are to be recycled or disposed of in accordance with Department of Environmental Protection regulations. All building materials and wastes must be removed from the site and recycled or disposed in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1 et seq., 271.1 et seq., and 287.1 et seq. No building material, wastes or unused building materials shall be buried, dumped, or discharged at the site.

UTILITY GENERAL NOTES


1. Public water service shall be provided to the project via a water main extensions from the water main stubs installed with Phase I construction.
2. Public sanitary sewer service shall be provided to the project via gravity sewer extensions. The northern portion of the site shall be served via extension from existing manhole LS11–31 installed with Autumn Chase Phase I and southern portion of the site (future phases) shall be served via an extension from the sewer system located within the Pennington Farms Community. All sewer construction to be in accordance with Township standards.
3. Electric and telecommunication utilities shall serve the project. These utility designs shall be performed by the applicable utility company after conditional plan approval.

SOIL PROBE/PERCOLATION TEST

A Geologic Evaluation and Infiltration Testing Report was prepared by CMX which detailed soils, geology and infiltration/soil testing information. The underlying geology is shale with some limestone (majority of site is in shale although eastern portion of site along Hertzler Road is in Limestone Geology). Soil probes and percolation tests where conducted at each of the stormwater basin locations. All of soil test locations yielded suitable probes and infiltration rates. If any sinkholes are encountered during construction contractor and/or owner should immediately consult with a Geotechnical Engineer for guidance on proper sinkhole(s) repair. See above referenced report for probe descriptions and infiltration test rates.

CRITICAL STAGES OF PLAN IMPLEMENTATION

This plan identifies the Post Construction Stormwater Management BMPs for the project. In accordance with NPDES permitting requirements, critical stages of implementation of the plan shall have a licensed professional or designee on site. The critical stages of construction associated with this project would be verification of the outfall pipe installations with antiseep collars, proper soil restoration preparation of the Bioretention–Detention Basin bottoms followed by placement of soil amendment mixture and intended retentive basin seed mixture. All other BMPs can be inspected after construction to verify consistency with the intended design.



0 30 60
Scale: 1" = 60'

DRAWING INDEX MAP
Scale: 1" = 750'

PASDA Aerial

LOCATION/NPDES BOUNDARY MAP
Scale: 1" = 1,200'

Mellott Engineering, Inc.
Timothy L. Mellott, P.E.
7500 Devonshire Heights Road
Hummelstown, PA 17036
PH: 717–566–6533
FAX: 717–427–2700

COMMONWEALTH OF PENNSYLVANIA
REGISTERED PROFESSIONAL
TIMOTHY L. MELLOTT
ENGINEER No. 056207–E

PCSM #1

REVISIONS
1. Addressing Review Comments – DATE 8–5–2022
2. Addressing Review Comments – 9–5–2022
3. Adding Veolia Water System Design to the plans – 5–1–2023

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
mellotteng@comcast.net
717–566–6533

POST CONSTRUCTION STORMWATER MANAGEMENT PLAN

AUTUMN CHASE PRD – PHASE II

FOR


Land Developer: Hertzler Road Associates, L.P.

UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No. PCSM #1
10 of 21

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 PCSM–2.dwg 5/6/2023 1:43:13 PM EDT



DRAWING INDEX MAP
Scale: 1" = 750'

LEGEND

- PROPOSED STORM SEWER, INLET
- PROPOSED END SECTION W/ RIPRAP
- PROPOSED SANITARY SEWER MAIN, MANHOLE
- PROPOSED WATER MAIN (Concept)
- PROPOSED CURB/EDGE OF PAVE
- PROPOSED PERMANENT CONTOUR (2')
- PROPOSED PERMANENT CONTOUR (1')
- PROPOSED PAVEMENT
- Existing 2' Contour
- Existing Property Line
- Existing Adjoining Property
- Existing Right-of-way
- Existing Edge of Pave
- Existing Storm Sewer, Inlet, ID#
- Existing Water Main, Hydrant, Valve
- Existing Sanitary Sewer, MH, ID#
- Existing Soil Boundary Line & Soil Description
- Existing Infiltration Test (See SWM Report)
- Existing Treeline to remain
- Existing Wetland
- Existing Stream
- Existing 100 Year Floodplain (Effective)

Scale: 1" = 60'

SOILS TABLE

SOIL SYMBOL	SOIL DESCRIPTION	SLOPE (%)	HYDROLOGIC GROUP	DEPTH TO WATER TABLE (FT)	SOIL REACTION (pH)	SUITABILITY FOR ROADFILL	SUITABILITY FOR TOPSOIL
BdB	Bedington Shaly Silt Loam	3 to 8%	B	5+	4.5–7.3	FAIR	POOR
BdC	Bedington Shaly Silt Loam	8 to 15%	B	5+	4.5–7.3	FAIR	POOR
BdD	Bedington Shaly Silt Loam	15 to 25%	B	5+	4.5–7.3	FAIR	POOR
BpB	Blairton silt loam	3 to 8%	C	½–3	4.5–5.5	POOR	POOR
BrB	Brinkerton silt loam	3 to 8%	D	0–½	4.5–5.5	POOR	POOR
DuB	Duffield silt loam	3 to 8%	B	5+	5.1–7.3	POOR	FAIR
EdB	Edom silt loam	3 to 8%	B	5+	5.1–7.8	POOR	POOR
EdC	Edom silt loam	8 to 15%	B	5+	5.1–7.8	POOR	POOR
HaA	Hagerstown shaly silt loam	0 to 3%	B	5+	4.5–7.3	POOR	POOR
HaB	Hagerstown shaly silt loam	3 to 8%	B	5+	4.5–7.3	POOR	POOR
Me	Melvin silt loam	0 to 2%	B/D	0–1	6.1–7.3	POOR	POOR
Pe	Penlaw silt loam	0 to 3%	C/D	½–1½	5.6–7.3	POOR	POOR

In general, the soils present should not pose any significant limitation to the type of development proposed. Reference the following recommendation pertaining to possible issues that may be encountered during construction.

- If unrippable rock is encountered during proposed grading, blasting or drilling may be required. Removed rock can be crushed if necessary and used for fill.
- If water table is encountered during excavation, dirty water shall be pumped out into a filter bag or sediment removal pond.
- The NRCS Soil Survey indicates some of the soils have a poor rating for use as road fill. The contractor should use only what soils are suitable for road fill and shall place and compact fill in accordance with standard practice. All road fill must meet Penn DOT Pub. 408 standards.
- Trap/Basin Core material shall be unified class CH or CL soil compacted to 98% of max dry density. Homogeneous embankment material to be compacted in 8" layers to a minimum final density of not less than 98% of max. Dry density within 2% of optimum moisture content. (ASTM Method D1557).
- If sinkhole is encountered during construction contractor and/or owner should immediately consult with a Geotechnical Engineer for guidance on proper sinkhole repair.

Hertzler Road
Unnamed Stream (UNT)
Stream Easement
Existing Culvert "I" 18" RCP Inv in=494.09 Inv out=490.23
Existing Culvert "I" 18" RCP Inv in=494.09 Inv out=490.23
Existing Swale
Existing Phase I Road Taper
BMP
Vegetated Swale
N/F
Allenview Home Owners Association
Deed Book 35, Volume X, Page 953
Map Book 42, Page 69
Tax Parcel 42-28-2423-268
Allen View
Swale P1
Building P
Building C
Building B
Building N
Building O
Building A
Temporary Cul-de-sac (40' dia. pave, 50' R/W)
4' Sidewalk
Proposed Hydrant
LS11-41
LS11-42
LS11-43
LS11-40
LS11-39
LS11-38
LS11-37
LS11-36
LS11-35
LS11-47
LS11-46
LS11-45
LS11-44
LS11-48
LS11-49
LS11-50
A21
A22
A23
A24
A25
A26
A27
A28
A29
A30
A31
A32
A33
A34
A35
A36
A37
A38
A39
A40
A41
A42
A43
A44
A45
A46
A47
A48
A49
A50
A51
A52
A53
A54
A55
A56
A57
A58
A59
A60
A61
A62
A63
A64
A65
A66
A67
A68
A69
A70
A71
A72
A73
A74
A75
A76
A77
A78
A79
A80
A81
A82
A83
A84
A85
A86
A87
A88
A89
A90
A91
A92
A93
A94
A95
A96
A97
A98
A99
A100
A101
A102
A103
A104
A105
A106
A107
A108
A109
A110
A111
A112
A113
A114
A115
A116
A117
A118
A119
A120
A121
A122
A123
A124
A125
A126
A127
A128
A129
A130
A131
A132
A133
A134
A135
A136
A137
A138
A139
A140
A141
A142
A143
A144
A145
A146
A147
A148
A149
A150
A151
A152
A153
A154
A155
A156
A157
A158
A159
A160
A161
A162
A163
A164
A165
A166
A167
A168
A169
A170
A171
A172
A173
A174
A175
A176
A177
A178
A179
A180
A181
A182
A183
A184
A185
A186
A187
A188
A189
A190
A191
A192
A193
A194
A195
A196
A197
A198
A199
A200
A201
A202
A203
A204
A205
A206
A207
A208
A209
A210
A211
A212
A213
A214
A215
A216
A217
A218
A219
A220
A221
A222
A223
A224
A225
A226
A227
A228
A229
A230
A231
A232
A233
A234
A235
A236
A237
A238
A239
A240
A241
A242
A243
A244
A245
A246
A247
A248
A249
A250
A251
A252
A253
A254
A255
A256
A257
A258
A259
A260
A261
A262
A263
A264
A265
A266
A267
A268
A269
A270
A271
A272
A273
A274
A275
A276
A277
A278
A279
A280
A281
A282
A283
A284
A285
A286
A287
A288
A289
A290
A291
A292
A293
A294
A295
A296
A297
A298
A299
A300
A301
A302
A303
A304
A305
A306
A307
A308
A309
A310
A311
A312
A313
A314
A315
A316
A317
A318
A319
A320
A321
A322
A323
A324
A325
A326
A327
A328
A329
A330
A331
A332
A333
A334
A335
A336
A337
A338
A339
A340
A341
A342
A343
A344
A345
A346
A347
A348
A349
A350
A351
A352
A353
A354
A355
A356
A357
A358
A359
A360
A361
A362
A363
A364
A365
A366
A367
A368
A369
A370
A371
A372
A373
A374
A375
A376
A377
A378
A379
A380
A381
A382
A383
A384
A385
A386
A387
A388
A389
A390
A391
A392
A393
A394
A395
A396
A397
A398
A399
A400
A401
A402
A403
A404
A405
A406
A407
A408
A409
A410
A411
A412
A413
A414
A415
A416
A417
A418
A419
A420
A421
A422
A423
A424
A425
A426
A427
A428
A429
A430
A431
A432
A433
A434
A435
A436
A437
A438
A439
A440
A441
A442
A443
A444
A445
A446
A447
A448
A449
A450
A451
A452
A453
A454
A455
A456
A457
A458
A459
A460
A461
A462
A463
A464
A465
A466
A467
A468
A469
A470
A471
A472
A473
A474
A475
A476
A477
A478
A479
A480
A481
A482
A483
A484
A485
A486
A487
A488
A489
A490
A491
A492
A493
A494
A495
A496
A497
A498
A499
A500
A501
A502
A503
A504
A505
A506
A507
A508
A509
A510
A511
A512
A513
A514
A515
A516
A517
A518
A519
A520
A521
A522
A523
A524
A525
A526
A527
A528
A529
A530
A531
A532
A533
A534
A535
A536
A537
A538
A539
A540
A541
A542
A543
A544
A545
A546
A547
A548
A549
A550
A551
A552
A553
A554
A555
A556
A557
A558
A559
A560
A561
A562
A563
A564
A565
A566
A567
A568
A569
A570
A571
A572
A573
A574
A575
A576
A577
A578
A579
A580
A581
A582
A583
A584
A585
A586
A587
A588
A589
A590
A591
A592
A593
A594
A595
A596
A597
A598
A599
A600
A601
A602
A603
A604
A605
A606
A607
A608
A609
A610
A611
A612
A613
A614
A615
A616
A617
A618
A619
A620
A621
A622
A623
A624
A625
A626
A627
A628
A629
A630
A631
A632
A633
A634
A635
A636
A637
A638
A639
A640
A641
A642
A643
A644
A645
A646
A647
A648
A649
A650
A651
A652
A653
A654
A655
A656
A657
A658
A659
A660
A661
A662
A663
A664
A665
A666
A667
A668
A669
A670
A671
A672
A673
A674
A675
A676
A677
A678
A679
A680
A681
A682
A683
A684
A685
A686
A687
A688
A689
A690
A691
A692
A693
A694
A695
A696
A697
A698
A699
A700
A701
A702
A703
A704
A705
A706
A707
A708
A709
A710
A711
A712
A713
A714
A715
A716
A717
A718
A719
A720
A721
A722
A723
A724
A725
A726
A727
A728
A729
A730
A731
A732
A733
A734
A735
A736
A737
A738
A739
A740
A741
A742
A743
A744
A745
A746
A747
A748
A749
A750
A751
A752
A753
A754
A755
A756
A757
A758
A759
A760
A761
A762
A763
A764
A765
A766
A767
A768
A769
A770
A771
A772
A773
A774
A775
A776
A777
A778
A779
A780
A781
A782
A783
A784
A785
A786
A787
A788
A789
A790
A791
A792
A793
A794
A795
A796
A797
A798
A799
A800
A801
A802
A803
A804
A805
A806
A807
A808
A809
A810
A811
A812
A813
A814
A815
A816
A817
A818
A819
A820
A821
A822
A823
A824
A825
A826
A827
A828
A829
A830
A831
A832
A833
A834
A835
A836
A837
A838
A839
A840
A841
A842
A843
A844
A845
A846
A847
A848
A849
A850
A851
A852
A853
A854
A855
A856
A857
A858
A859
A860
A861
A862
A863
A864
A865
A866
A867
A868
A869
A870
A871
A872
A873
A874
A875
A876
A877
A878
A879
A880
A881
A882
A883
A884
A885
A886
A887
A888
A889
A890
A891
A892
A893
A894
A895
A896
A897
A898
A899
A900
A901
A902
A903
A904
A905
A906
A907
A908
A909
A910
A911
A912
A913
A914
A915
A916
A917
A918
A919
A920
A921
A922
A923
A924
A925
A926
A927
A928
A929
A930
A931
A932
A933
A934
A935
A936
A937
A938
A939
A940
A941
A942
A943
A944
A945
A946
A947
A948
A949
A950
A951
A952
A953
A954
A955
A956
A957
A958
A959
A960
A961
A962
A963
A964
A965
A966
A967
A968
A969
A970
A971
A972
A973
A974
A975
A976
A977
A978
A979
A980
A981
A982
A983
A984
A985
A986
A987
A988
A989
A990
A991
A992
A993
A994
A995
A996
A997
A998
A999
A1000
A1001
A1002
A1003
A1004
A1005
A1006
A1007
A1008
A1009
A1010
A1011
A1012
A1013
A1014
A1015
A1016
A1017
A1018
A1019
A1020
A1021
A1022
A1023
A1024
A1025
A1026
A1027
A1028
A1029
A1030
A1031
A1032
A1033
A1034
A1035
A1036
A1037
A1038
A1039
A1040
A1041
A1042
A1043
A1044
A1045
A1046
A1047
A1048
A1049
A1050
A1051
A1052
A1053
A1054
A1055
A1056
A1057
A1058
A1059
A1060
A1061
A1062
A1063
A1064
A1065
A1066
A1067
A1068
A1069
A1070
A1071
A1072
A1073
A1074
A1075
A1076
A1077
A1078
A1079
A1080
A1081
A1082
A1083
A1084
A1085
A1086
A1087
A1088
A1089
A1090
A1091
A1092
A1093
A1094
A1095
A1096
A1097
A1098
A1099
A1100
A1101
A1102
A1103
A1104
A1105
A1106
A1107
A1108
A1109
A1110
A1111
A1112
A1113
A1114
A1115
A1116
A1117
A1118
A1119
A1120
A1121
A1122
A1123
A1124
A1125
A1126
A1127
A1128
A1129
A1130
A1131
A1132
A1133
A1134
A1135
A1136
A1137
A1138
A1139
A1140
A1141
A1142
A1143
A1144
A1145
A1146
A1147
A1148
A1149
A1150
A1151
A1152
A1153
A1154
A1155
A1156
A1157
A1158
A1159
A1160
A1161
A1162
A1163
A1164
A1165
A1166
A1167
A1168
A1169
A1170
A1171
A1172
A1173
A1174
A1175
A1176
A1177
A1178
A1179
A1180
A1181
A1182
A1183
A1184
A1185
A1186
A1187
A1188
A1189
A1190
A1191
A1192
A1193
A1194
A1195
A1196
A1197
A1198
A1199
A1200
A1201
A1202
A1203
A1204
A1205
A1206
A1207
A1208
A1209
A1210
A1211
A1212
A1213
A1214
A1215
A1216
A1217
A1218
A1219
A1220
A1221
A1222
A1223
A1224
A1225
A1226
A1227
A1228
A1229
A1230
A1231
A1232
A1233
A1234
A1235
A1236
A1237
A1238
A1239
A1240
A1241
A1242
A1243
A1244
A1245
A1246
A1247
A1248
A1249
A1250
A1251
A1252
A1253
A1254
A1255
A1256
A1257
A1258
A1259
A1260
A1261
A1262
A1263
A1264
A1265
A1266
A1267
A1268
A1269
A1270
A1271
A1272
A1273
A1274
A1275
A1276
A1277
A1278
A1279
A1280
A1281
A1282
A1283
A1284
A1285
A1286
A1287
A1288
A1289
A1290
A1291
A1292
A1293
A1294
A1295
A1296
A1297
A1298
A1299
A1300
A1301
A1302
A1303
A1304
A1305
A1306
A1307
A1308
A1309
A1310
A1311
A1312
A1313
A1314
A1315
A1316
A1317
A1318
A1319
A1320
A1321
A1322
A1323
A1324
A1325
A1326
A1327
A1328
A1329
A1330
A1331
A1332
A1333
A1334
A1335
A1336
A1337
A1338
A1339
A1340
A1341
A1342
A1343
A1344
A1345
A1346
A1347
A1348
A1349
A1350
A1351
A1352
A1353
A1354
A1355
A1356
A1357
A1358
A1359
A1360
A1361
A1362
A1363
A1364
A1365
A1366
A1367
A1368
A1369
A1370
A1371
A1372
A1373
A1374
A1375
A1376
A1377
A1378
A1379
A1380
A1381
A1382
A1383
A1384
A1385
A1386
A1387
A1388
A1389
A1390
A1391
A1392
A1393
A1394
A1395
A1396
A1397
A1398
A1399
A1400
A1401
A1402
A1403
A1404
A1405
A1406
A1407
A1408
A1409
A1410
A1411
A1412
A1413
A1414
A1415
A1416
A1417
A1418
A1419
A1420
A1421
A1422
A1423
A1424
A1425
A1426
A1427
A1428
A1429
A1430
A1431
A1432
A1433
A1434
A1435
A1436
A1437
A1438
A1439
A1440
A1441
A1442
A1443
A1444
A1445
A1446
A1447
A1448
A1449
A1450
A1451
A1452
A1453
A1454
A1455
A1456
A1457
A1458
A1459
A1460
A1461
A1462
A1463
A1464
A1465
A1466
A1467
A1468
A1469
A1470
A1471
A1472
A1473
A1474
A1475
A1476
A1477
A1478
A1479
A1480
A1481
A1482
A1483
A1484
A1485
A1486
A1487
A1488
A1489
A1490
A1491
A1492
A1493
A1494
A1495
A1496
A1497
A1498
A1499
A1500
A1501
A1502
A1503
A1504
A1505
A1506
A1507
A1508
A1509
A1510
A1511
A1512
A1513
A1514
A1515
A1516
A1517
A1518
A1519
A1520
A1521
A1522
A1523
A1524
A1525
A1526
A1527
A1528
A1529
A1530
A1531
A1532
A1533
A1534
A1535
A1536
A1537
A1538
A1539
A1540
A1541
A1542
A1543
A1544
A1545
A1546
A1547
A1548
A1549
A1550
A1551
A1552
A1553
A1554
A1555
A1556
A1557
A1558
A1559
A1560
A1561
A1562
A1563
A1564
A1565
A1566
A1567
A1568
A1569
A1570
A1571
A1572
A1573
A1574
A1575
A1576
A1577
A1578
A1579
A1580
A1581
A1582
A1583
A1584
A1585
A1586
A1587
A1588
A1589
A1590
A1591
A1592
A1593
A1594
A1595
A1596
A1597
A1598
A1599
A1600
A1601
A1602
A1603
A1604
A1605
A1606
A1607
A1608
A1609
A1610
A1611
A1612
A1613
A1614
A1615
A1616
A1617
A1618
A1619
A1620
A1621
A1622
A1623
A1624
A1625
A1626
A1627
A1628
A1629
A1630
A1631
A1632
A1633
A1634
A1635
A1636
A1637
A1638
A1639
A1640
A1641
A1642
A1643
A1644
A1645
A1646
A1647
A1648
A1649
A1650
A1651
A1652
A1653
A1654
A1655
A1656
A1657
A1658
A1659
A1660
A1661
A1662
A1663
A1664
A1665
A1666
A1667
A1668
A1669
A1670
A1671
A1672
A1673
A1674
A1675
A1676
A1677
A1678
A1679
A1680
A1681
A1682
A1683
A1684
A1685
A1686
A1687
A1688
A1689
A1690
A1691
A1692
A1693
A1694
A1695
A1696
A1697
A1698
A1699
A1700
A1701
A1702
A1703
A1704
A1705
A1706
A1707
A1708
A1709
A1710
A1711
A1712
A1713
A1714
A1715
A1716
A1717
A1718
A1719
A1720
A1721
A1722
A1723
A1724
A1725
A1726
A1727
A1728
A1729
A1730
A1731
A1732
A1733
A1734
A1735
A1736
A1737
A1738
A1739
A1740
A1741
A1742
A1743
A1744
A1745
A1746
A1747
A1748
A1749
A1750
A1751
A1752
A1753
A1754
A1755
A1756
A1757
A1758
A1759
A1760
A1761
A1762
A1763
A1764
A1765
A1766
A1767
A1768
A1769
A1770
A1771
A1772
A1773
A1774
A1775
A1776
A1777
A1778
A1779
A1780
A1781
A1782
A1783
A1784
A1785
A1786
A1787
A1788
A1789
A1790
A1791
A1792
A1793
A1794
A1795
A1796
A1797
A1798
A1799
A1800
A1801
A1802
A1803
A1804
A1805
A1806
A1807
A1808
A1809
A1810
A1811
A1812
A1813
A1814
A1815
A1816
A1817
A1818
A1819
A1820
A1821
A1822
A1823
A1824
A1825
A1826
A1827
A1828
A1829
A1830
A1831
A1832
A1833
A1834
A1835
A1836
A1837
A1838
A1839
A1840
A1841
A1842
A1843
A1844
A1845
A1846
A1847
A1848
A1849
A1850
A1851
A1852
A1853
A1854
A1855
A1856
A1857
A1858
A1859
A1860
A1861
A1862
A1863
A1864
A1865
A1866
A1867
A1868
A1869
A1870
A1871
A1872
A1873
A1874
A1875
A1876
A1877
A1878
A1879
A1880
A1881
A1882
A1883
A1884
A1885
A1886
A1887
A1888
A1889
A1890
A1891
A1892
A1893
A1894
A1895
A1896
A1897
A1898
A1899
A1900
A1901
A1902
A1903
A1904
A1905
A1906
A1907
A1908
A1909
A1910
A1911
A1912
A1913
A1914
A1915
A1916
A1917
A1918
A1919
A1920
A1921
A1922
A1923
A1924
A1925
A1926
A1927
A1928
A1929
A1930
A1931
A1932
A1933
A1934
A1935
A1936
A1937
A1938
A1939
A1940
A1941
A1942
A1943
A1944
A1945
A1946
A1947
A1948
A1949
A1950
A1951
A1952
A1953
A1954
A1955
A1956
A1957
A1958
A1959
A1960
A1961
A1962
A1963
A1964
A1965
A1966
A1967
A1968
A1969
A1970
A1971
A1972
A1973
A1974
A1975
A1976
A1977
A1978
A1979
A1980
A1981
A1982
A1983
A1984
A1985
A1986
A1987
A1988
A1989
A1990
A1991
A1992
A1993
A1994
A1995
A1996
A1997
A1998
A1999
A2000
A2001
A2002
A2003
A2004
A2005
A2006
A2007
A2008
A2009
A2010
A2011
A2012
A2013
A2014
A2015
A2016
A2017
A2018
A2019
A2020
A2021
A2022
A2023
A2024
A2025
A2026
A2027
A2028
A2029
A2030
A2031
A2032
A2033
A2034
A2035
A2036
A2037
A2038
A2039
A2040
A2041
A2042
A2043
A2044
A2045
A2046
A2047
A2048
A2049
A2050
A2051
A2052
A2053
A2054
A2055
A2056
A2057
A2058
A2059
A2060
A2061
A2062
A2063
A2064
A2065
A2066
A2067
A2068
A2069
A2070
A2071
A2072
A2073
A2074
A2075
A2076
A2077
A2078
A2079
A2080
A2081
A2082
A2083
A2084
A2085
A2086
A2087
A2088
A2089
A2090
A2091
A2092
A2093
A2094
A2095
A2096
A2097
A2098
A2099
A2100
A2101
A2102
A2103
A2104
A2105
A2106
A2107
A2108
A2109
A2110
A2111
A2112
A2113
A2114
A2115
A2116
A2117
A2118
A2119
A2120
A2121
A2122
A2123
A2124
A2125
A2126
A2127
A2128
A2129
A2130
A2131
A2132
A2133
A2134
A2135
A2136
A2137
A2138
A2139
A2140
A2141
A2142
A2143
A2144
A2145
A2146
A2147
A2148
A2149
A2150
A2151
A2152
A2153
A2154
A2155
A2156
A2157
A2158
A2159
A2160
A2161
A2162
A2163
A2164
A2165
A2166
A2167
A2168
A2169
A2170
A2171
A2172
A2173
A2174
A2175
A2176
A2177
A2178
A2179
A2180
A2181
A2182
A2183
A2184
A2185
A2186
A2187
A2188
A2189
A2190
A2191
A2192
A2193
A2194
A2195
A2196
A2197
A2198
A2199
A2200
A2201
A2202
A2203
A2204
A2205
A2206
A2207
A2208
A2209
A2210
A2211
A2212
A2213
A2214
A2215
A2216
A2217
A2218
A2219
A2220
A2221
A2222
A2223
A2224
A2225
A2226
A2227
A2228
A2229
A2230
A2231
A2232
A2233
A2234
A2235
A2236
A2237
A2238
A2239
A2240
A2241
A2242
A2243
A2244
A2245
A2246
A2247
A2248
A2249
A2250
A2251
A2252
A2253
A2254
A2255
A2256
A2257
A2258
A2259
A2260
A2261
A2262
A2263
A2264
A2265
A2266
A2267
A2268
A2269
A2270
A2271
A2272
A2273
A2274
A2275
A2276
A2277
A2278
A2279
A2280
A2281
A2282
A2283
A2284
A2285
A2286
A2287
A2288
A2289
A2290
A2291
A2292
A2293
A2294
A2295
A2296
A2297
A2298
A2299
A2300
A2301
A2302
A2303
A2304
A2305
A2306
A2307
A2308
A2309
A2310
A2311
A2312
A2313
A2314
A2315
A2316
A2317
A2318
A2319
A2320
A2321
A2322
A2323
A2324
A2325
A2326
A2327
A2328
A2329
A2330
A2331
A2332
A2333
A2334
A2335
A2336
A2337
A2338
A2339
A2340
A2341
A2342
A2343
A2344
A2345
A2346
A2347
A2348
A2349
A2350
A2351
A2352
A2353
A2354
A2355
A2356
A2357
A2358
A2359
A2360
A2361
A2362
A2363
A2364
A2365
A2366
A2367
A2368
A2369
A2370
A2371
A2372
A2373
A2374
A2375
A2376
A2377
A2378
A2379
A2380
A2381
A2382
A2383
A2384
A2385
A2386
A2387
A2388
A2389
A2390
A2391
A2392
A2393
A2394
A2395
A2396
A2397
A2398
A2399
A2400
A2401
A2402
A2403
A2404
A2405
A2406
A2407
A2408
A2409
A2410
A2411
A2412
A2413
A2414
A2415
A2416
A2417
A2418
A2419
A2420
A2421
A2422
A2423
A2424
A2425
A2426
A2427
A2428
A2429
A2430
A2431
A2432
A2433
A2434
A2435
A2436
A2437
A2438
A2439
A2440
A2441
A2442
A2443
A2444
A2445
A2446
A2447
A2448
A2449
A2450
A2451
A2452
A2453
A2454
A2455
A2456
A2457
A2458
A2459
A2460
A2461
A2462
A2463
A2464
A2465
A2466
A2467
A2468
A2469
A2470
A2471
A2472
A2473
A2474
A2475
A2476
A2477
A2478
A2479
A2480
A2481
A2482
A2483
A2484
A2485
A2486
A2487
A2488
A2489
A2490
A2491
A2492
A2493
A2494
A2495
A2496
A2497
A2498
A2499
A2500
A2501
A2502
A2503
A2504
A2505
A2506
A2507
A2508
A2509
A2510
A2511
A2512
A2513
A2514
A2515
A2516
A2517
A2518
A2519
A2520
A2521
A2522
A2523
A2524
A2525
A2526
A2527
A2528
A2529
A2530
A2531
A2532
A2533
A2534
A2535
A2536
A2537
A2538
A2539
A2540
A2541
A2542
A2543
A2544
A2545
A2546
A2547
A2548
A2549
A2550
A2551
A2552
A2553
A2554
A2555
A2556
A2557
A2558
A2559
A2560
A2561
A2562
A2563
A2564
A2565
A2566
A2567
A2568
A2569
A2570
A2571
A2572
A2573
A2574
A2575
A2576
A2577
A2578
A2579
A2580
A2581
A2582
A2583
A2584
A2585
A2586
A2587
A2588
A2589
A2590
A2591
A2592
A2593
A2594
A2595
A2596
A2597
A2598
A2599
A2600
A2601
A2602
A2603
A2604
A2605
A2606
A2607
A2608
A2609
A2610
A2611
A2612
A2613
A2614
A2615
A2616
A2617
A2618
A2619
A2620
A2621
A2622
A2623
A2624
A2625
A2626
A2627
A2628
A2629
A2630
A2631
A2632
A2633
A2634
A2635
A2636
A2637
A2638
A2639
A2640
A2641
A2642
A2643
A2644
A2645
A2646
A2647
A2648
A2649
A2650
A2651
A2652
A2653
A2654
A2655
A2656
A2657
A2658
A2659
A2660
A2661
A2662
A2663
A2664
A2665
A2666
A2667
A2668
A2669
A2670
A2671
A2672
A2673
A2674
A2675
A2676
A2677
A2678
A2679
A2680
A2681
A2682
A2683
A2684
A2685
A2686
A2687
A2688
A2689
A2690
A2691
A2692
A2693
A2694
A2695
A2696
A2697
A2698
A2699
A2700
A2701
A2702
A2703
A2704
A2705
A2706
A2707
A2708
A2709
A2710
A2711
A2712
A2713
A2714
A2715
A2716
A2717
A2718
A2719
A2720
A2721
A2722
A2723
A2724
A2725
A2726
A2727
A2728
A2729
A2730
A2731
A2732
A2733
A2734
A2735
A2736
A2737
A2738
A2739
A2740
A2741
A2742
A2743
A2744
A2745
A2746
A2747
A2748
A2749
A2750
A2751
A2752
A2753
A2754
A2755
A2756
A2757
A2758
A2759
A2760
A2761
A2762
A2763
A2764
A2765
A2766
A2767
A2768
A2769
A2770
A2771
A2772
A2773
A2774
A2775
A2776
A2777
A2778
A2779
A2780
A2781
A2782
A2783
A2784
A2785
A2786
A2787
A2788
A2789
A2790
A2791
A2792
A2793
A2794
A2795
A2796
A2797
A2798
A2799
A2800
A2801
A2802
A2803
A2804
A2805
A2806
A2807
A2808
A2809
A2810
A2811
A2812
A2813
A2814
A2815
A2816
A2817
A2818
A2819
A2820
A2821
A2822
A2823
A2824
A2825
A2826
A2827
A2828
A2829
A2830
A2831
A2832
A2833
A2834
A2835
A2836
A2837
A2838
A2839
A2840
A2841
A2842
A2843
A2844
A2845
A2846
A2847
A2848
A2849
A2850
A2851
A2852
A2853
A2854
A2855
A2856
A2857
A2858
A2859
A2860
A2861
A2862
A2863
A2864
A2865
A2866
A2867
A2868
A2869
A2870
A2871
A2872
A2873
A2874
A2875
A2876
A2877
A2878
A2879
A2880
A2881
A2882
A2883
A2884
A2885
A2886
A2887
A2888
A2889
A2890
A2891
A2892
A2893
A2894
A2895
A2896
A2897
A2898
A2899
A2900
A2901
A2902
A2903
A2904
A2905
A2906
A2907
A2908
A2909
A2910
A2911
A2912
A2913
A2914
A2915
A2916
A2917
A2918
A2919
A2920
A2921
A2922
A2923
A2924
A2925
A2926
A2927
A2928
A2929
A2930
A2931
A2932
A2933
A2934
A2935
A2936
A2937
A2938
A2939
A2940
A2941
A2942
A2943
A2944
A2945
A2946
A2947
A2948
A2949
A2950
A2951
A2952
A2953
A2954
A2955
A2956
A2957
A2958
A2959
A2960
A2961
A2962
A2963
A2964
A2965
A2966
A2967
A2968
A2969
A2970
A2971
A2972
A2973
A2974
A2975
A2976
A2977
A2978
A2979
A2980
A2981
A2982
A2983
A2984
A2985
A2986
A2987
A2988
A2989
A2990
A2991
A2992
A2993
A2994
A2995
A2996
A2997
A2998
A2999
A3000
A3001
A3002
A3003
A3004
A3005
A3006
A3007
A3008
A3009
A3010
A3011
A3012
A3013
A3014
A3015
A3016
A3017
A3018
A3019
A3020
A3021
A3022
A3023
A3024
A3025
A3026
A3027
A3028
A3029
A3030
A3031
A3032
A3033
A3034
A3035
A3036
A3037
A3038
A3039
A3040
A3041
A3042
A3043
A3044
A3045
A3046
A3047
A3048
A3049
A3050
A3051
A3052
A3053
A3054
A3055
A3056
A3057
A3058
A3059
A3060
A3061
A3062
A3063
A3064
A3065
A3066
A3067
A3068
A3069
A3070
A3071
A3072
A3073
A3074
A3075
A3076
A3077
A3078
A3079
A3080
A3081
A3082
A3083
A3084
A3085
A3086
A3087
A3088
A3089
A3090
A3091
A3092
A3093
A3094
A3095
A3096
A3097
A3098
A3099
A3100
A3101
A3102
A3103
A3104
A3105
A3106
A3107
A3108
A3109
A3110
A3111
A3112
A3113
A3114
A3115
A3116
A3117
A3118
A3119
A3120
A3121
A3122
A3123
A3124
A3125
A3126
A3127
A3128
A3129
A3130
A3131
A3132
A3133
A3134
A3135
A3136
A3137
A3138
A3139
A3140
A3141
A3142
A3143
A3144
A3145
A3146
A3147
A3148
A3149
A3150
A3151
A3152
A3153
A3154
A3155
A3156
A3157
A3158
A3159
A3160
A3161
A3162
A3163
A3164
A3165
A3166
A3167
A3168
A3169
A3170
A3171
A3172
A3173
A3174
A3175
A3176
A3177
A3178
A3179
A3180
A3181
A3182
A3183
A3184
A3185
A3186
A3187
A3188
A3189
A3190
A3191
A3192
A3193
A3194
A3195
A3196
A3197
A3198
A3199
A3200
A3201
A3202
A3203
A3204
A3205
A3206
A3207
A3208
A3209
A3210
A3211
A3212
A3213
A3214
A3215
A3216
A3217
A3218
A3219
A3220
A3221
A3222
A3223
A3224
A3225
A3226
A3227
A3228
A3229
A3230
A3231
A3232
A3233
A3234
A3235
A3236
A3237
A3238
A3239
A3240
A3241
A3242
A3243
A3244
A3245
A3246
A3247
A3248
A3249
A3250
A3251
A3252
A3253
A3254
A3255
A3256
A3257
A3258
A3259
A3260
A3261
A3262
A3263
A3264
A3265
A3266
A3267
A3268
A3269
A3270
A3271
A3272
A3273
A3274
A3275
A3276
A3277
A3278
A3279
A3280
A3281
A3282
A3283
A3284
A3285
A3286
A3287
A3288
A3289
A3290
A3291
A3292
A3293
A3294
A3295
A3296
A3297
A3298
A3299
A3300
A3301
A3302
A3303
A3304
A3305
A3306
A3307
A3308
A3309
A3310
A3311
A3312
A3313
A3314
A3315
A3316
A3317
A3318
A3319
A3320
A3321
A3322
A3323
A3324
A3325
A3326
A3327
A3328
A3329
A3330
A3331
A3332
A3333
A3334
A3335
A3336
A3337
A3338
A3339
A3340
A3341
A3342
A3343
A3344
A3345
A3346
A3347
A3348
A3349
A3350
A3351
A3352
A3353
A3354
A3355
A3356
A3357
A3358
A3359
A3360
A3361
A3362
A3363
A3364
A3365
A3366
A3367
A3368
A3369
A3370
A3371
A3372
A3373
A3374
A3375
A3376
A3377
A3378
A3379
A3380
A3381
A3382
A3383
A3384
A3385
A3386
A3387
A3388
A3389
A3390
A3391
A3392
A3393
A3394
A3395
A3396
A3397
A3398
A3399
A3400
A3401
A3402
A3403
A3404
A3405
A3406
A3407
A3408
A3409
A3410
A3411
A3412
A3413
A3414
A3415
A3416
A3417
A3418
A3419
A3420
A3421
A3422
A3423
A3424
A3425
A3426
A3427
A3428
A3429
A3430
A3431
A3432
A3433
A3434
A3435
A3436
A3437
A3438
A3439
A3440
A3441
A3442
A3443
A3444
A3445
A3446
A3447
A3448
A3449
A3450
A3451
A3452
A3453
A3454
A3455
A3456
A3457
A3458
A3459
A3460
A3461
A3462
A3463
A3464
A3465
A3466
A3467
A3468
A3469
A3470
A3471
A3472
A3473
A3474
A3475
A3476
A3477
A3478
A3479
A3480
A3481
A3482
A3483
A3484
A3485
A3486
A3487
A3488
A3489
A3490
A3491
A3492
A3493
A3494
A3495
A3496
A3497
A3498
A3499
A3500
A3501
A3502
A3503
A3504
A3505
A3506
A3507
A3508
A3509
A3510
A3511
A3512
A3513
A3514
A3515
A3516
A3517
A3518
A3519
A3520
A3521
A3522
A3523
A3524
A3525
A3526
A3527
A3528
A3529
A3530
A3531
A3532
A3533
A3534
A3535
A3536
A3537
A3538
A3539
A3540
A3541
A3542
A3543
A3544
A3545
A3546
A3547
A3548
A3549
A3550
A3551
A3552
A3553
A3554
A3555
A3556
A3557
A3558
A3559
A3560
A3561
A3562
A3563
A3564
A3565
A3566
A3567
A3568
A3569
A3570
A3571
A3572
A3573
A3574
A3575
A3576
A3577
A3578
A3579
A3580
A3581
A3582
A3583
A3584
A3585
A3586
A3587
A3588
A3589
A3590
A3591
A3592
A3593
A3594
A3595
A3596
A3597
A3598
A3599
A3600
A3601
A3602
A3603
A3604
A3605
A3606
A3607
A3608
A3609
A3610
A3611
A3612
A3613
A3614
A3615
A3616
A3617
A3618
A3619
A3620
A3621
A3622
A3623
A3624
A3625
A3626
A3627
A3628
A3629
A3630
A3631
A3632
A3633
A3634
A3635
A3636
A3637
A3638
A3639
A3640
A3641
A3642
A3643
A3644
A3645
A3646
A3647
A3648
A3649
A3650
A3651
A3652
A3653
A3654
A3655
A3656
A3657
A3658
A3659
A3660
A3661
A3662
A3663
A3664
A3665
A3666
A3667
A3668
A3669
A3670
A3671
A3672
A3673
A3674
A3675
A3676
A3677
A3678
A3679
A3680
A3681
A3682
A3683
A3684
A3685
A3686
A3687
A3688
A3689
A3690
A3691
A3692
A3693
A3694
A3695
A3696
A3697
A3698
A3699
A3700
A3701
A3702
A3703
A3704
A3705
A3706
A3707
A3708
A3709
A3710
A3711
A3712
A3713
A3714
A3715
A3716
A3717
A3718
A3719
A3720
A3721
A3722
A3723
A3724
A3725
A3726
A3727
A3728
A3729
A3730
A3731
A3732
A3733
A3734
A3735
A3736
A3737
A3738
A3739
A3740
A3741
A3742
A3743
A3744
A3745
A3746
A3747
A3748
A3749
A3750
A3751
A3752
A3753
A3754
A3755
A3756
A3757
A

OPERATION AND MAINTENANCE NOTES

BMPs Inspection and Maintenance Requirements
The property owner on which the stormwater facilities are located shall be responsible for operation and maintenance of the on-lot SWM BMP facilities consistent with the Operation and Maintenance Plan for the project and in accordance with the "Operation & Maintenance Agreement Stormwater Management Best Management Practices". The Home Owners Association shall be responsible for the Operation and Maintenance of all stormwater facilities located outside of a public right of way excluding individual on lot infiltration beds and/or rain gardens which shall be owned and maintained by the respective property owner (only roof area not draining to a Basin requires an infiltration bed and/or rain garden, see plan for applicable lots).

Description of Operation and Maintenance Requirements
The following inspection and maintenance activities shall be performed on a regular basis; bi-monthly during mowing months, monthly on non mowing months and within 48 hours after a major storm event: (> 1 inch rainfall depth). In addition to the following see the Township Inspection Reporting requirements following the below list:

Bioretention-Detention Basins
1. Basin outlet structures shall be routinely inspected to verify the orifices and/or grate top are not clogged. Remove any accumulated debris from the outlet structure.
2. Emergency Spillways shall be routinely inspected for erosion. Bare soil shall be stabilized with topsoil, seeding and permanent liner as detailed.
3. All trash and debris should be regularly removed from basins and upslope areas.
4. Reseed bare areas; install appropriate erosion control measures when native soil is exposed.
5. Mow or trim vegetation to maintain vegetation lengths as required by Township. Stormwater Management Basin bottoms are planted with a wetland-type basin seed mix to aid in filtering and treatment of stormwater runoff. The basin bottoms may be trimmed for aesthetics and to remove debris and inspect for damage; however, the bottom areas shall not be mowed.
6. Basins shall be inspected at time of mowing for invasive weeds, large shrubs and trees (no mowing of basin bottom, see above note). Remove such undesirable invasive vegetation as necessary.
7. Basin Embankment and surrounding areas shall be free of burrowing animals in order to protect the structural integrity of the stormwater facility.
8. All piping inlet and outlet structures shall be free of holes, cracks, seepage, leakage or other defects.
9. Inspect of Basin dewatering times: All basins are to fully dewater within 72 hours of the completion of a rain event. If standing water remains in a basin after maximum allowable 72 hours dewatering time the Home Owners Associated shall contact the site engineer for an inspection. The following remediation measures should be implemented if it is believed the upper topsoil/amendment mixture (12" layer) is the limiting factor: chisel plow the top surface layer to maximum depth practical, smooth out surface followed by stabilization with intended retentive basin seed mixture. The following remediation measures should be implemented if it is believed the subsoils (soil horizon below topsoil/amendments layer) is the limiting factor: remove and stockpile top soil/amendment layer (12" layer), chisel plow the subsoils to maximum depth practical, place the topsoil/amendment mixture over the remediated subsoils, smooth out surface followed by stabilization with intended retentive basin seed mixture.

Vegetated Swales
1. Swales shall be inspected for erosion. Any erosion shall be immediately stabilized with topsoil, seeding and liner accordingly.
2. All trash and debris should be regularly removed from swales and upslope areas.
3. Mow and trim vegetation to ensure safety, aesthetics, proper swale operation, or to suppress weeds and invasive vegetation; mow only when swale is dry to avoid rutting.

Storm Sewer System & Riprap Aprons (Located outside of public right of ways)
1. All inlets and the surrounding areas shall be free of all obstructions, spent liquids such as oils, fuels, petroleum products, antifreeze, sediment, grease, trash and debris.
2. All riprap aprons shall be inspected and reestablished if needed.

PROPERTY OWNERSHIP O&M & TOWNSHIP RIGHT OF ENTRY NOTE
The property owner on which the stormwater facilities are located shall be responsible for operation and maintenance of the on-lot facilities consistent with the Operation and Maintenance Plan associated with the project. In the event that the responsible person or entity fails to do so, the owner hereby grants to Upper Allen Township the right but not the duty to enter upon the premises to repair or restore said facilities, to charge and assess the costs thereof to the owner, and to enforce said charges and assessments by lien upon the property. In addition, the deed for the applicable lots shall contain a covenant binding the grantee and all successors' title and interest designating the responsibility for operation and maintenance of the on-lot facilities.

The Owner shall agree that no action will be taken to block or impede the passage of water through said stormwater management facilities and will place no structure, building, or fence, nor plant any trees or shrubs which would impede the use of said facilities for its intended purposes, without prior approval from the Township.

Current Property Owner/Responsible Party
The current owner (Hertzler Road Associates, L.P.), or any succeeding owner or any succeeding owner(s), has a legal duty to maintain the stormwater and drainage facilities as detailed above and in accordance with the associated Stormwater O&M Agreement.

PERMANENT SEEDING


A. All disturbed soil not to be covered with impervious surfaces, riprap or landscaping mulch shall be permanently seeded to provide protection against the impact of precipitation, running water and wind.
B. Mulching shall be used to protect seeding and help in preventing runoff. Clean straw mulch shall be required in all disturbed areas and applied at a rate of 3 tons/acre (equivalent to 0.75" to 1" deep). Clean straw mulch should not be finely chopped nor broken during application.

Maintenance procedure:
1) Maintain a minimum 70% soil surface coverage with grass and/or mulch.
2) If a washout, slope failure or similar disturbance occurs, correct drainage problem if necessary, then reapply soil to the proper grade, reapply soil amendments, seed and mulch.


Permanent seeding schedule is as follows:
For gentle lawn areas
Species: 40% Kentucky Bluegrass
40% Pennlawn Creeping Red Fescue
20% Norlea Perennial Ryegrass


For Swales, steep slopes and wet areas: 100% Tall Fescue, varieties such as K-31, Altra,
or other recently released dwarf variety
% Pure live seed: 98%
Application rate: 6 lbs./1000 sq. ft.
Fertilizer type: general purpose granular, 10-20-20
Fertilizer application rate: 1000 lbs per acre
Liming rate: Four (4) tons per acre of agricultural grade lime
Strawbale mulch rate: three (3) tons per acre
Seeding dates: Between 4/1 and 10/15

STORMWATER INLETS
All inlets located in the street shall be PennDOT Type "C" inlets with 8" hoods and all inlets in grass areas shall be Type "M" inlets.




PPADOT TYPE C INLET TO (8" HOOD)






PPADOT TYPE M INLET
N.T.S.



NOTES:
1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH PENN DOT PUBLICATION 408, SECTION 714 AND STANDARDS FOR ROADWAY CONSTRUCTION, RC-34. CONTRACTOR SHALL VERIFY INLET BOX SIZING BASED ON PIPE SIZES AND ALIGNMENT PRIOR TO ORDERING PRECAST STRUCTURES. STRUCTURE SHALL BE CERTIFIED FOR H20 LOADING.
2. ALL DRAINAGE STRUCTURES SHALL HAVE POURED-IN-PLACE CONCRETE CHANNEL BOTTOMS.
3. ALL INLETS TO HAVE PENN DOT TYPE BICYCLE SAFE GRATES.
4. PROVIDE WEEP HOLES IN ALL INLET BOXES @ SUBGRADE TO ALLOW FOR DRAINAGE DURING CONSTRUCTION.
5. OPENINGS SHALL BE PROVIDED WHERE NECESSARY FOR PAVEMENT BASEDRAIN TIE-IN.
6. INLETS SHALL NOT HAVE A SUMP CONDITION IN THE BOTTOM. PIPES SHALL BE FLUSH WITH THE BOTTOM OF THE BOX OR CONCRETE CHANNELS SHALL BE POURED. SUMPED INLETS MAY BE PERMITTED WHERE SPECIFICALLY UTILIZED FOR WATER QUALITY PURPOSE.
7. INLETS MUST BE SIZED TO ACCEPT THE SPECIFIED PIPE SIZES WITHOUT KNOCKING OUT ANY INLET CORNERS.
8. ANY INLETS OR JUNCTION BOXES OVER FIVE FEET IN DEPTH SHALL BE EQUIPPED WITH LADDER RIGS.


STORM INLET DETAILS



NOTES:
1. THIS DETAIL IS A GENERAL REPAIR MEASURE FOR SINKHOLES. ALL ROCK SIZES AND DEPTHS ARE SUBJECT TO THE SIZE AND CONDITIONS OF THE SPECIFIC SINKHOLE. AS SUCH THE EXACT REPAIR FOR EACH SINKOLE ENCOUNTERED SHALL BE PER THE RECOMMENEDATION OF A GEOTECHNICAL ENGINEER. CONTRACTOR MUST COORDINATE WITH A GEOTECHNICAL ENGINEER FOR TO OBTAIN INSTRUCTIONS ON PROPER REPAIR MEASURES TO IMPLEMENT.
2. REASONABLE EFFORTS SHOULD BE MADE TO EXCAVATE ALL LOOSE AND UNSTABLE SOILS FROM THE BASE OF THE SINKHOLE (I.E. THROAT)
3. FLOWABLE FILL,IF USED,SHOULD BE ALLOWED TO CURE FOR A MINIMUM OF 24 HOURS PRIOR TO THE PLACEMENT OF THE FOLLOWING LAYERS WITHIN THE INVERTED FILTER.
4. THE FINAL LAYER OF STRUCTURAL FILL SHOULD BE PLACED IN LOOSE 12" LIFTS AND COMPACTED TO A MINIMUM OF 95% OF THE SOIL'S MAXIMUM MODIFIED DRY DENSITY.
5. INSTALLATION OF THE INVERTED FILTER SHOULD BE COMPLETED UNDER THE DIRECTION OF THE GEOTECHNICAL ENGINEER..


The repairs outlined above are general guidelines and each sinkhole occurrence should thoroughly be reviewed by the Geotechnical Engineer of Record for an appropriate remediation plan.


INVERTED FILTER SINKHOLE REPAIR DETAIL
NO SCALE




NOTE:
1. USE THIS DETAIL FOR TRENCH RESTORATION OUTSIDE OF EXISTING PAVED AREAS.
2. ALL MATERIALS AND INSTALLATION PROCEDURES SHALL CONFORM TO PENN DOT PUBLICATION 408, MOST RECENT AMENDMENT.
*3. BACKFILL MAY COMPACTED IN 8" LIFTS IF VIBRATORY EQUIPMENT IS USED.

STORM SEWER DETAIL FOR TRENCHES IN GRASSED AREAS OR NEW PAVEMENT
NTS







CHANNEL CROSS-SECTION

* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

	SWALE DESIGNATION	CHANNEL SLOPE (%)	Z1	Z2	BW (FT.)	D (MIN.) (FT.)	TW (MIN.) (FT.)	TEMPORARY LINING	PERMANENT LINING
Stage 1 (Phase II)	P1	8	3	3	4	1.1	10.6	N.A.G. C350	N.A.G. C350/CLASS D VEG.
	P2	2	3	3	3	2.0	15.0	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P2a	20	3	3	10	1.1	16.6	N.A.G. P300	N.A.G. P300/CLASS C VEG.
	P3	10	3	3	4	1.2	11.2	N.A.G. P550	N.A.G. P550/CLASS D VEG.
	P4	10	3	3	2	1.5	11	N.A.G. C350	N.A.G. C350/CLASS D VEG.
	*Ex. Hertzler	4	3	3	2	1.2	9.2	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	**T1	4	3	3	4	1.2	11.2	N.A.G. P300	N.A.G. P300/CLASS D VEG.


* Hertzler Road swale exist although data provided for reconstruction if needed in future.
** Temporary swale T1 shall receive swale P3 runoff until future phase construction
N.A.G. = North American Green Product (permanent liners)

NOTES:
ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL ANCHOR TRENCHES. CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED.

CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION. SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.

NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

STANDARD CONSTRUCTION DETAIL #6-1
VEGETATED CHANNEL



Outlet No.	Pipe Dia. Do (in)	Tail Water Condition (Max/Min)	Man. "n" For Pipe	Pipe Slope (%)	*Q (cfs)	**V (fps)	Riprap Size	Rt (in)	Ai (ft)	Aiw (ft)	Atw (ft)
A1	30	Min	0.012	2.50	41.5	9.2	R-5	27	23	6	29
A10	24	Min	0.012	2.00	32.4	11.2	R-5	27	16	6	22
***A27	42	Min	0.012	1.00	57	11.3	R-5	27	22	10.5	32.5
A25	18	Min	0.012	1.00	7.3	8.0	R-4	18	8	4.5	12.5
****F1	36	Min	0.012	0.01	47	10.9	R-5	27	20	9.0	29.0


* 100 Year storm event
** The anticipated velocity (V) should not exceed the maximum permissible shown in Table 6.6 for the proposed riprap protection. Adjust for less than full pipe flow. Use Manning's equation to calculate velocity for pipe slopes > 9.05 ft/ft.
***A27 apron includes flow from A29 as well; discharge to same conservatively designed apron.
***** F1 apron exist. Original design reflected above; now received reduced basin discharges.

EW = Concrete End Wall (RC-31M)
ES = Plastic End Section (RC-33M)

NOTES:
ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS.

ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.

STANDARD CONSTRUCTION DETAIL #9-1
RIPRAP APRON AT PIPE OUTLET
WITH FLARED END SECTION OR ENDWALL



BASIN OUTLET	# COLLARS	W (ft)
4A	3	6
4B	2	5
5	2	6
6	2	5

Phase II
Phase II
Future Phase
Future Phase

Basin 4B anti-seep collars shall be installed outside of the street right of way between the outlet structure and inlet A4.

GENERAL NOTES
1. INSTALL COLLARS INSIDE OF EMBANKMENT CORE.
2. ANTI-SEEP COLLAR AND CONNECTION TO THE PIPE (BARREL) MUST BE WATERTIGHT.
3. COLLARS SHOULD NOT BE LOCATED CLOSER THAN 2 FEET TO A PIPE JOINT.

ANTI-SEEP COLLAR DETAIL
N.T.S.

INSTALLATION INSTRUCTIONS:
APPLY TAR OR MASTIC TO COLLAR AND LAY PIPE ON COLLAR; APPLY MASTIC TO TOP HALF OF COLLAR AND SET IN PLACE LINING UP RED STRIPES AND BOLT TWO HALVES TOGETHER. INSTALL METAL BANDS ON SPLIT HALVES OF COLLAR; TIGHTEN BOLTS AND BANDS. APPLY MASTIC AS NEEDED TO INSURE GOOD WATERTIGHT SEAL. BACKFILL AND TAMP ACCORDINGLY. ABOVE PRODUCT CAN BE PURCHASED FROM SCHEIB PRODUCTS (660-446-2343); EQUIVALENT PRODUCT CAN BE USED.

BIO-RETENTION BASIN SEEDING


In an effort to improve water quality of surface water runoff and increase infiltration the following special seed mix is proposed for all Basins.

Retention Basin Floor Seeding - Low Maintenance
(ERNMX-126 by Ernst Conservation Seeds 1-800-873-3321)


Percent Composition	Common Name	Scientific Name
20%	Redtop	Agrostis Alba (A. gigantea)
20%	Virginia Wild Rye, PA Ecotype	Elymus virginicus, PA Ecotype
20%	Nuttal's Alkaligrass	Puccinellilea nuttalliana
15%	Fox Sedge, PA Ecotype	Carex vulpinoidea, PA Ecotype
10%	Creeping Bentgrass	Agrostis stolonifera
10%	Fowl Bluegrass	Poa palustris
2%	Autumn Bentgrass, APB	Agrostis perennans, APB
2%	Tickle grass (Rough Bentgrass), PA Ecotype	Agrostis scabra, PA Ecotype
1%	Path Rush, PA Ecotype	Juncus tenius, PA Ecotype

Recommended seeding rate: 20-40 lbs/acre


TRASH RACK TABLE				
REFERENCE	*(A)	(B)	(C)	(D)
REFERENCE	1 1/2"	9"	6"	12"



LOW FLOW ORIFICE SCREEN DETAIL




EMERGENCY SPILLWAY DETAIL
N.T.S.



NOTES:
1. CONSTRUCT OUTLET STRUCTURE IN ACCORDANCE WITH PENN DOT STANDARDS, RC-34 FOR PRECAST CONCRETE INLETS.
2. BOTTOM ORIFICE SHALL BE PROTECTED BY LOW FLOW ORIFICE TRASH RACK AND ALL HIGHER ORIFICES (IF APPLICABLE) SHALL BE PROVIDED WITH BAR RACKS (SEE DETAILS).

STORMWATER BASIN OUTLET STRUCTURE DETAIL
N.T.S.



NOTES
1. CORE MATERIAL SHALL BE UNIFIED CLASS CH OR CL SOIL COMPACTED TO 95% OF MAX. HOMOGENEOUS EMBANKMENT MATERIAL TO BE COMPACTED IN 8" LAYERS TO A MINIMUM FINAL DENSITY OF NOT LESS THAN 95% OF MAX. DRY DENSITY WITHIN 2% ± OPTIMUM MOISTURE CONTENT. (ASTM METHOD D698).

BASIN SECTION AT OUTLET
N.T.S.

SOIL AMENDMENT MIXTURE TO BE A WELL BLENDED SANDY LOAM TOPSOIL WITH MIN. 5% SAND. ORGANIC MATTER (COMPOST) SHALL COMPRISE 30% NATIVE TOPSOIL TO COMPRISE 65% (See Sequence Notes)

Critical Stage of Construction (Basin Conversions): After up slope contributing areas are permanently stabilized and after receiving authorization from a Conservation District representative Basins/Trap shall be converted to the permanent stormwater basin configurations. Install 12" compost sock around outlet structure to provide for filtering during final stabilization process. Soil restoration and amendments of the Stormwater Basin bottoms shall be provided at time of conversion. The basin bottom preparation consists of over excavating the basin bottoms to 12" below finished grade, scarification/till the subgrade bottom (10" depth desired). Place 12" of the amended soils mixture over the prepared (tilled) basin bottom followed by stabilization with intended basin seed mixture and mulch. The scarification/tiling of the subsoils is intended to enhance permeability of the subsoils and to provide increased interface between the subsoils and the amended soils mixture and the amended soils mixture will promote infiltration and enhance vegetation growth. Compost sock around the outlet structure can be removed after the basin bottom is fully vegetated/stabilized.

	BASIN ID	TOP OF BERM A	TOP OF BERM B	BOTTOM C	EMERGENCY SPILLWAY D	EMERGENCY SPILLWAY E	EMERGENCY SPILLWAY LINING	DISCHARGE F	DISCHARGE PIPE	DISCHARGE G	ORIFICE(s) SIZE (H)	ORIFICE(s) ELEV. (H)	ORIFICE(s) SIZE (I)	ORIFICE(s) ELEV. (I)	OUTLET STRUCTURE GRATE (J)
Phase 2	4A	466.0	8'	457.5	464.5	175'	* SC250	455.8	80'-36" HDPE @ 1.00%	455.0	3" Dia.	457.8	48"Wx6"H	462.0	**463.5 (24"x72")
Phase 2	4B	474.0	8'	469.0	472.6	130'	* SC250	467.5	50'-24" HDPE @ 2.00%	466.5	3" Dia.	469.3	–	–	**471.8 (24"x72")
Future Phase	5	468.0	8'	463.0	466.5	320'	* SC250	460.8	60'-36" HDPE @ 1.00%	460.2	3" Dia.	463.3	24"Wx12"H	464.0	466.0
Future Phase	6	484.0	8'	479.0	482.5	90'	* SC250	478.5	35'-24" HDPE @ 1.43%	478.0	3" Dia.	479.3	–	–	482.0

* SC250 Liner – as manufactured by North American Green, Inc.
** Basins 4A and 4B outlet structures shall be 24" x 72" in-lieu-of standard 24"x48".

STORMWATER BASIN DETAIL


REVISIONS	DATE
1. Addressing Review Comments	8-3-2022
2. Addressing Review Comments	9-5-2022
3. Adding Veolia Water System Design to the plans	5-1-2023
4.	
5.	
6.	
7.	
8.	
9.	

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 PCSM-2.dwg 5/8/2023 1:46:23 PM EDT

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
717-566-6533 mellottengr@comcast.net

PCSM #3
POST CONSTRUCTION STORMWATER MANAGEMENT
CONSTRUCTION DETAILS
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022
Sheet No. PCSM #3
12 of 21



LEGEND

- Deciduous Tree
- Evergreen Tree
- Shrubs

Landscaping shall be provided with Autumn Chase PRD Phase 2 as indicated on this plan. Landscaping associated with this plan consists of the following:

Required Landscape Area	Buffer Type	Buffer Area (lf)			
			# of Trees Required		
SWM Area # 4A	3	215	Deciduous (per 30')	Evergreen (per 10')	Shrub (per 10')
			7	22	22
			# of Trees Proposed		
			Deciduous	Evergreen	Shrub
			5	0	4
		Difference	-2	-22	-18
			# of Trees Required		
SWM Area # 4B	3	425	Deciduous (per 30')	Evergreen (per 10')	Shrub (per 10')
			14	43	43
			# of Trees Proposed		
			Deciduous	Evergreen	Shrub
			2	11	17
		Difference	-12	-32	-26

Summary Required Landscape Screening			
	Required	Proposed	Difference
Deciduous	21	7	-14
Evergreen	64	11	-53
Shrub	64	21	-43
Total Screening	149	39	-110
Street Trees			
LF of ROW	Required (per 50')	Proposed	Difference
4910	98	87	-11
Additional Proposed Plantings			
	Required	Proposed	Difference
SWM 4A			
Evergreen	0	10	10
SWM 4B			
Evergreen	0	27	27
OS-6			
Evergreen	0	4	4
Shrub	0	24	24
Northern Property Line			
Evergreen	0	7	7
Entrances			
Evergreen	0	13	
Shrubs	0	49	32
Total Additional Plantings	0	134	134
Total Landscaping Summary			
	Required	Proposed	Difference
Deciduous	21	7	-14
Evergreen	64	59	-5
Shrub	64	94	30
Street Trees	98	87	-11
Total	247	247	0

LANDSCAPE NOTES

The Owner/Developer has the option to modify/change the landscaping and planting list, provided the landscaping proposed is reviewed and approved by Township.

Street trees are proposed which upon maturing will create a canopy effect.

All disturbed areas shall be stabilized. Refer to Erosion and Sediment Pollution Control Plan for temporary and permanent topsoil and seeding requirements, stabilization techniques and specifications.


Street trees shall be planted as not to interfere with utilities, roadways, clear sight triangles, sanitary sewer and storm water facilities.

SHORT TERM LANDSCAPE MAINTENANCE PLAN

1. The landscape contractor and/or developer/lot owners shall be responsible for watering landscaping material during and after installation.
2. Lawn areas shall be watered once weekly during dry periods of the first growing season to establish healthy grass. Watering should occur during the early part of the day to an even saturation depth of one inch.
3. Newly planted trees shall be watered regularly during the dry periods to completely saturate the root ball during the first growing season.
4. Disease, insect and weed control and prevention should be performed in accordance with manufacturer's recommendations.
5. Newly installed plantings shall be selectively pruned if necessary to provide a neat, uniform appearance. Any dead or broken branches shall be removed. All noticeably diseased or damaged plant material shall be removed and replaced prior to final acceptance.
6. All guying and staking shall be maintained regularly to assure plant stabilization and straight, uniform growth for at least the first year following the date of planting.
7. All plant material shall be true to species and variety and shall conform to measurements and minimum standards as set forth in the plant schedule.
8. All plant materials and lawn areas are to be guaranteed by the contractor for a period of one year from date of installation.


LONG TERM LANDSCAPE MAINTENANCE PLAN

1. Maintenance of trees, shrubs and grass on individual lots shall be the responsibility of the lot owner.
2. Maintenance of street trees located within a public right-of way or easement shall be the responsibility of the property owner whose property directly fronts that portion of right-of-way or easement.
3. Maintenance of all landscaping located in an Open Space Area and within the public right-of-way shall be the responsibility of the Homeowners Association.
4. The lot owner shall be responsible for regular mowing, clean-up, and grooming of all lawn and planted areas.




Note:
1. Street trees must be planted at an average of (2) trees every 100' and shall be placed a minimum of 40' apart along the street right-of-way and shall be located so as to maximize the growth potential of the plan material, minimize the potential for root interference with public infrastructure, and enhance the quality of the development. Street trees will be one of the species identified in Section 220-26.D.(7) of the Upper Allen Township Subdivision and Land Development Ordinance. (See plan for general layout).

DECIDUOUS STREET TREE PLANTING DETAIL
N.T.S.



NOTE:
1. In areas of mass planting, continuously excavate and mulch entire bed.

SHRUB PLANTING
N.T.S.



NOTE:
1. PLANT SHALL BEAR SAME RELATIONSHIP TO FINISHED GRADE AS IT DID IN ITS PREVIOUS LOCATION.
2. TIE TREE WRAP AT THE TOP AND BOTTOM AND AT 18" INTERVALS ALONG THE TRUNK.

PLANTING AND STAKING METHODS FOR EVERGREEN TREES
NO SCALE

DATE
8-3-2022
9-5-2022
5-1-2023

REVISIONS
1. Addressing Review Comments
2. Addressing Review Comments
3. Adding Veolia Water System Design to the plans


MELLOTT ENGINEERING, INC.
Civil Engineering · Land Planning & Development · Water Resources
7500 Devonshire Heights Road · Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

LANDSCAPE PLAN
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
13 of 21


M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 LS.dwg 4/28/2023 3:52:45 PM EDT



STREET LIGHT GENERAL NOTES

1. Street lighting is proposed throughout Phase II as shown on this plan. Street lights are proposed at all street intersections and at off street parking areas. The proposed street lighting is not intended to over light areas but to alert vehicular traffic of intersections.
2. Street lights shall be standard PPL fixtures and poles as conceptually shown on this plan.

1 inch = 60 ft.



DATE
8-2-2022
9-5-2022

REVISIONS
1. Addressing Review Comments
2. Addressing Review Comments
3.
4.
5.
6.
7.
8.
9.

M:\Drawings\2022\202202 Autumn Chase Phase II\202202 LT.dwg, 9/2/2022 2:46:50 PM, EDT

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
mellotteng@comcast.net
717-566-6533

LIGHTING PLAN

FOR


AUTUMN CHASE PRD – PHASE II

Land Developer: Hertzler Road Associates, L.P.

UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA


Project No. 202202
Date July 1, 2022

Sheet No.
14 of 21




Sidewalks shall be installed with 4' width excluding curb ramps and the proposed 5'x5' passing spaces.

PUBLIC MINOR STREET CROSS SECTION
NTS




BOULEVARD ENTRANCE CROSS SECTION
NTS

NOTES:
1. The above cross sections apply to all proposed streets (see plan view for boulevard entrance locations).
2. All construction methods and materials shall be in conformance with Township and Penn DOT Specifications for Roadway Construction, Pub. 408 (inlucding RC-, TC-, & TS- Standard Drawings).
3. No road construction activity shall be permitted in the Township of Upper Allen until and unless the contractor shall notify the Township at least one week in advance of commencing work. The contractor shall at all times during the progress of work have a competent superintendent or foreman on the job site. Inspection of road work shall be done by the Township or its designee.
4. Roadway subgrade shall be free of sod, vegetative matter, boulders, spongy soil or other unsuitable material. Where poor subsurface drainage conditions exist, adequate drainage facilities shall be installed.
5. The subgrade shall not be prepared during freezing weather or when frozen or when it is unstable due to excessive moisture.
6. All utility lines, under drains, sewer lines, including laterals and service lines, being placed in the roadway shall be installed prior to the commencement of road construction at the following minimum depths:
2. Gravity sewer lines: six feet.
3. Force main sewer: four feet below finish grade.
4. Waterlines: four feet.
5. Gas lines: 2 1/2 feet.
6. Telephone, electrical and television cable: two feet; not to be located within paved cartway.
7. Sewer and water lines shall have a minimum separation distance of 10 feet.
8. PA DEP and private utility regulations and procedures will prevail where applicable.
7. All backfill for utilities under existing roadways shall be 2A stone compacted to within 3% of the optimum material moisture content and placed in not greater than eight-inch lifts. The Township may require flowable fill or other alternate backfill material where conditions may warrant such measures.
8. All backfill for utilities under new roadways shall be suitable backfill material with no stones over four inches and no organic material, compacted to within 3% of the optimum material moisture content and placed in not greater than eight-inch lifts.
9. Preparation of road subgrade.
   (a) The subgrade shall be compacted and fine graded to not more than 0.2 foot below the grade as shown on the plan.
   (b) All soft, plastic (as determined by proof roll) or rock areas in the subgrade shall be undercut to a depth of at least 12 inches or more if deemed necessary by the Township Engineer and shall be refilled with approved materials and/or underdrained and/or reinforced with geotextile, as determined by the Township Engineer.
   (c) The subgrade shall conform to the same crown as the paved surface.
   (d) Prior to the placement of subbase or base course, the subgrade shall be proof-rolled with a fully loaded tandem axle dump truck. The proof rolling shall be observed by the Township Engineer. An acceptable proof roll shall be non-movement of the subgrade.
10. Preparation of road base.
   (a) The base course material shall consist of compacted PennDOT No. 2A subbase meeting the specifications of Pennsylvania Department of Transportation Publication 408, as amended, and shall be laid in the manner prescribed therein to the following thickness: 8" eight inches.
   (b) Pipe underdrain shall be provided in wet areas, in areas of roadway sag conditions, or any other areas as required by the Township Engineer.
11. Preparation of road surface. Roads shall be constructed from multiple courses of pavement materials, including a base course and a wearing course of hot-mixed, hot-laid asphaltic concrete. An additional binder course may be required on collector roads and industrial or commercial areas.
   (a) The base course shall consist of a minimum of five inches of compacted HMA Superpave base, P664-22, 37.5 mm mix, meeting the specifications of the Pennsylvania Department of Transportation Publication 408, as amended, and shall be laid in the manner prescribed therein. The base course shall be repaired if defects occurred prior to placement of wearing course. Where cracking or any other type of failure has occurred in the base course, the contractor shall completely remove the base course, stabilize the subgrade if necessary and construct new base course. Where the deficiency involves depressions or raveling in the surface of the base course, the repair may be made by skin patching with a suitable bituminous material.
   (b) The wearing course shall consist of a minimum of 1 1/2 inches of compacted HMA Superpave wearing course, P664-22, 9.5 mm mix, meeting the requirements of the Pennsylvania Department of Transportation Publication 408, as amended, and shall be laid in the manner prescribed therein. Where a wearing course is placed on an existing street, a minimum one-half-inch scratch course of compacted HMA Superpave wearing course, P664-22, 9.5 mm mix, shall be placed prior to the wearing course. The Township Engineer may require that the existing pavement be milled prior to placement of the scratch course.
   (c) The wearing course shall only be placed after sufficient time has passed to ensure that no further settling will take place. The wearing course shall only be placed after an inspection has determined no sags, low spots or depressions exist which could adversely affect the integrity of the wearing course. Any defects found shall be repaired prior to the placement of the wearing course. In the event of any deficiency in the wearing course such as raveling, depressions, cracking etc., such deficiencies shall be repaired by removing the wearing course and replacing with new material. Subject to said inspection, the wearing course shall be placed no later than the time when 90% of the lots have been issued a certificate of occupancy by the Township. A tack coat meeting the requirements of the Pennsylvania Department of Transportation Publication 408, as amended, shall be placed prior to paving with the wearing course.
   (d) Where required, the binder course shall consist of a minimum of 2.5 inches of HMA Superpave binder course, P664-22, 19.0 mm mix, meeting the requirements of the Pennsylvania Department of Transportation Publication 408, as amended, and shall be laid in the manner prescribed therein.




ISOMETRIC VIEW

This transition detail shall be applied to each side of the inlet.




PLAN VIEW



FRONT ELEVATION


Slant curb shall be installed for all proposed streets. Standard Type "C" Stormwater Inlets with an 8" hood (See Detail) shall be installed for all curbside street drainage collection. Use the above detail for the necessary curb transition to stormwater inlet boxs. The top of the curb and inlet hood shall be flush and will not require a vertical transition (provides a 3" sump at inlet, see pavement slope tranistion above for pavement transition to sumped inlet).

VERTICAL TO SLANT CURB TRANSITION DETAIL
NTS




SLANT CURB DETAIL
NTS

Sidewalks shall be installed with 4' width excluding curb ramps and the proposed 5'x5' passing spaces.



NOTES:
1. Sidewalks to be constructed in accordance with PA DOT Pub. 408.
2. Slabs to be poured in separate 30' lengths and shall be completely separated by 1" expansion joints.
3. Surface to be provided with broom finish.


CONCRETE SIDEWALK DETAIL
NTS



WIRE MESH SHIELD

Note:
1. Install underdrains where shown on the plan, where field conditions warrant, 50 feet in either direction of an inlet located in a sag vertical curve and as directed in the field by the Township.
2. The road subgrade and stone subbase are to be established prior to the placement of the underdrain.

PAVEMENT UNDERDRAIN DETAIL
NTS




Clear-sight triangle requirements at driveways:
1. No building or obstruction shall be permitted in this area that would obscure the vision of a motorist.
2. Grading and / or plantings (existing through mature growth) less than three (3) feet above the street grade are permitted in the clear-sight triangle.

DRIVEWAY CLEAR SIGHT TRIANGLE DETAIL
N.T.S.


Curb ramps shall be installed where sidewalk meets with a street/curbline. Curb Ramps shall be installed in accordance with current Commonwealth of Pennsylvania Department of Transportation Standards for Roadway Construction Publication 72M requirements. The curb ramps shall be installed in accordance with RC-67M Alternative Type 4A Curb Ramp (Perpendicluiar) dated February 19, 2021. Painted Crosswalks shall be installed at each ramp/road crossing in accordance with Publication 111 TC-8600 requirements (6' crosswalk width centered on crossing, 6" white lines). Stop sign and stop bar shall be installed 4' away from the crosswalks where applicable.

CURB RAMP-CROOSWALK REQUIREMENTS




NOTES:
1. Driveways shall be constructed in accordance with Township Subdivision and Land Development Ordinance Section 220-17, Zoning Ordinance Section 245-259.B. and Sections 02500 & 02525 of Construction and Materials Specifications manual requirements.
2. Sidewalks to be constructed in accordance with PA DOT Pub. 408. All concrete sidewalks shall have a minimum thickness of 4", except at driveways, where the sidewalks shall have a minimum thickness of 6" and shall be reinforced with WWF 6x6 – W2.9 x W2.9(6 ga.) wire meach placed 2" from top of surface.
3. Driveways shall be constructed with a concrete apron from the depressed curb to the proposed sidewalk. Driveway shall be bituminous pavement or concrete from the sidewalk to the unit/dwelling.

DRIVEWAY APRON DETAIL



ON SITE PATH TO GAZEBO
NTS



HERTZLER ROAD TRAIL/PATH
NTS

	DATE
1.	8-3-2022
2.	9-5-2022
3.	
4.	
5.	
6.	
7.	
8.	
9.	


REVISIONS
Addressing Township Comments
Addressing Review Comments


MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
mellottengr@comcast.net
717-566-6533

CONSTRUCTION DETAILS
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
15 of 21





NOTES:


1. SPECIAL LETTERED COVER PRODUCT NO. 00103664
2. REF. LOGO DWG. 00103665
3. EST. COVER WT. 150 LBS. (68 kg)
4. SPECIFIED MATERIAL: GRAY IRON
5. FURNISH FOUR (4) 1" DIA. HOLES IN COVER WHEN SPECIFIED (SEE VENTED COVER DETAIL)
6. √ DESIGNATES MACHINED SURFACE

FILE NAME: MH-1 - MH COVER SELF-SEALING.DWG

STANDARD DETAILS
HEAVY DUTY MANHOLE SELF-SEALING COVER
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/14	DWG. UPDATED
5/22	DWG. UPDATED

SCALE	DWG. NO.
NO SCALE	MH-1



NOTES (FRAME & COVER):


WATERTITE ASSEMBLY PRODUCT NO. 00104638	EST. WT. COVER–150 LBS (68kg) FRAME–156 LBS (71kg)
CATALOG NO. 1040APT, 1040ZSRT	UNIT–306 LBS (139kg)
REF. SALES DRAWING: 00104592, 00103665	MATL. SPEC. COVER – GRAY IRON ASTM A48 CL35B FRAME – GRAY IRON ASTM A48 CL35B

FILE NAME: MH-3-HD-FRAMECOVER-BOLTED.DWG

STANDARD DETAILS
HEAVY DUTY MANHOLE WATERTIGHT FRAME AND COVER
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED

SCALE	DWG. NO.
NO SCALE	MH-3



NOTES:


1. BOLTING OF MANHOLE FRAME AND COVER REQUIRED FOR ALL MANHOLES.
2. 3/4" DIA. STAINLESS STEEL EXPANSION ANCHOR BOLTS MAY BE USED IN PLACE OF THREADED STUDS AND INSERTS.
3. MANHOLE THREADED INSERT SPACING TO MATCH HOLE CENTER SPACING ON SPECIFIED FRAME AND COVER FOR EACH MANHOLE.
4. MANHOLE FRAME SHALL BE SET WITH DOUBLE APPLICATION OF PREFORMED PLASTIC GASKET SEALANT MATERIAL.
5. PIPES SHALL PROTRUDE MIN. 2" INSIDE MANHOLE WALL.
6. ANNULAR SPACE AROUND PIPES TO BE FILLED WITH NON–SHRINK CEMENT GROUT FLUSH WITH MANHOLE WALL.
7. FOR LENGTH OF PIPE CONNECTIONS TO MANHOLES, REFERENCE SPECIFICATION SECTION 02501.
8. REFERENCE SPECIFICATION SECTION 02501 FOR ANTI–FLOATATION REQUIREMENTS.
9. ALL STONE GRADATIONS ARE AASHTO CLASSIFICATION.

FILE NAME: MH-4-PRECASTCONC-1.dwg

STANDARD DETAILS
STANDARD PRECAST CONCRETE MANHOLE WITH PRECAST CONCRETE BASE
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
12/16	NOTE REVISIONS

SCALE	DWG. NO.
NO SCALE	MH-4



FILE NAME: MH-5-PRECASTCONC-2.DWG

STANDARD DETAILS
STANDARD PRECAST CONCRETE MANHOLE WITH PRECAST CONCRETE BASE
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
12/16	NOTE REVISIONS

SCALE	DWG. NO.
NO SCALE	MH-5

NOTES:

1. NO CEMENT GROUTING BETWEEN MANHOLE, LEVELING RINGS AND FRAME, OR ON INSIDE OR OUTSIDE OF MANHOLE PERMITTED. SEALING WITH APPLICATION OF HIGH BUILD EPOXY COATING PERMITTED (SIKA GUARD 62 OR APPROVED EQUAL).
2. RUBBER ADJUSTMENT RISERS PERMITTED FOR PAVED AREAS AND MAY BE TAPERED FOR STREET GRADE ADJUSTMENT.
3. 3/4" DIA. STAINLESS STEEL EXPANSION ANCHOR BOLTS MAY BE USED IN PLACE OF THREADED STUDS AND INSERTS.

FILE NAME: MH-9-LEV-RINGS-BOLTED-FRAME.DWG

STANDARD DETAILS
LEVELING RINGS AND BOLTED FRAME DETAILS
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
12/16	NOTE REVISIONS

SCALE	DWG. NO.
NO SCALE	MH-9

FILE NAME: MH-11-RISER-STEEP-SLOPE.DWG

STANDARD DETAILS
MANHOLE ADJUSTMENT RISERS FOR STREET GRADES OF 2% OR GREATER
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
11/08	RUBBER RISER REVISION
12/16	NOTE REVISIONS

SCALE	DWG. NO.
NO SCALE	MH-11

FILE NAME: MH-2-HC-H-25-FRAME.dwg

STANDARD DETAILS
HEAVY DUTY MANHOLE FRAME (H–25)
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED

SCALE	DWG. NO.
NO SCALE	MH-2

NOTE:

AFTER PIPE–TO–MANHOLE INSTALLATION, SEAL ANNULAR SPACE AROUND PIPE ON INSIDE OF MANHOLE WITH TYPE II NON–SHRINK CEMENT GROUT. (TYP. OF ALL CONNECTIONS).

FILE NAME: MH-13-PIPE_GASKETS-2.dwg

STANDARD DETAILS
MANHOLE PIPE GASKETS
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
1/17	DWG. UPDATED

SCALE	DWG. NO.
NO SCALE	MH-13

STANDARD DETAILS
MANHOLE SECTION JOINT SEAL
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED

SCALE	DWG. NO.
NO SCALE	MH-14

FILE NAME: MH-14-SEAL.DWG

DATE
8–5–2022
9–5–2022

REVISIONS
1. Addressing Review Comments
2. Addressing Review Comments


M:\Drawings\2022\202202 Autumn Chase Phase II\202202 STL SAN.dwg, 8/3/2022 10:56:01 PM, EST

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
717–566–6533
mellottengr@comcast.net

SANITARY SEWER CONSTRUCTION DETAILS
FOR
AUTUMN CHASE PRD – PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
16 of 21



Sanitary Sewer Main installation associated with Phase II construction consist of a sewer extension out of existing manhole LS11-31

SEWER INDEX MAP (Phases I - III)

Scale: 1" = 350'

Autumn Chase Phase II Sanitary Sewer Table


Manhole ID	Northing	Easting
LS11-31	309672.2855	2189747.0931
LS11-32	309672.1566	2189461.7567
LS11-33	309507.3258	2189440.5263
LS11-34	309469.1898	2189274.4912
LS11-35	309361.5765	2188893.4667
LS11-36	309401.1110	2188775.9746
LS11-37	309588.0820	2188834.0092
LS11-38	309628.6622	2188717.9413
LS11-39	309775.9343	2188582.9085
LS11-40	309855.9186	2188424.1479
LS11-41	309909.2713	2188203.9921
LS11-42	309884.9739	2188078.3796
LS11-43	309814.5205	2187985.2336
LS11-44	309557.8283	2187858.0314
LS11-46	309230.0665	2188662.1482

Autumn Chase Phase I Sanitary Sewer Table

Manhole ID	Northing	Easting
LS11-31	309671.2855	2189747.0931
LS11-30	309761.2851	2189747.3679
LS11-29	310237.9865	2189528.8256
LS11-28	310498.4435	2189767.0394
LS11-27	310500.9512	2189922.4286
LS11-26	310421.7006	2189998.7128
LS11-25	310288.0259	2190009.0481
LS11-19	310265.1728	2189208.2267
LS11-18	310229.9955	2189342.0434
LS11-12	310183.4472	2188933.9678
LS11-11	310009.1336	2189113.5309
LS11-10	310001.3764	2189333.9994
LS11-09	309987.3969	2189731.3118
LS11-08	310004.6310	2189829.5479
LS11-07	309897.1731	2189909.8983
LS11-06	309766.1648	2189916.1379
LS11-05	309781.4463	2190140.6930
LS11-04	309798.8039	2190298.7632
LS11-03	309830.7293	2190315.8047
LS11-02	309893.2210	2190650.1124
LS11-01	310138.5917	2190966.0131
LS02-04	310139.8939	2191097.8051

Autumn Chase Phase III Sanitary Sewer Table

Manhole ID	Northing	Easting
LS11-24	310843.2791	2188547.6443
LS11-23	310746.3736	2188923.5014
LS11-22	310705.7149	2189070.3850
LS11-21	310603.7094	2189146.3821
LS11-20	310390.5693	2189220.6744
LS11-17	310733.3898	2188414.1357
LS11-16	310566.9996	2188363.2161
LS11-15	310454.4677	2188430.5288
LS11-14	310400.5381	2188703.2339
LS11-13	310324.4619	2188830.6998



ELEVATION


NOTES:

1. 2-WAY CLEANOUT NOT TO BE LOCATED IN SIDEWALK OR BENEATH OTHER CURB LINE UTILITIES.
2. THERE SHALL BE A 10 FOOT HORIZONTAL SEPARATION BETWEEN THE WATER SERVICE AND THE SERVICE LATERAL/BUILDING SEWER.
3. 2-WAY CLEANOUT TO BE LOCATED ON TOWNSHIP R/W AND LOCATION TO BE SITE SPECIFIC WITH RESPECT TO CURB AND SIDEWALK.
4. WHERE 2-WAY CLEANOUT IS NOT REQUIRED, SERVICE CONNECTION SHALL BE EXTENDED TO THE RIGHTS-OF-WAY LINE AND PLUGGED.
5. DETECTION TAPE REQUIRED IN PIPE TRENCH AT A DEPTH OF NO MORE THAN 12-INCHES BELOW FINAL SURFACE GRADE OR PAVEMENT SUBGRADE.
6. 2-WAY CLEANOUTS MAY ALSO BE USED FOR TESTING AND OBSERVATION.

FILE NAME: LAT-2-DEEP.DWG

STANDARD DETAILS
SERVICE LATERAL – DEEP SEWER
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
1/17	DWG./NOTE REVISIONS
SCALE: NO SCALE	DWG. NO.: LAT-2




NOTES:

1. 2-WAY CLEANOUT NOT TO BE LOCATED IN SIDEWALK OR BENEATH OTHER CURB LINE UTILITIES.
2. THERE SHALL BE A 10 FOOT HORIZONTAL SEPARATION BETWEEN THE WATER SERVICE AND THE SERVICE LATERAL/BUILDING SEWER.
3. 2-WAY CLEANOUT TO BE LOCATED ON TOWNSHIP R/W LINE AND LOCATION TO BE SITE SPECIFIC WITH RESPECT TO CURB AND SIDEWALK.
4. WHERE 2-WAY CLEANOUT IS NOT REQUIRED, SERVICE CONNECTION SHALL BE EXTENDED TO THE RIGHTS-OF-WAY LINE AND PLUGGED.
5. DETECTION TAPE REQUIRED IN PIPE TRENCH AT A DEPTH OF NO MORE THAN 12-INCHES BELOW FINAL SURFACE GRADE OR PAVEMENT SUBGRADE.
6. 2-WAY CLEANOUTS MAY ALSO BE USED FOR TESTING AND OBSERVATION.

FILE NAME: LAT-1-SHALLOW.DWG

STANDARD DETAILS
SERVICE LATERAL – SHALLOW SEWER
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
1/17	DWG./NOTE REVISIONS
SCALE: NO SCALE	DWG. NO.: LAT-1




NOTES:

1. PIPE SIZES AND MATERIALS TO BE IN ACCORDANCE WITH TOWNSHIP REQUIREMENTS.
2. 2-WAY CLEANOUT (OBSERVATION TEE) TO BE LOCATED AT TOWNSHIP R/W LINE AND LOCATION TO BE SITE SPECIFIC WITH RESPECT TO CURB AND SIDEWALK.
3. FOR 4" BUILDING SEWER USE ECCENTRIC 4"x6" ADAPTER FITTING AT TRANSITION TO 2-WAY CLEANOUT (4"x6" FLEXIBLE COUPLING NOT ALLOWED).
4. CLEANOUT/TEST TEE SPACING IS 60' MAXIMUM, UNLESS OTHERWISE APPROVED IN WRITING BY TOWNSHIP.
5. WALL SLEEVE TO BE 2" GREATER THAN DIAMETER OF BUILDING SEWER PIPE AND SEALED WATER TIGHT.
6. ANY PIPE LESS THAN 3 FEET OF COVER SHALL BE APPROVED IN WRITING BY TOWNSHIP.
7. THERE SHALL BE A 10 FOOT HORIZONTAL SEPARATION BETWEEN WATER SERVICE AND SERVICE LATERAL/BUILDING SEWER, OR WATER SERVICE SHALL BE ENCASED IN A WATERTIGHT PVC CONDUIT SEALED AT BOTH ENDS WITH APPROPRIATE FERNCO ADAPTER.
8. INSTALL TEST PLUGS AS REQUIRED FOR ACCEPTANCE AIR TESTING.
9. TRAFFIC RATED PROTECTION CASTING REQUIRED IN PAVED AREAS ONLY.
10. DETECTION TAPE REQUIRED IN PIPE TRENCH AT A DEPTH OF 12-INCHES BELOW FINAL SURFACE GRADE OR PAVEMENT SUBGRADE.

SCALE: 1/4" = 1'-0"	DWG. CREATED: 8/08	DWG. UPDATED: 12/13	DWG. UPDATED: 1/17	DRAWN BY: BJM

FILE NAME: LAT-4 BUILDING SEWER.DWG




NOTES;

1. CASTING FRAME AND COVER SHALL BE HEAVY DUTY WITH "S" MARKING ON COVER. (EAST JORDAN IRON WORKS CATALOG No. 1565, OR APPROVED EQUAL.)

FILE NAME: LAT-8-CO-CAP.DWG

STANDARD DETAILS
CAP PROTECTION CASTING FOR CLEANOUT COVER IN VEHICULAR TRAFFIC AREAS
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
1/17	NOTE/TITLE REVISIONS
SCALE: NO SCALE	DWG. NO.: LAT-8




NOTE:

1. BACKFILL AND COMPACTION REQUIREMENT APPLIES TO PAVED ROADWAYS AND SHOULDERS OF PROPOSED AND EXISTING STREETS (OTHER THAN STATE HIGHWAYS), PAVED DRIVEWAYS, AND SIDEWALKS.

FILE NAME: TRENCH-1-PAVED.DWG

STANDARD DETAILS
TRENCH BACKFILL DETAIL IN PAVED AREAS
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
1/17	NOTE REVISIONS
SCALE: NO SCALE	DWG. NO.: TR-1




BACKFILLING REQUIREMENTS:

1. UNPAVED AREAS OUTSIDE ROADWAYS – SUITABLE ON-SITE BACKFILL COMPACTED AS INDICATED ABOVE TO BOTTOM OF TOPSOIL. REPLACE TOPSOIL TO APPROXIMATE DEPTH OF EXISTING OR MIN. 4".
2. UNPAVED AREAS WITHIN R/W LIMITS OF STATE HIGHWAYS – CONFORMING TO REQUIREMENTS OF PA DOT PUBLICATION 408.
3. UNPAVED SHOULDERS OF PROPOSED AND EXISTING STREETS OTHER THAN STATE HIGHWAYS – AGGREGATE BACKFILL COMPACTED AS INDICATED ABOVE.
4. STONE DRIVEWAYS AND PARKING AREAS – PA NO. 2A COARSE AGGREGATE BACKFILL COMPACTED AS INDICATED ABOVE.
5. UNIMPROVED STREETS – AGGREGATE BACKFILL COMPACTED AS INDICATED ABOVE.

FILE NAME: TRENCH-2-ROW.DWG

STANDARD DETAILS
TRENCH BACKFILL DETAIL IN UNPAVED AREAS
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
1/17	NOTE REVISIONS
SCALE: NO SCALE	DWG. NO.: TR-2




NOTES:

1. IF STABLE UNDISTURBED EARTH OR ROCK UNATTAINABLE, STABILIZATION METHOD TO BE DETERMINED BY ENGINEER.
2. DETECTION TAPE REQUIRED; REFERENCE APPROPRIATE TRENCH DETAIL.

FILE NAME: TRENCH-3-UNE.DWG

STANDARD DETAILS
UNSUITABLE MATERIAL EXCAVATION
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
12/13	DWG. UPDATED
SCALE: NO SCALE	DWG. NO.: TR-3



FILE NAME: TRENCH-7-CONC-ENCASEMENT.DWG

STANDARD DETAILS
CONCRETE ENCASEMENT DETAIL
UPPER ALLEN TOWNSHIP

DATE	REVISIONS
3/08	DWG. CREATED
SCALE: NO SCALE	DWG. NO.: TR-7

DATE
8-5-2022
9-5-2022

REVISIONS
Addressing Review Comments
Addressing Review Comments

M:\Projects\2022\202202 Autumn Chase Phase II\Drawings\202202 ETL SAN.dwg, 8/3/2022 2:57:54 PM, ETL


1. 2. 3. 4. 5. 6. 7. 8. 9.

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
717-566-6533 mellotteng@comcast.net

SANITARY SEWER CONSTRUCTION DETAILS
FOR
AUTUMN CHASE PRD – PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No.
17 of 21



DRAWING INDEX MAP
Scale: 1" = 750'

Location-NPDES Boundary Map
Scale: 1" = 1,200'

EROSION CONTROL PLAN INTENT NOTE

Autumn Chase is a partially constructed residential community consisting of a total of 317 proposed residential dwellings. This Plan shall address erosion control measures to be implemented with the Autumn Chase Project for all construction south of Hertzler Road (previous plan approvals were previously granted for Hertzler Road Improvements and Phases I & 3 located on the north side of Hertzler Road, 78 single–family dwelling lots). The construction on the south side of Hertzler Road consists of 239 dwelling units and associated infrastructure. Subdivision Plans shall be processed with the Township in several separate Phases although this erosion control plan set shall address all phases of construction with a single overall erosion control plan. While this erosion control plan shall address all earth disturbance proposed on the south side of Hertzler Road, the sequencing and associated construction shall be proposed in stages as detailed on these plans. The first stage (Stage 1) of construction shall address the initial earthwork and improvements associated with Autumn Chase Phase II, the second stage (Stage 2) shall address earthwork and improvements associated with Autumn Chase Phase V and the third stage (Stage 3) shall address all remaining phases. There are no DEP permits required for the proposed work detailed on these plans although a Water Obstruction and Encroachment Permit was obtained for the stream impacts associated with Hertzler Road improvements (Permit No. E21–468, issued on April 28, 2020.); see previously approved Erosion Control Plans for Phase I.

The E&S control BMPs associated with this plan consists of three sediment basins, one existing sediment trap, rock construction entrances, water bars, vegetated swales, riprap aprons, silt barriers and stabilization requirements. See below general description of each proposed E&S BMP:

Stabilized Rock Construction Entrances:
Rock construction entrances shall be installed at specific locations where construction equipment shall transition from stabilized areas to the disturbance areas, see plan and sequencing for installation timing and locations. All ingress & egress to the site shall be through a defined RCE.

Sediment Basins:
There are three Sediment Basins proposed with this plan; The basins shall provide treatment of sediment laden runoff prior to discharge.

Sediment Trap:
There is one existing temporary sediment trap previously installed with Phase I construction although the trap will be removed early in the construction sequence (referenced in this note for completeness).

Water Bars:
Water bars are proposed to direct sediment laden runoff to a proposed treatment BMP.

Vegetated Swales:
Vegetated swales are proposed for collection and conveyance of runoff.

Riprap Aprons:
Riprap aprons are proposed at all pipe discharges. Riprap aprons provide energy dissipation and returns runoff flow to a sheet flow condition.

Silt Barriers:
Silt barriers shall be installed down slope of all earth disturbances that do not drain to a sediment basin or trap. Silt barriers shall be compost filter socks. Silt barriers shall filter sediment laden runoff.

Stabilization:
All pervious disturbed areas shall be permanently stabilized with vegetated cover in accordance with the stabilization measures specified on the plan. All proposed slope 3 to 1 and graded shall be matted with NAG S75 matting or equivalent.

SOILS TABLE

SOIL SYMBOL	SOIL DESCRIPTION	SLOPE (%)	HYDROLOGIC GROUP	DEPTH TO WATER TABLE (FT)	SOIL REACTION (pH)	SUITABILITY FOR ROADFILL	SUITABILITY FOR TOPSOIL
BdB	Bedington Shaly Silt Loam	3 to 8%	B	5+	4.5–7.3	FAIR	POOR
BdC	Bedington Shaly Silt Loam	8 to 15%	B	5+	4.5–7.3	FAIR	POOR
BdD	Bedington Shaly Silt Loam	15 to 25%	B	5+	4.5–7.3	FAIR	POOR
BpB	Blairton silt loam	3 to 8%	C	½–3	4.5–5.5	POOR	POOR
BrB	Brinkerton silt loam	3 to 8%	D	0–½	4.5–5.5	POOR	POOR
DuB	Duffield silt loam	3 to 8%	B	5+	5.1–7.3	POOR	FAIR
EdB	Edom silt loam	3 to 8%	B	5+	5.1–7.8	POOR	POOR
EdC	Edom silt loam	8 to 15%	B	5+	5.1–7.8	POOR	POOR
HaA	Hagerstown shaly silt loam	0 to 3%	B	5+	4.5–7.3	POOR	POOR
HaB	Hagerstown shaly silt loam	3 to 8%	B	5+	4.5–7.3	POOR	POOR
Me	Melvin silt loam	0 to 2%	B/D	0–1	6.1–7.3	POOR	POOR
Pe	Penlaw silt loam	0 to 3%	C/D	½–1½	5.6–7.3	POOR	POOR

In general, the soils present should not pose any significant limitation to the type of development proposed. Reference the following recommendation pertaining to possible issues that may be encountered during construction.

- If unrippable rock is encountered during proposed grading, blasting or drilling may be required. Removed rock can be crushed if necessary and used for fill.
- If water table is encountered during excavation, dirty water shall be pumped out into a filter bag or sediment removal pond.
- The NRCS Soil Survey indicates some of the soils have a poor rating for use as road fill. The contractor should use only what soils are suitable for road fill and shall place and compact fill in accordance with standard practice. All road fill must meet Penn DOT Pub. 408 standards.
- Trap/Basin Core material shall be unified class CH or CL soil compacted to 98% of max dry density. Homogeneous embankment material to be compacted in 8" layers to a minimum final density of not less than 98% of max. Dry density within 2% of optimum moisture content. (ASTM Method D1557).
- If sinkhole is encountered during construction contractor and/or owner should immediately consult with a Geotechnical Engineer for guidance on proper sinkhole repair.

LEGEND

- SS18 — 18" COMPOST FILTER SOCK
- SS12 — 12" COMPOST FILTER SOCK
- LD — PROPOSED LIMIT OF DISTURBANCE
- RCE #1 — ROCK CONSTRUCTION ENTRANCE
- A1 — PROPOSED STORM SEWER, INLET
- A — PROPOSED END SECTION / ENDWALL W/ RIPRAP
- S — PROPOSED SANITARY SEWER, MANHOLE
- W — PROPOSED WATER LINE
- PROPOSED EDGE OF PAVE/CURB LINE
- PROPOSED STREET & PARKING PAVEMENT
- PROPOSED RIGHT-OF-WAY LINE
- PROPOSED PROPERTY LINE
- 475.0 — PROPOSED SPOT ELEVATION
- PROPOSED SWALE LINING
- 458 — PROPOSED 2' CONTOUR
- 456 — PROPOSED 2' TEMPORARY CONTOUR
- 396 — *Existing 2' Contour*
- *Existing Property Line*
- *Existing Adjoining Property*
- *Existing Right-of-way*
- *Existing Edge of Pave*
- I–1 — *Existing Storm Sewer, Inlet, ID#*
- BdC — SOIL TYPE AND BOUNDARY

GENERAL EROSION CONTROL NOTES

1. The existing NPDES Permit for the project is PAC210094. There is no other DEP permitting required for the proposed construction associated with this plan although Water obstruction and encroachment permitting was obtained for the Hertzler Road improvements (Hertzler Road improvements plan was previously approved with Phases 1 & 3 approvals, Water Obstruction Permit No. E21–468, issued on April 28, 2020.).
2. The entire project site is located within the Yellow Breeches Creek watershed (CWF).
3. Wetlands shown on this plan are per field delineation performed by Vortex Environmental, Inc.. No wetland impacts are proposed with this project.
4. BMPs, trees, debris and any other materials not proposed to permanently remain on–site are to be recycled or disposed of in accordance with Department of Environmental Protection regulations. All building materials and wastes must be removed from the site and recycled or disposed in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1 et seq., 271.1 et seq., and 287.1 et seq. No building material or wastes or unused building materials shall be buried, dumped, or discharged at the site.
5. Autumn Chase NPDES permittee and the Autumn Chase site contractor shall both become a copermittee to the Pennington NPDES permit prior to performing the offsite sanitary sewer extension within the Pennington community.

SEE FOLLOWING PLAN SHEET FOR STAGE 1 SEQUENCE NOTES

0 30 60
Scale: 1" = 60'

PENNSYLVANIA ONE CALL SYSTEM, INC. — STOP CALL BEFORE YOU DIG!

Before You Dig Anywhere
In . . . PENNSYLVANIA
STOP! Call 1–800–242–1776 Toll Free
PA Law requires 3 working days before you excavate
PA One Call System, Inc.
One Call Serial # : –

PENNSYLVANIA ACT 199 (2004) AS AMENDED REQUIRES NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN THE COMMONWEALTH.

DATE
8–5–2022
9–5–2022
5–1–2023

REVISIONS
1. Addressing Review Comments
2. Addressing Review Comments
3. Adding Veolia Water System Design to the plans
4.
5.
6.
7.
8.
9.

M:\Drawings\2022\202202 Autumn Chase Phase II\ES1.dwg, 5/1/2023 1:46:21 PM, EST

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
mellotteng@comcast.net
717–566–6533

ES1

EROSION AND SEDIMENTATION CONTROL PLAN
FOR
AUTUMN CHASE PRD – PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No. ES1
18 of 21

SEQUENCE OF CONSTRUCTION (Stage 1)

The following Sequence of Construction includes references to the proposed temporary erosion control measures and permanent stormwater BMPs; see the PCSM Plan sheets for the permanent BMPs.

- At least 7 days before starting any earth disturbance activities, the owner and/or operator shall invite all contractors involved in those activities, the landowner, all appropriate municipal officials (Township), the erosion and sediment control plan preparer, and a representative of the County Conservation District to an on-site pre-construction meeting.
- At least 3 days before starting any earth disturbance activities, all contractors involved in those activities shall notify the Pennsylvania One Call System Incorporated at 811 for the location of existing underground utilities.
- All earth disturbance activities shall proceed in accordance with the following sequence. Each stage shall be completed and immediately stabilized before any following stage is initiated. Clearing, grubbing and topsoil stripping shall be limited only to those areas described in each stage.
- Immediately upon discovering unforeseen circumstances posing the potential for accelerated erosion and/or sediment pollution, the operator shall implement appropriate best management practices (BMPs) to eliminate the potential for accelerated erosion and/or sediment pollution.
- If any fill material must be brought to the site, it must come from a site with an approved Erosion Control Plan and the contractor or developer must notify the County Conservation District and provide the appropriate information pertaining to the borrow site prior to start of hauling operations.
- All pumping of sediment laden water shall be through a sediment control BMP, such as a pumped water filter bag or equivalent sediment removal facility, over undisturbed vegetated areas.
- A suitable concrete washout facility must be provided for the cleaning of chutes, mixers, and hoppers of the delivery vehicles unless such a facility will be used at the source of the concrete. Under no circumstances may wash water from these vehicles be allowed to enter any surface waters.

1. Initial access to the site shall be via the existing gravel driveway off Hertzler across from N. Autumn Chase Drive (location of proposed S. Autumn Chase Drive entrance). Install construction fencing around the stormwater basin bottom areas to prevent compaction from construction equipment and at the wetland area (downslope of Basin 4A). Install stabilized rock construction entrance #1 (additional RCEs shall be installed later in the sequence). Ingress and egress to the site will be restricted to the construction entrances only.
2. Install all compost filter sock barriers. Some of the sock locations correspond with sock locations previously installed with Phase I construction; existing sock shall be inspected and replaced as needed.
3. Critical Stage of Construction. Install Sediment Basin 4A including permanent outlet structure, temporary riser attachment, plywood extension, barrel, riprap apron, baffles and cleanout stake (See Details). The outfall pipe shall be installed with a concrete cradle (no cradle required for existing pipe stub installed under the existing nature trail, cradle only required for the proposed basin outfall pipe extension). To minimize soil compaction of the subsoils below the basin bottom, basin excavation shall be performed from the sides of the basin to the extent possible once grading is within 2' of proposed finished grade. Any grading that cannot be performed from the sides of the basin(s) shall be performed with wide track equipment (no rubber tire equipment to be used in basin bottom areas due to concentrated loads that occur under the tires). See end of sequence notes for basin conversion and soil restoration/amendment notes.
4. Install Swale P2a (SW corner of Basin 4A); immediately stabilize swale (see detail).
5. Install Culvert A27, including concrete endwalls and riprap apron at discharge and riprap at the upstream endwall.
6. Install Swale P2; immediately stabilize swale (see detail).
7. Install Swale P1; immediately stabilize swale (see detail). Swale P1 collection shall protect the existing steep slope area along Hertzler Road. Swale P1 shall discharge into existing sediment trap T1 (trap discharge drains to sediment basin 4A).
8. After the above described perimeter erosion control measures are installed strip and stockpile topsoil as needed for areas to be regraded; stockpiles shall not exceed a maximum height of 35 feet and shall be no steeper than 2:1. Stockpiles to be stabilized accordingly. Perform grading and storm sewer installation out of Basin 4A up to proposed Basin 4B (endwall A1 up to Outlet structure 4B). Perform bulk grading. Grading shall be such as to maintain sediment laden runoff to the intended receiving sediment control BMP(s).
9. Stormwater Basin 4B shall be installed as a clean water basin with initial construction although the amended soils in the basin bottom shall not be installed until upslope areas are fully stabilized (basin 4B temporary bottom shall be at the proposed finished grade elevation although do not over excavate the basin bottom until future installation of amended soils mixture; see end of sequence notes). Basin 4B bottom shall be stabilized in accordance with permanent seeding specifications until future installation of amended soils (retentive basin seeding proposed with future amended soils installation).
10. Install temporary swale T1 from upstream limit of swale P2 followed by installation of permanent swale P3; immediately stabilize swales (see detail). Temporary swale T1 shall convey swale P3 flow around S. Fall Harvest Drive temporary cul-de-sac to swale P2 until future phase storm sewer installation.
11. Install storm sewer out of Basin 4B from endwall A10 up to endwall A24. Existing sediment trap T1 shall be removed during the above referenced storm sewer installation. Install riprap apron out pipe discharge and install R4 riprap at upstream endwall A24. Install rock construction #2. Install Water bar directly upslope of RCE #2 to direct runoff to the east.
12. Begin utilities installation.
13. Install Swale P4 after storm sewer is installed up to endwall A16.
14. Install conduit street crossings for electric and telecommunications. Install street curbing after utilities installation. Install stone subbase on streets as soon as possible to shield soil from erosion. Install out of street electric and telecommunication utilities.
15. Install rock construction entrances #3 and 4 off the limits of the temporary cul-de-sacs as shown.
16. Replace topsoil and permanently seed and mulch all non-paved areas where grading is complete. As disturbed areas within a project approach final grade, preparations should be made for seeding and mulching to begin (i.e. anticipate the completion date and schedule the seeder). In no case should an area exceeding 15,000 square feet, which is to be stabilized by vegetation, reach final grade without being seeded and mulched.
17. Begin building construction. Home builders shall implement Typical Individual On-Lot Erosion Controls to limit sediment from entering streets or abutting developed lots although no additional on lot measures are needed for disturbance areas that drain directly to a Sediment trap and/or basin.
18. The erosion control measures may not be removed until the entire upslope drainage area has a permanent stabilization. This occurs with a minimum uniform 70% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements. All paved areas must be paved or have a compacted stone base in place. Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operators shall contact the County Conservation District for an inspection prior to the removal of the erosion control BMP's.
19. After the Conservation District representative has inspected the site and agrees the site is stabilized the BMP's can be removed as follows:
    a. Critical Stage of Construction (Basin 4B amended soils): After all upslope contributing areas are permanently stabilized and after receiving authorization from a CCCD representative Stormwater Basin 4B amended soils installation can be performed (prior to conversion of Sed Basin 4A). Install 18" compost sock around outlet structure to provide for filtering during final stabilization process. Soil restoration and amendments of the Stormwater Basin bottom shall be provided at time of conversion. The basin bottom preparation consists of over excavating the basin bottom to 12" below finished grade, scarification/till the subgrade bottom (10" depth desired), smooth out bottom with light weight track equipment and place 12" of the amended soils mixture across basin bottom followed by stabilization with intended basin seed mixture and mulch.
    b. Critical Stage of Construction (Sed Basin 4A conversion): After all upslope contributing areas are permanently stabilized including full vegetation of upslope Stormwater Basin 4B and after receiving authorization from a CCCD representative Sediment Basin 4A can be converted to the permanent stormwater basin configuration. Install 18" compost sock around outlet structure to provide for filtering during final stabilization process. Remove temporary riser attachment and convert outlet structure to permanent condition. Install permanent emergency spillway and associated liner (spillway requires berm excavation as shown). Soil restoration and amendments of the Stormwater Basin bottom shall be provided at time of conversion. The basin bottom preparation consists of over excavating the basin bottoms to 12" below finished grade, scarification/till the subgrade bottom (10" depth desired), smooth out bottom with light weight track equipment and place 12" of the amended soils mixture across basin bottom followed by stabilization with intended basin seed mixture and mulch.
    c. Silt barriers can be removed.
    d. BMPs, trees, debris and any other materials not proposed to permanently remain on-site are to be recycled or disposed of in accordance with Department of Environmental Protection regulations. All building materials and wastes must be removed from the site and recycled or disposed in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1 et seq., 271.1 et seq., and 287.1 et seq. No building material or wastes or unused building materials shall be buried, dumped, or discharged at the site.

CRITICAL STAGES OF PLAN IMPLEMENTATION

This plan identifies the Post Construction Stormwater Management BMPs for the project. In accordance with NPDES permitting requirements, critical stages of implementation of the plan shall have a licensed professional or designee on site. The critical stages of construction associated with this project would be construction of the Bioretention-Detention Basin embankments and outlet structures, soil restoration of basin bottoms and verification of appropriate basin seeding. All other BMPs can be inspected after construction to verify consistency with the intended design.

UTILITY GENERAL NOTES

1. Public water service shall be provided to the project via water main extensions from the water main stubs installed with Phase I construction (stubs are located at the S. Fall Harvest and S. Autumn Chase Drive intersections with Hertzler Road.
2. Public sanitary sewer service shall be provided to the project via gravity sewer extensions. The northern portion of the site shall be served via extension from existing manhole LS11-31 previously installed with Autumn Chase Phase I and southern portion of the site (future phases) shall be served via an extension from the sewer system located within the Pennington Farms Community. All sewer construction to be in accordance with Township standards.
3. Electric and telecommunication utilities shall serve the project. These utility designs shall be performed by the applicable utility company after conditional plan approval.

STABILIZATION NOTES

1. Permanent stabilization is defined as a minimum uniform 70% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements.
2. Immediately after earth disturbance activities cease or temporary cessation preparations should be made for seeding and mulching to begin (i.e. anticipate the completion date and schedule the seeder). In no case should an area exceeding 15,000 square feet, which is to be stabilized by vegetation, reach final grade without being seeded and mulched. During non-germinating periods, mulch must be applied at the specified rates. Disturbed areas which are not at finished grade and which will be re-disturbed within 1 year must be stabilized in accordance with the temporary vegetative stabilization specifications. Disturbed areas which are at final grade or which will not be re-disturbed within 1 year must be stabilized in accordance with the intended permanent vegetative stabilization specifications.
3. An erosion control blanket will be installed on all disturbed slopes 3:1 or steeper, all areas of concentrated flows, all disturbance with 50' of Waters of the Commonwealth and all other areas specifically identified on the plans. N.A.G. S75 biodegradable matting shall be used for all general slope matting unless otherwise noted on the plans.
4. Soil restoration and amendments of the basin bottoms shall be provided at time of conversion to permanent stormwater basins. The basin bottom preparation consists of over excavating the basin bottoms to 12" below finished grade, scarification/till the subgrade bottom (10" depth desired), smooth out bottom with light weight track equipment and place 12" of the amended soils mixture across basin bottom followed by stabilization with intended basin seed mixture and mulch. The scarification/tilling of the subsoils is intended to enhance permeability of the subsoils and the amended soils will also promote infiltration and enhance vegetation growth
5. Replace all topsoil where construction is complete (4" to 8" depth). Prior to seeding, prepare surface by removal of rocks and unsuitable matter by hand raking or the use of a rock hound with light weight equipment. Stabilize with intended seed, straw and mulch per intended seeding specifications (See plan for type: grass, meadow, wetland mix and vegetated filter strip). Matting is required for all slopes 3:1 and steeper, see plan for locations).
6. Straw and hay mulch should be anchored immediately after application to prevent being windblown. A tractor-drawn implement may be used to "crimp" the straw or hay into the soil. This method is limited to slopes no steeper than 3:1. The machinery should be operated on the contour. (Note: Crimping of hay or straw by running over it with tracked machinery is not recommended.)
    A. Asphalt, either emulsified or cut-back, containing no solvents or other diluting agents toxic to plant or animal life, uniformly applied at the rate of 31 gallons per 1000 sy may be used to tack mulch.
    B. Synthetic Binders (chemical binders) may be used as recommended by the manufacturer to anchor mulch provided sufficient documentation is provided to show they are non-toxic to native plant and animal species.
    C. Wood mulch can be used over straw at a rate of 210 lb. per 1000 sy.
    D. Lightweight plastic, fiber, or paper nets may be stapled over the mulch to manufacturer's recommendations.
7. Tracking steep slopes (>25% or 4:1) may be utilized by running tracked machinery up and down the slope, leaving tread marks parallel to the contour. (Note: If a bulldozer is used, the blade shall be up.). Care should be exercised on soils having a clay content to avoid over-compaction. See notes above for permanent stabilization.

PERMANENT SEEDING

A. All disturbed soil not to be covered with impervious surfaces, riprap or landscaping mulch shall be permanently seeded to provide protection against the impact of precipitation, running water and wind.
B. Mulching shall be used to protect seeding and help in preventing runoff. Clean straw mulch shall be required in all disturbed areas and applied at a rate of 3 tons/acre (equivalent to 0.75" to 1" deep). Clean straw mulch should not be finely chopped nor broken during application.

Maintenance procedure:
1) Maintain a minimum 70% soil surface coverage with grass and/or mulch.
2) If a washout, slope failure or similar disturbance occurs, correct drainage problem if necessary, then reapply soil to the proper grade, reapply soil amendments, seed and mulch.

Permanent seeding schedule is as follows:
For gentle lawn areas
Species: 40% Kentucky Bluegrass
40% Pennlawn Creeping Red Fescue
20% Norlea Perennial Ryegrass

For Swales, steep slopes and wet areas: 100% Tall Fescue, varieties such as K-31, Altra, or other recently released dwarf variety
% Pure live seed: 98%
Application rate: 6 lbs./1000 sq. ft.
Fertilizer type: general purpose granular, 10-20-20
Fertilizer application rate: 1000 lbs per acre
Liming rate: Four (4) tons per acre of agricultural grade lime
Strawbale mulch rate: three (3) tons per acre
Seeding dates: Between 4/1 and 10/15


TEMPORARY SEEDING

The contractor shall temporarily stabilize any rough graded area, topsoil stockpile or unused excavated fill material. The grass will provide interim protection against the impact of precipitation, running water and wind.
Temporary seeding schedule is as follows:

Species: annual rye grass
% Live Seed: 98%
Application rate: 1 lbs./1000 sq. ft.
Fertilizer type: general purpose granular, 5-5-5
Fertilizer application rate: 1000 lbs per acre
Liming rate: one (1) ton per acre of agricultural grade lime
Strawbale mulch rate: three (3) tons per acre
Seeding dates: no seeding between 1/1 and 3/15

STANDARD EROSION & SEDIMENT CONTROL PLAN NOTES

1. A copy of the stamped approved drawings signed and dated by the Cumberland County Conservation District must be available at the project site at all times.
2. At least 7 days prior to starting any earth disturbance activities (including clearing and grubbing), the owner and/or operator shall invite all contractors, the landowner, appropriate municipal officials, the E&S Plan preparer, the post construction stormwater management plan preparer, and a representative from the Cumberland County Conservation District to an on-site preconstruction meeting.
3. At least 3 days prior to starting any earth disturbance activities, or expanding into an area previously unmarked, the Pennsylvania One Call System Inc. shall be notified at 1-800-242-1776 for the location of existing underground utilities.
4. All earth disturbance activities shall proceed in accordance with the sequence provided on the plan drawings. Deviation from that sequence must be approved in writing from the Cumberland County Conservation District or by DEP prior to implementation.
5. Clearing, grubbing, and topsoil stripping shall be limited to those areas described in each stage of the construction sequence. General site clearing, grubbing and topsoil stripping may not commence in any stage or phase of the project until the E&S BMPs specified by the Construction Sequence for that stage or phase has been installed and are functioning as described in this document.
6. At no time shall construction vehicles be allowed to enter areas outside the limit of disturbance boundaries shown on the plan maps. These areas must be clearly marked and fenced off before clearing and grubbing operations begin.
7. Stockpile heights must not exceed 35 feet. Stockpile slopes must be 2H:1V or flatter.
8. Immediately upon discovering unforeseen circumstances posing the potential for accelerated erosion and/or sediment pollution, the operator shall implement appropriate BMPs to minimize the potential for erosion and sediment pollution and notify the Cumberland County Conservation District and/or the regional office of DEP.
9. All building materials and wastes must be removed from the site and recycled or disposed of in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code Chapter 260, §§260.1 et seq., 271.1, and 287.1 et. seq. No building materials or wastes or unused building materials shall be burned, buried, dumped, or discharged at the site.
10. All off-site waste and borrow areas must have an E&S Plan approved by the Cumberland County Conservation District or DEP fully implemented prior to being activated.
11. The contractor is responsible for ensuring that any material brought on site is Clean Fill.
12. Form FP-001 must be retained by the property owner for any fill material affected by a spill or release of a regulated substance but qualifying as Clean Fill due to analytical testing. Clean Fill is defined as: Uncontaminated, non-water soluble, non-decomposable, inert, solid material. The term includes soil, rock, stone, dredged material, used asphalt, and brick, block or concrete from construction and demolition activities that is separate from other waste and is recognizable as such. The term does not include materials placed in or on the waters of the Commonwealth unless otherwise authorized. (The term "used asphalt" does not include milled asphalt or asphalt that has been processed for re-use.). Any placement of clean fill that has been affected by a spill or release of a regulated substance must use form FP-001 to certify the origin of the fill material and the results of the analytical testing to qualify the material as clean fill. Form FP-001 must be retained by the owner of the property receiving the fill. Environmental due diligence must be performed to determine if the fill materials associated with the project qualify as clean fill. Environmental due diligence is defined as: Investigative techniques, including, but not limited to, visual property inspections, electronic data base searches, review of property ownership, review of property use history, Sanborn maps, environmental questionnaires, transaction screens, analytical testing, environmental assessments or audits. Analytical testing is not a required part of due diligence unless visual inspection and/or review of the past land use of the property indicates that the fill may have been subjected to a spill or release of a regulated substance. If the fill may have been affected by a spill or release of a regulated substance, it must be tested to determine if it qualifies as clean fill. Testing should be performed in accordance with Appendix A of the Department's policy "Management of Clean Fill."
13. All pumping of water from any work area shall be done according to the procedure described in this plan, over undisturbed vegetated areas.
14. Until the site is stabilized, all E&S BMPs must be maintained properly. Maintenance must include inspections of all E&S BMPs after each runoff event and on a weekly basis. All preventative and remedial maintenance work, including clean out, repair, replacement, re-grading, reseeding, re-mulching and re-netting must be performed immediately. If E&S BMPs fail to perform as expected, replacement BMPs, or modifications of those installed will be required.
15. A written report showing dates that E&S BMPs were inspected as well as any deficiencies found and the date they were corrected shall be maintained on the site and be made available to regulatory agency officials at the time of inspection.
16. Sediment tracked onto any public roadway or sidewalk shall be returned to the construction site by the end of each work day and disposed in the manner described in this plan. In no case shall the sediment be washed, shoveled, or swept into any roadside ditch, storm sewer, or surface water.
17. All sediment removed from BMPs shall be disposed of in the manner described on the plan drawings.
18. Areas which are to be topsoiled shall be scarified to a minimum depth of 4 inches prior to placement of topsoil. Areas to be vegetated shall have a minimum 4 inches of topsoil in place prior to seeding and mulching. Fill outslopes shall have a minimum of 2 inches of topsoil.
19. All fills shall be compacted as required to reduce erosion, slippage, settlement, subsidence or other related problems. Fill intended to support buildings, structures and conduits, etc. shall be compacted in accordance with local requirements or codes.
20. Fill materials shall be free of frozen particles, brush, roots, sod, or other foreign or objectionable materials that would interfere with or prevent construction of satisfactory fills.
21. Frozen materials or soft, mucky, or highly compressible materials shall not be incorporated into fills.
22. Fill shall not be placed on saturated or frozen surfaces.
23. Seeps or springs encountered during construction shall be handled in accordance with the standard and specification for subsurface drain or other approved method.
24. All graded areas shall be permanently stabilized immediately upon reaching finished grade. Cut slopes in competent bedrock and rock fills need not be vegetated.
25. Immediately after earth disturbance activities cease in any area or subarea of the project, the operator shall stabilize all disturbed areas. During non-germinating months, mulch or protective blanketing shall be applied as described in the plan. Areas not at finished grade, which will be reactivated within 1 year, may be stabilized in accordance with the temporary stabilization specifications. Those areas which will not be reactivated within 1 year shall be stabilized in accordance with the permanent stabilization specifications.
26. Permanent stabilization is defined as a minimum uniform, perennial 70% vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated erosion. Cut and fill slopes shall be capable of resisting failure due to slumping, sliding, or other movements.
27. E&S BMPs must remain functional as such until all areas tributary to them are permanently stabilized or until they are replaced by another BMP approved by the Cumberland County Conservation District or DEP.
28. Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the Cumberland County Conservation District for an inspection prior to removal/conversion of the E&S BMPs.
29. After final site stabilization has been achieved, temporary E&S BMPs must be removed or converted to permanent post construction stormwater management BMPs. Areas disturbed during removal or conversion of the BMPs must be stabilized immediately. In order to ensure rapid revegetation of disturbed areas, such removal/conversions should be done only during the germinating season.
30. Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the Cumberland County Conservation District to schedule a final inspection.
31. Erosion control blanketing shall be installed on all slopes 3H:1V or steeper within 50 feet of a surface water and on all other disturbed areas specified on the plan maps and/or detail sheets.
32. Failure to correctly install E&S BMPs, failure to prevent sediment-laden runoff from leaving the construction site, or failure to take immediate corrective action to resolve failure of E&S BMPs may result in administrative, civil, and/or criminal penalties being instituted by the Pennsylvania Department of Environmental Protection as defined in Section 602 of the Pennsylvania Clean Streams Law. The Clean Streams Law provides for up to $10,000 per day in civil penalties, up to $10,000 in summary criminal penalties, and up to $25,000 in misdemeanor criminal penalties for each violation.
33. Concrete wash water shall be handled in the manner described on the plan drawings. In no case shall it be allowed to enter any surface waters or groundwater systems.
34. All channels shall be kept free of obstructions including but not limited to fill, rocks, leaves, woody debris, accumulated sediment, excess vegetation, and construction materia/wastes.
35. Underground utilities cutting through any active channel shall be immediately backfilled and the channel restored to its original cross-section and protective lining. Any base flow within the channel shall be conveyed past the work area in the manner described in this plan until such restoration is complete
36. Sediment basins and/or traps shall be kept free of all construction waste, wash water, and other debris having potential to clog the basin/trap outlet structures and/or pollute the surface waters.
37. Any damage that occurs in whole or in part as a result of basin or trap discharge shall be immediately repaired by the permittee in a permanent manner satisfactory to the municipality, Cumberland County Conservation District and the owner of the damaged property.
38. Erosion control blanketing shall be installed on all slopes 3H:1V or steeper within 50 feet of a surface water and on all other disturbed areas specified on the plan maps and/or detail sheets.
39. Fill material for embankments shall be free of roots, or other woody vegetation, organic material, large stones, and other objectionable materials. The embankment shall be compacted in maximum 8" layered lifts at 95% modified proctor per ASTM D1557.





DRAWING INDEX MAP
Scale: 1" = 750'

REVISIONS	DATE
1. Addressing Review Comments	8-5-2022
2. Addressing Review Comments	9-5-2022
3. Adding Veolia Water System Design to the plans	5-1-2023
4.	-
5.	-
6.	-
7.	-
8.	-
9.	-

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 ES2.dwg 5/7/2023 1:46:21 PM EDT


MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
717-566-6533
mellottengr@comcast.net

EROSION AND SEDIMENTATION CONTROL PLAN
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA


Project No. 202202
Date July 1, 2022

Sheet No. ES2
19 of 21

100' RCE length required to meet ABACT requirements



PROFILE



PLAN VIEW

* MOUNTABLE BERM USED TO PROVIDE PROPER COVER FOR PIPE

NOTES:

REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE.

RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.


MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.

STANDARD CONSTRUCTION DETAIL #3-1
ROCK CONSTRUCTION ENTRANCE

NOT TO SCALE

Compost Filter Sock to be installed around filter bag (ABACT)



NOTES:

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5% FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.


NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

PUMPED WATER FILTER BAG WITH COMPOST FILTER SOCK




PLAN VIEW

NOTES:

THE UPSLOPE DIVERSION CHANNEL SHOULD BE INSTALLED WHEREVER THE LOT EXTENDS MORE THAN 150 FEET ABOVE THE ROADWAY OR WHERE RUNOFF FORM AREAS ABOVE THE LOT IS NOT OTHERWISE DIVERTED AWAY FROM THE LOT. THE CHANNEL SHOULD BE PROPERLY SIZED AND PROVIDED WITH A SUITABLE PROTECTIVE LINING. THE DESIGNER AND/OR CONTRACTOR MUST EXERCISE CAUTION TO PROTECT ALL DOWNSTREAM PROPERTY OWNERS WHEN SELECTING A DISCHARGE POINT FOR THIS CHANNEL.

STANDARD CONSTRUCTION DETAIL #10-1
TYPICAL ON-LOT BMPs FOR LOT ABOVE ROADWAY

NOT TO SCALE




PLAN VIEW

NOTES:

THE AREA DOWNSLOPE OF THE COMPOST SOCK BARRIER MAY NOT BE UNDER DEVELOPMENT OR OTHERWISE DISTURBED.

STANDARD CONSTRUCTION DETAIL #10-2
TYPICAL ON-LOT BMPs FOR LOT BELOW ROADWAY

NOT TO SCALE



PLAN VIEW

NOTES:

THE AREA DOWNSLOPE OF THE COMPOST SOCK BARRIER MAY NOT BE UNDER DEVELOPMENT OR OTHERWISE DISTURBED.


THE UPSLOPE DIVERSION CHANNEL SHOULD BE INSTALLED WHEREVER RUNOFF FROM AREAS ABOVE THE LOT ARE NOT OTHERWISE DIVERTED AWAY FROM THE LOT. THE CHANNEL SHOULD BE PROPERLY SIZED AND PROVIDED WITH A SUITABLE PROTECTIVE LINING. THE DESIGNER AND/OR CONTRACTOR MUST EXERCISE CAUTION TO PROTECT ALL DOWNSTREAM PROPERTY OWNERS WHEN SELECTING A DISCHARGE POINT FOR THIS CHANNEL.

IN AREAS WHERE SLOPE IS AT AN OBLIQUE ANGLE TO THE ROADWAY, BMPS SHALL BE ADJUSTED ACCORDINGLY.

DIVERSION CHANNEL MAY OUTLET TO ROADSIDE DITCH OR STORM SEWER SYSTEM, BUT NOT ONTO STREET OR ROADWAY.

STANDARD CONSTRUCTION DETAIL #10-3
TYPICAL ON-LOT BMPs FOR LOT ALONG ASCENDING OR DESCENDING ROADWAY

NOT TO SCALE




NOTES:

1. THIS DETAIL IS A GENERAL REPAIR MEASURE FOR SINKHOLES. ALL ROCK SIZES AND DEPTHS ARE SUBJECT TO THE SIZE AND CONDITIONS OF THE SPECIFIC SINKHOLE. AS SUCH THE EXACT REPAIR FOR EACH SINKOLE ENCOUNTERED SHALL BE PER THE RECOMMENEDATION OF A GEOTECHNICAL ENGINEER. CONTRACTOR MUST COORDINATE WITH A GEOTECHNICAL ENGINEER TO OBTAIN INSTRUCTIONS ON PROPER REPAIR MEASURES TO IMPLEMENT.
2. REASONABLE EFFORTS SHOULD BE MADE TO EXCAVATE ALL LOOSE AND UNSTABLE SOILS FROM THE BASE OF THE SINKHOLE (I.E. THROAT)
3. FLOWABLE FILL,IF USED,SHOULD BE ALLOWED TO CURE FOR A MINIMUM OF 24 HOURS PRIOR TO THE PLACEMENT OF THE FOLLOWING LAYERS WITHIN THE INVERTED FILTER.
4. THE FINAL LAYER OF STRUCTURAL FILL SHOULD BE PLACED IN LOOSE 12" LIFTS AND COMPACTED TO A MINIMUM OF 95% OF THE SOIL'S MAXIMUM MODIFIED DRY DENSITY.
5. INSTALLATION OF THE INVERTED FILTER SHOULD BE COMPLETED UNDER THE DIRECTION OF THE GEOTECHNICAL ENGINEER..

The repairs outlined above are general guidelines and each sinkhole occurrence should thoroughly be reviewed by the Geotechnical Engineer of Record for an appropriate remediation plan.

INVERTED FILTER SINKHOLE REPAIR DETAIL


NO SCALE




INTERMITTENT CHECK SLOT

LONGITUDINAL ANCHOR TRENCH

PREPARE SOIL AND APPLY SEED BEFORE INSTALLING BLANKETS, MATS, OR OTHER TEMPORARY CHANNEL LINER SYSTEM.



ISOMETRIC VIEW



CHANNEL CROSS-SECTION

* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

	SWALE DESIGNATION	CHANNEL SLOPE (%)	Z1	Z2	BW (FT.)	D (MIN.) (FT.)	TW (MIN.) (FT.)	TEMPORARY LINING	PERMANENT LINING
Stage 1 (Phase II)	P1	8	3	3	4	1.1	10.6	N.A.G. C350	N.A.G. C350/CLASS D VEG.
	P2	2	3	3	3	2.0	15.0	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P2a	20	3	3	10	1.1	16.6	N.A.G. P300	N.A.G. P300/CLASS C VEG.
	P3	10	3	3	4	1.2	11.2	N.A.G. P550	N.A.G. P550/CLASS D VEG.
	P4	10	3	3	2	1.5	11	N.A.G. C350	N.A.G. C350/CLASS D VEG.
	*Ex. Hertzler	4	3	3	2	1.2	9.2	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	**T1	4	3	3	4	1.2	11.2	N.A.G. P300	N.A.G. P300/CLASS D VEG.
Stage 2 (Phase V)	P6	1.5	3	3	2	1.5	11	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P7a	1.5	3	3	4	2.5	19	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P7b	1.5	3	3	4	2.5	19	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P8	1-4	3	3	2	1.5	11	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P10	2.5	3	3	2	1.2	9.2	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P11	1.0	3	3	2	1.5	11	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
Stage 3 (Remaining Phases)	P5	3.3	3	3	2	1.1	8.6	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P9	1.2	3	3	2	1.0	8	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P12	1.5	3	3	2	1.5	11	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P13	1.2	3	3	2	1.5	11	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P14	1.4	3	3	2	1.5	11	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P15	11	3	3	2	1	8	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P16	1.2	3	3	2	1.5	11	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.
	P17	2	3	3	2	1.2	9.2	N.A.G. SC250	N.A.G. SC250/CLASS D VEG.

* Hertzler Road swale exist although data provided for reconstruction if needed in future.
** Temporary swale T1 shall receive swale P3 runoff until future phase construction
N.A.G. SC250 is a permanent vegetative lined, North American Green Product


NOTES:

ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL ANCHOR TRENCHES. CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED.

CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION. SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.

NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

STANDARD CONSTRUCTION DETAIL #6-1
VEGETATED CHANNEL



Outlet No.	Pipe Dia. Do (in)	Tail Water Condition (Max/Min)	Man. "n" For Pipe	Pipe Slope (%)	*Q (cfs)	**V (fps)	Riprap Size	Rt (in)	Al (ft)	Alw (ft)	Atw (ft)
A1	30	Min	0.012	2.50	41.5	9.2	R-5	27	23	7.5	30.5
A10	24	Min	0.012	2.00	32.4	11.2	R-5	27	16	6	22
***A27	42	Min	0.012	1.00	57	11.3	R-5	27	22	10.5	32.5
A25	18	Min	0.012	1.00	7.3	8.0	R-4	18	8	4.5	12.5
A32	18	Min	0.012	0.83	6.2	6.1	R-4	18	8	4.5	12.5
A34	36	Min	0.012	1.00	39.5	8.4	R-5	27	20	9	29
A51	18	Min	0.012	2.50	12.9	8.4	R-4	18	12	4.5	16.5
*****6	24	Min	0.012	1.43	10.0	8.4	R-4	18	12	6	18
*****1	36	Min	0.012	1.00	47	10.9	R-5	27	20	9	29
*****1	30	Min	0.012	1.00	37	10.1	R-5	27	16	7.5	23.5
B1	24	Min	0.012	3.67	25.4	8.4	R-5	27	16	6	22
B8	36	Min	0.012	0.90	58.3	9.5	R-5	27	21	9	30
B39	15	Min	0.012	2.56	4.6	6.9	R-4	18	8	3.75	11.75
C1	24	Min	0.012	3.08	33.7	10.4	R-5	27	20	6	26

* 100 Year storm event
** The anticipated velocity (V) should not exceed the maximum permissible shown in Table 6.6 for the proposed riprap protection. Adjust for less than full pipe flow. Use Manning's equation to calculate velocity for pipe slopes > 0.05 ft/ft.
***A27 apron includes flow from A29 as well; discharge to same conservatively designed apron.
***** F1 & J1 aprons exist. Original design reflected above; new received reduced basin discharges. Designs for future phase "B & C" systems shall be provided with future phase submission.
******6 – Basin 6 discharge was conservatively assumed to be 10 cfs while actual is less.
All pipe end treatments shall be Concrete End Wall (RC-31M)

NOTES:

ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS.

ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.

STANDARD CONSTRUCTION DETAIL #9-1
RIPRAP APRON AT PIPE OUTLET
WITH FLARED END SECTION OR ENDWALL

Compost Filter Sock

SECTION

PLAN VIEW

NOTES:

SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.
COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.
TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS.
ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.
COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.
BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

STANDARD CONSTRUCTION DETAIL #4-1
COMPOST FILTER SOCK

NOT TO SCALE

NOTES:
1. INSTALL ON FLAT GRADE FOR OPTIMUM PERFORMACE (2% MAX)
2. 18" DIAMETER FILTER SOCK CAN BE STACKED ONTO DOUBLE 24" DIAMTER SOCKS IN PYRAMIDAL CONFIGURATION FOR ADDED HEIGHT.

A suitable concrete washout facility must be provided for the cleaning of chutes, mixers, and hoppers of the delivery vehicles unless such a facility will be used at the source of the concrete. Under no circumstances may wash water from these vehicles be allowed to enter any surface waters. Make sure that proper signage is provided to drivers so that they are aware of the presence of washout facilities.

Washout facilities should not be placed within 50 feet of storm drains, open ditches or surface waters. They should be in a convenient location for the trucks, preferably near the place where the concrete is being poured, but far enough from other vehicular traffic to minimize the potential for accidental damage or spills. Wherever possible, they should be located on slopes not exceeding a 2% grade.

Compost Sock Washout
Wherever compost sock washouts are used, a suitable impervious geomembrane should be placed at the location of the washout. Compost socks should be staked in the manner recommended by the manufacturer around perimeter of the geomembrane so as to form a ring with the ends of the sock located at the upslope corner (See Detail). Care should be taken to ensure continuous contact of the sock with the geomembrane at all locations. Where necessary, socks may be stacked and staked so as to form a triangular cross-section.

CONCRETE WASHOUT DETAIL

NOT TO SCALE

SECTION VIEW

NOTES:

WATERBARS SHALL DISCHARGE TO A STABLE AREA.

WATERBARS SHALL BE INSPECTED WEEKLY (DAILY ON ACTIVE ROADS) AND AFTER EACH RUNOFF EVENT. DAMAGED OR ERODED WATERBARS SHALL BE RESTORED TO ORIGINAL DIMENSIONS WITHIN 24 HOURS OF INSPECTION.


MAINTENANCE OF WATERBARS SHALL BE PROVIDED UNTIL ROADWAY, SKIDTRAIL, OR RIGHT-OF-WAY HAS ACHIEVED PERMANENT STABILIZATION.

WATERBARS ON RETIRED ROADWAYS, SKIDTRAILS, AND RIGHT-OF-WAYS SHALL BE LEFT IN PLACE AFTER PERMANENT STABILIZATION HAS BEEN ACHIEVED.

SEE PA DEP EROSION CONTROL MANUAL TABLE 3.1 FOR WATERBAR SPACING.

STANDARD CONSTRUCTION DETAIL #3-5
WATERBAR

NOT TO SCALE



NOTES:

1. SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET.
2. PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.
3. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS.
4. BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.
5. THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
6. BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

STANDARD CONSTRUCTION DETAIL #11-1
EROSION CONTROL BLANKET INSTALLATION

NOT TO SCALE

DATE
8-5-2022
9-5-2022
5-1-2023

REVISIONS
1. Addressing Review Comments
2. Addressing Review Comments
3. Adding Veolia Water System Design to the plans
4.
5.
6.
7.
8.
9.

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 ES1.dwg, 5/7/2023 2:06:29 PM, EDT


MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road Hummelstown, PA 17036
mellottengr@comcast.net
717-566-6533

ES3

EROSION AND SEDIMENTATION CONTROL PLAN
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA


Project No. 202202
Date July 1, 2022


Sheet No. ES3
20 of 21



NOTE:
IF SEDIMENT REACHES CLEANOUT LEVEL, REMOVE SEDIMENT AND PLACE ON TOPSOIL STOCKPILE. RESTORE BASIN TO ORIGINAL DIMENSIONS.

SEDIMENT CLEANOUT STAKE DETAIL





INSTALLATION INSTRUCTIONS:
APPLY TAR OR MASTIC TO COLLAR AND LAY PIPE ON COLLAR. APPLY MASTIC TO TOP HALF OF COLLAR AND SET IN PLACE LINING UP RED STRIPES AND BOLT TWO HALVES TOGETHER. INSTALL METAL BANDS ON SPLIT HALVES OF COLLAR. TIGHTEN BOLTS AND BANDS. APPLY MASTIC AS NEEDED TO INSURE GOOD WATERTIGHT SEAL. BACKFILL AND TAMP ACCORDINGLY. ABOVE PRODUCT CAN BE PURCHASED FROM SCHEIB PRODUCTS (660-446-2343); EQUIVALENT PRODUCT CAN BE USED.

	BASIN OUTLET	# COLLARS	W (ft)
Stage 1 (Phase II)	4A	3	6
Stage 1 (Phase II)	4B	2	5
Stage 2 (Phase 5)	5	2	6
Stage 3	6	2	5

Basin 4B collar design is shown for reference although; Basin 4B is not a sediment control facility

GENERAL NOTES
1. INSTALL COLLARS ON BOTH SIDES OF EMBANKMENT CORE.
2. ANTI-SEEP COLLAR AND CONNECTION TO THE PIPE (BARREL) MUST BE WATERTIGHT.
3. COLLARS SHOULD NOT BE LOCATED CLOSER THAN 2 FEET TO A PIPE JOINT.

ANTI-SEEP COLLAR DETAIL


N.T.S.

BASIN NO.	COE (FT)	TEMP CREST ELEV TRCE (FT)	PERM CREST ELEV PRCE (FT)	PLYWOOD BOX CREST ELEV PRCE (FT)	TEMP FABRICATED RISER HEIGHT H (FT)	TEMP FABRICATED RISER WIDTH W (FT)	TEMP FABRICATED RISER DEPTH D (FT)	PERFORATIONS NO. HOLES PER ROW	PERFORATIONS NO. OF ROWS	PERFORATIONS VERTICAL SPACING OF ROWS (FT)
4A	459.1	462.5	463.5	465.2	*5	1.5	0.5	10	5	1.2
5	464.0	NA	466.0	NA	**2.5	1.5	0.5	14	3	.67
6	480.0	NA	482.0	NA	**2.5	1.5	0.5	4	4	0.5


* Basin 4A temp riser attachment shall be installed from elevation 457.5 (bottom) to top of outlet structure without the 12" top slab (TRCE elv). The first two rows of holes shall be installed in the fabricted riser attachment and the final two rows shall be installed in the plywood extension. The riser attachment is installed to 457.5 as to be below the basins low flow orfice (allows for basin to dewater through the holes as intended). # of holes per rule of thumb method.
** Basins 5 & 6 fabricated risers shall accomodate dewatering holes extending from the cleanout elevation to top of box (fabricated box height to be such to allow for holes at cleanout level).

SEDIMENT BASIN TEMPORARY RISER BOX

N.T.S.



SECTION VIEW



BASIN OR TRAP NO.	BAFFLE LENGTH Bal (FT)	BAFFLE HEIGHT Bah (FT)	OUTLET CREST ELEV. TRCE (FT)	BOTTOM ELEV BE (FT)
4A	140	7.7	465.2	457.5
	140	7.7		
5	110	3	466.0	463.0
6	125	3	482.0	479.0

BASIN/ TRAP NO.	Z1 (FT)	Z2 (FT)	FABRICATED RISER HEIGHT H (FT)	FABRICATED RISER WIDTH W (FT)	FABRICATED RISER DEPTH D (FT)	FABRICATED RISER ELEV. SRE (FT)	PERF. ELEV CDE (FT)	STORM SEWER INVERT ELEV. SSIE (FT)	INLET CREST ELEV. ICE (FT)	EMBANK. TOP ELEV. ETE (FT)	BOTTOM ELEV. BE (FT)
4A	3	3	×	×	×	×	459.1	455.8	465.2	467.0	457.5
5	3	3	×	×	×	×	464.0	460.8	466.0	468.0	463.0
6	3	3	×	×	×	×	480.0	478.5	482.0	484.0	479.0

* See above standalone Sediment Basin Temporary Riser Box.

BASIN/ TRAP NO.	EMBANKMENT TOP ELEV ETE (FT)	EMBANKMENT TOP WIDTH ETw (FT)	EMBANKMENT KEY TRENCH DEPTH KD (FT)	EMBANKMENT KEY TRENCH WIDTH KW (FT)	CLEANOUT ELEV CDE (FT)	BOTTOM ELEV BE (FT)	BARREL DIA Bd (IN)	BARREL INLET ELEV BIE (FT)	BARREL MAT'L	BARREL LENGTH BL (FT)	OUTLET ELEV BOE (FT)
4A	467.0	8	2	4	459.1	457.5	36	455.8	HDPE	80	455.0
5	468.0	8	2	4	464.0	463.0	30	460.8	HDPE	60	460.2
6	484.0	8	2	4	480.0	479.0	24	478.5	HDPE	35	478.0

NOTES:
SEDIMENT BASINS, INCLUDING ALL APPURTENANT WORKS, SHALL BE CONSTRUCTED TO THE DETAIL AND DIMENSIONS SHOWN ON THE E&S PLAN DRAWINGS.

AREA UNDER EMBANKMENT SHALL BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO A DEPTH OF TWO FEET PRIOR TO ANY PLACEMENT AND COMPACTION OF EARTHEN FILL. FILL MATERIAL FOR THE EMBANKMENTS SHALL BE FREE OF ROOTS, OR OTHER WOODY VEGETATION, ORGANIC MATERIAL, LARGE STONES, AND OTHER OBJECTIONABLE MATERIALS. THE EMBANKMENT SHALL BE COMPACTED IN LAYERED LIFTS OF NOT MORE THAN 6 TO 9 IN. THE MAXIMUM ROCK SIZE SHALL BE NO GREATER THAN 2/3 THE LIFT THICKNESS. UPON COMPLETION, THE EMBANKMENT SHALL BE SEEDED AND MULCHED OR OTHERWISE STABILIZED ACCORDING TO THE SPECIFICATIONS OF THE E&S PLAN DRAWINGS. TREES SHALL NOT BE PLANTED ON THE EMBANKMENT.

ACCESS SHALL BE PROVIDED FOR SEDIMENT REMOVAL AND OTHER REQUIRED MAINTENANCE ACTIVITIES.

A CLEAN OUT STAKE SHALL BE PLACED NEAR THE CENTER OF EACH BASIN. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED THE CLEAN OUT ELEVATION ON THE STAKE AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS. DISPOSE OF MATERIALS REMOVED FROM THE BASIN IN THE MANNER DESCRIBED IN THE E&S PLAN.

INSPECT ALL SEDIMENT BASINS ON AT LEAST A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. CHECK BASIN EMBANKMENTS, SPILLWAYS, AND OUTLETS FOR EROSION, PIPING AND SETTLEMENT. NECESSARY REPAIRS SHALL BE MADE IMMEDIATELY. DISPLACED RIPRAP WITHIN THE OUTLET ENERGY DISSIPATER SHALL BE REPLACED IMMEDIATELY. ACCUMULATED SEDIMENT SHALL BE REMOVED AND DISTURBED AREAS SHALL BE STABILIZED INSIDE THE BASIN BEFORE CONVERSION TO A STORMWATER MANAGEMENT FACILITY. THE DEVICE SHOWN IN STANDARD CONSTRUCTION DETAIL #7-16 MAY BE USED TO DEWATER SATURATED SEDIMENT PRIOR TO ITS REMOVAL. ROCK FILTERS SHALL BE ADDED AS NECESSARY.

STANDARD CONSTRUCTION DETAIL #7-6 & #8-7
TYPE M INLET SEDIMENT BASIN-TRAP &
SEDIMENT BASIN EMBANKMENT AND SPILLWAY DETAILS

NOT TO SCALE

NOTES:
SEE APPROPRIATE BASIN DETAIL FOR PROPER LOCATION AND ORIENTATION.

AN ACCEPTABLE ALTERNATIVE IS TO INSTALL A SUPER SILT FENCE AT THE BAFFLE LOCATION

IN POOLS WITH DEPTHS EXCEEDING 7', THE TOP OF THE PLYWOOD BAFFLE DOES NOT NEED TO EXTEND TO THE TEMPORARY RISER CREST. SUPER SILT FENCE BAFFLES NEED NOT EXTEND TO TRCE ELEVATION.

BAFFLES SHALL BE TIED INTO ONE SIDE OF THE BASIN UNLESS OTHERWISE SHOWN ON THE PLAN DRAWINGS.


SUBSTITUTION OF MATERIALS NOT SPECIFIED IN THIS DETAIL SHALL BE APPROVED BY THE DEPARTMENT OR THE LOCAL CONSERVATION DISTRICT BEFORE INSTALLATION.

DAMAGED OR WARPED BAFFLES SHALL BE REPLACED WITHIN 7 DAYS OF INSPECTION.

BAFFLES REQUIRING SUPPORT POSTS SHALL NOT BE INSTALLED IN BASINS REQUIRING IMPERVIOUS LINERS.

STANDARD CONSTRUCTION DETAIL #7-14
BAFFLE

NOT TO SCALE



EMBANKMENT SECTION ALONG EMERGENCY SPILLWAY SECTION X-X
RIPRAP OUTLET DISSIPATOR

BASIN NO.	WEIR Z3 (FT)	WEIR Z4 (FT)	WEIR TOP ELEV WTE (FT)	WEIR CREST ELEV WCE (FT)	WEIR WIDTH Ww (FT)	LINING TRM TYPE	LINING STAPLE PATTERN	CHANNEL Z5 (FT)	CHANNEL DEPTH Cd (FT)	DISSIPATOR LENGTH DI (FT)	DISSIPATOR WIDTH Dw (FT)	DISSIPATOR RIPRAP SIZE (R-__)	DISSIPATOR RIPRAP THICK. DR't (IN)
4A	3	3	467.0	466.0	360	** NA	Per Man	3	0.5	NA	NA	NA	NA
5	3	3	468.0	466.5	220	*SC250	Per Man	3	0.5	NA	NA	NA	NA
6	3	3	484.0	482.5	90	*SC250	Per Man	3	0.5	NA	NA	NA	NA

*SC250 = permanent SC250 liner as Manufactures by North American Green — liner with vegetation
** Emergency spillway not used in design; all flow through principal structure.

NOTES:
HEAVY EQUIPMENT SHALL NOT CROSS OVER SPILLWAY WITHOUT PRECAUTIONS TAKEN TO PROTECT TRM LINING.

DISPLACED LINER WITHIN THE SPILLWAY AND/OR OUTLET CHANNEL SHALL BE REPLACED IMMEDIATELY.

RIPRAP AT TOE OF EMBANKMENT SHALL BE EXTENDED A SUFFICIENT LENGTH IN BOTH DIRECTIONS TO PREVENT SCOUR.


THE USE OF BAFFLES THAT REQUIRE SUPPORT POSTS ARE RESTRICTED FROM USE IN BASINS REQUIRING IMPERVIOUS LINERS.

STANDARD CONSTRUCTION DETAIL #7-13
SEDIMENT BASIN EMERGENCY SPILLWAY WITH TRM LINING


NOT TO SCALE

ALL SEDIMENT BASIN OUTFALL PIPES SHALL BE CONSTRUCTED WITH A CONCRETE CRADLE. ALL BASINS BERMS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD CONSTRUCTION DETAIL #7-6 INCLUDING ANTI-SEEP COLLARS INSTALLED IN BERM CORE. NO CRADLE NEEDED FOR PORTIONS OF OUTFALL PIPES PREVIOUSLY INSTALLED WITH TRAIL INSTALLATION.

ANTI-SEEP COLLARS TO BE INSTALLED PER DETAIL. NO FILTER DIAPHRAGM PROPOSED.



EMBANKMENT ALONG PRINCIPAL SPILLWAY



CROSS-SECTION AT OUTLET BARREL

NOTES:
A CONCRETE CRADLE SHALL BE USED IN CONJUNCTION WITH ANTI-SEEP COLLARS.
ANTI-SEEP COLLAR NUMBER, SIZE AND SPACING SHALL BE AS SHOWN ELSEWHERE IN PLAN.
* NO FILTER DIAPHRAGM IS PROPOSED.

STANDARD CONSTRUCTION DETAIL #7-17
CONCRETE CRADLE FOR BASIN OR TRAP OUTLET BARREL

NOT TO SCALE

DATE
8-3-2022
9-5-2022
5-1-2023

REVISIONS
1. Addressing Comments
2. Addressing Review Comments
3. Adding Veolia Water System Design to the plans
4.
5.
6.
7.
8.
9.

M:\Drawings\2022\202202 Autumn Chase Phase 2\202202 ETL-ES.dwg, 5/7/2023 2:31:04 PM, EDT

MELLOTT ENGINEERING, INC.
Civil Engineering • Land Planning & Development • Water Resources
7500 Devonshire Heights Road • Hummelstown, PA 17036
717-566-6533
mellotteng@comcast.net

ES4

EROSION AND SEDIMENTATION CONTROL PLAN
FOR
AUTUMN CHASE PRD - PHASE II
Land Developer: Hertzler Road Associates, L.P.
UPPER ALLEN TOWNSHIP CUMBERLAND COUNTY PENNSYLVANIA

Project No. 202202
Date July 1, 2022

Sheet No. ES4
21 of 21